

# Test Beam Plan of JLab GEM Tracker (June-July 2011)


E. Cisbani

INFN-Rome Sanità Group

RD51 Collaboration Meeting – 13-15 April 2011 - CERN


# SBS Spectrometer in Hall A

- Large luminosity
- Moderate acceptance
- Forward angles
- Reconfigurable detectors




- Electronics for:
- Small silicon detector (SiD)
  - Front GEM tracker
  - Large backward GEM trackers
- ⇒ **>100k channels**


# SBS Tracker Chambers configuration



GEP(5) SBS




- ✓ 40x50 cm<sup>2</sup> modules are composed to form larger chambers with different sizes
- ✓ Electronics along the borders and behind the frame (at 90°) – cyan and blue in drawing
- ✓ Front Tracker operates in Magnetic Fringe Field up to 200 Gauss




# Electronics Components

GEM ⇒ FEC ⇒ ADC+VME Controller ⇒ DAQ



Up to 10m  
twisted,  
shielded  
copper  
cable




Main features:

- Use analog readout APV25 chips
- 2 active components: Front-End card and VME64x custom module
- Copper cables between front-end and VME

# Prototype to be tested

- Fully equipped  
3xGEM 40x50 cm<sup>2</sup>  
module
- 2D readout, 400  $\mu$ m  
strip pitch
- 18 front-end APV25  
cards (2304  
channels)
- Gas: Ar/CO<sub>2</sub> 70/30



Front End Cards on the other side of the backplanes


# Beam test @ DESY (EUNET support)



# Purpose of the Test


- Characterize the 40x50 cm<sup>2</sup> 3xGEM module prototype in terms of:
  - Cluster width and displacement
  - Collected charge
  - Efficiency
  - Residuals
- Study in Magnetic Field up to 500 Gauss
- Study at highest intensity beam (?)
- Further characterization of the APV25 based electronics (field effects, noise ...)

# Verify assumption at low field





# Setup



Detector Under Tests: 40x50 cm<sup>2</sup> – 3xGEM Prototype

Ancillary Detectors:

2 PMTs

2 APDs

RD51 GEM (or uM)

- Use of Goliath (up to 500 Gauss)
- Gas: Ar/CO<sub>2</sub> 70/30 (premixed)

# Space requirements

- Control Room:
  - Desktop table
- Test Area:
  - 100x90 cm<sup>2</sup> for the detectors on
  - 100x50 cm<sup>2</sup> table for: low voltage and high voltage power supply and computer
  - 2 crates (VME+NIM) in ½ rack

# Preliminary Plan

- 1 day: installation + “commissioning” (first time!)
- 1 day: operation with stable beam
- 2 days: magnetic field scan (50 – 500 Gauss), different GEM-field angles (access to change the angle, ~3 per day), preferable low beam intensity (at least at the beginning)
- 2 days: beam intensity scan (low - medium - high intensity)
- 0.5 day: dismounting