

Production of CMS GEM detectors for the GE2/1 and ME0 stations

With lessons learnt from GE1/1

Antonello Pellecchia¹ for the CMS GEM group


¹ *INFN Bari*

RD51 collaboration meeting - Dec 4-8 2023



Report on the GE2/1 mass-production for the upgrade of CMS

Jeremie A. MERLIN
RD51 Collaboration Meeting
November 17, 2021



Jeremie A. Merlin

RD51 Collaboration Meeting


CERN, Nov. 17, 2021 p. 1



Production Overview

- Mass-production organized in parallel in several production sites at CERN and outside (same as GE1/1)
- 8 production sites:
 - 6 already participated to GE1/1
 - 2 new sites already validated
- Dedicated pre/post-production teams
- The collaboration will focus first on the BACK-type chambers (M1 to M4) for risk mitigation and to optimize the work flow between sites

Note: Additional training sessions and refreshing courses are continuously organized in 904



Jeremie A. Merlin

RD51 Collaboration Meeting


CERN, Nov. 17, 2021 p. 3

... more than 2 years ago

Meanwhile:




- Production has continued
- First validation results are available
- Priorities have shifted
- New lessons learnt, still more to understand

INFN CMS GEM project




- **GE1/1:** Complementing CSC system in $1.6 < |\eta| < 2.15$
*Early Phase-2 upgrade: **already installed** in 2019-2020, commissioned and taking data during Run 3*
- **GE2/1:** Complementing CSC system in $1.6 < |\eta| < 2.4$
- **ME0:** Complementing other GEMs and CSCs in $1.6 < |\eta| < 2.4$, extending muon system coverage to $2.4 < |\eta| < 2.8$



In this presentation: GE2/1 production status and outlook on ME0



INFN Production overview



CMS GEM Production Scheme




Production scheme as for GE1/1:

- **Component** QC at CERN
- Five **production sites** (Bari, CERN, Ghent+Aachen, Frascati, PKU) for **individual modules**
- Electronics, chamber assembly (4 modules together) and final validation with cosmics at CERN




What do the detectors look like? And how have they changed?


INFN GE2/1 detector design



1 chamber = 4 modules





- 2 GE2/1 **endcaps**
- **18 “super-chambers”** per endcap
- **2 chambers** per “super-chamber” “Front” and “back” type
- **4 modules** per chamber
Front modules (M5, M6, M7, M8)
Back modules (M1, M2, M3, M4)



Mechanical stretching scheme

Detector and electronics design **inherited from GE1/1**, but with **lessons learnt**:

- Noise
- Protection for readout electronics
- Planarity and response uniformity
- Intrinsic time resolution




INFN Lesson: detector planarity





Problem: in GE1/1, drift and R/O **PCBs tended to bend** under stretching force

→ **dishomogeneity** of gain, efficiency and timing


1st GE2/1 solution: pillars (sensitive to deformation on drift)




2nd GE2/1 solution: rings




- **Much improved** gain uniformity and efficiency uniformity
- **Reduced risk of sparks** by weak spots in induction gap



Top: GE1/1 "long" detector
Bottom: GE2/1 M4 module



The **PCB bending** was impacting the **time response uniformity** of the detector.



In GE1/1, this caused **non-uniformity in signal** rise time → timing modulation with strip position (“basin effect”)

- **Fixable in GE1/1** by applying different delays to trigger primitives in GEM front-end FPGA


Fixed in GE2/1 and ME0 design by using pillars to ensure uniformity of induction gap:

- SPS test beam results: good timing **uniformity over 4 eta partitions**


Not a problem in ME0
(Should also be ok in GE2/1)

Our **time resolution with front-end electronics** is 15 - 19 ns, not 8 - 10 ns

- Common issue between GE1/1, GE2/1 and ME0: **analog front-end** not optimized for GEM signal shape and duration
- We cannot improve the time resolution*, but **we can mitigate effect** on online physics performance:
 - Reading out **multiple BXs readout** in back-end firmware
Implemented in emulator, under development in GEM firmware
 - From first simulations, online segment efficiency **recovered with matching window 3 BX**
Slight worsening in bending angle resolution only at “hypothetical” pile-up 300




Time resolution of ME0 detector measured in test beam




**unless maybe we change gas mixture... we are starting an R&D to check*

Simulated online segment efficiency with 3-BX readout



INFN Lesson: noise



GE1/1 hybrid




GE2/1 plugin card



Very **good S/N ratio** verified with high-granularity efficiency measurement in test beam \rightarrow

Same front-end ASIC (VFAT3), new PCB

- Chip is now **packaged**, bump-bonded (higher yield compared to hybrids)
- **Flex PCB** for easier alignment between readout board (ROB) and GEM electronics board (GEB)
- **HRS 140** connector to R/O strips provides more grounding pins \rightarrow \sim x2 lower noise




INFN Lesson: readout damage



GE2/1 plugin card included new **“decoupling” circuit** to prevent discharge propagation to front-end

- Operations with GE2/1 and ME0 detectors (demonstrator in CMS, test beam, lab measurements) showed too **high probability of discharge damage**
- We changed the **protection circuit back to the GE1/1 design** (470 Ω series resistor)

Discharge studies now show **no damage**
(expected damage probability per chip $< 3 \times 10^{-3}$)




Discharge propagation more likely with front-end electronics attached





How is the production going?

INFN GEM production schedule





Production schedule **approved by CMS** in GE2/1 manufacturing progress review (MPR), May 2023:



- Install **30 chambers out of 36** (almost one endcap) in year-end technical stop (YETS) 2023-2024
- **Complete** production by **October 2024** (no float)
- Start **ME0** production in **November 2024**
- Complete full GE2/1 system **installation in YETS 24-25**

In short: complete mass production of GE2/1 before ME0

Note: ME0 installation is constrained to January 2027 by HGCal schedule




INFN GEM foil production

Original plan: two GE2/1 foil producers

- **MPT workshop (CERN):** M1, M4, M5, M8
- **KCMS/Mecaro (Korea):** M2, M3, M6, M7

Mecaro produced **300 foils with 99% yield**
Each foil delivered with in-depth QC results



Test Date	2021. 5. 10	Room Humidity(%)	50																																			
Shifter Name	Dayoung Kang	Room Temperature(°C)	22																																			
Mecaro Foil Number	MK-210413-2A																																					
Foil Information	M #	RESISTOR BATCH #	FOIL #																																			
	2	A 002	02																																			
Official Foil Name	GE21-FOIL-M2-G12-KR-002-002																																					
1) Optical/Visual Inspection																																						
Ro Side Surface Condition - Stain	21 defects, different current at 600V - at 100V = 0.41																																					
Drift Side Surface Condition - Stain																																						
2) SMD Resistor																																						
Ro Side SMD Resistor	Passed		Drift Side SMD Resistor																																			
			Passed																																			
3) HV Line																																						
Ro Side HV Line	Closed Circuit		Drift Side HV Line																																			
			Closed Circuit																																			
4) Defects																																						
One defect with hole located																																						
5) Hole Diameter Inspection																																						
- Realized Image https://drive.google.com/drive/folders/1zPwCfD6GfWkJKPp9wvz_1T1Mq3M0b6?usp=sharing https://drive.google.com/drive/folders/113c_snpCfV3MzGzDfD0-8D_1215Gz8M?usp=sharing																																						
- Drift Side																																						
	<table border="1"> <thead> <tr> <th>Foil Section</th> <th>1</th> <th>2</th> <th>3</th> <th>4</th> <th>5</th> <th>Total Avg.</th> </tr> </thead> <tbody> <tr> <td>RD2A_CPMean</td> <td>77.8</td> <td>78.95</td> <td>80.99</td> <td>79.13</td> <td>78.15</td> <td>78.88</td> </tr> <tr> <td>RD2A_CPSigma</td> <td>1.02</td> <td>0.89</td> <td>0.84</td> <td>0.82</td> <td>0.82</td> <td>1.76</td> </tr> <tr> <td>RD2A_P2Mean</td> <td>54.37</td> <td>55.77</td> <td>59.37</td> <td>54.94</td> <td>56</td> <td>52.88</td> </tr> <tr> <td>RD2A_P2Sigma</td> <td>1.18</td> <td>0.93</td> <td>0.69</td> <td>1.01</td> <td>0.75</td> <td>1.77</td> </tr> </tbody> </table>			Foil Section	1	2	3	4	5	Total Avg.	RD2A_CPMean	77.8	78.95	80.99	79.13	78.15	78.88	RD2A_CPSigma	1.02	0.89	0.84	0.82	0.82	1.76	RD2A_P2Mean	54.37	55.77	59.37	54.94	56	52.88	RD2A_P2Sigma	1.18	0.93	0.69	1.01	0.75	1.77
Foil Section	1	2	3	4	5	Total Avg.																																
RD2A_CPMean	77.8	78.95	80.99	79.13	78.15	78.88																																
RD2A_CPSigma	1.02	0.89	0.84	0.82	0.82	1.76																																
RD2A_P2Mean	54.37	55.77	59.37	54.94	56	52.88																																
RD2A_P2Sigma	1.18	0.93	0.69	1.01	0.75	1.77																																
- RO Side																																						
	<table border="1"> <thead> <tr> <th>Foil Section</th> <th>1</th> <th>2</th> <th>3</th> <th>4</th> <th>5</th> <th>Total Avg.</th> </tr> </thead> <tbody> <tr> <td>RD2A_CPMean</td> <td>75.48</td> <td>77.04</td> <td>75.71</td> <td>71.01</td> <td>76.18</td> <td>75.05</td> </tr> <tr> <td>RD2A_CPSigma</td> <td>0.79</td> <td>1.05</td> <td>0.91</td> <td>0.92</td> <td>1.19</td> <td>2.41</td> </tr> <tr> <td>RD2A_P2Mean</td> <td>51.5</td> <td>52.07</td> <td>53.59</td> <td>50.24</td> <td>51.29</td> <td>51.74</td> </tr> <tr> <td>RD2A_P2Sigma</td> <td>0.73</td> <td>1.07</td> <td>1.26</td> <td>0.8</td> <td>1.24</td> <td>1.52</td> </tr> </tbody> </table>			Foil Section	1	2	3	4	5	Total Avg.	RD2A_CPMean	75.48	77.04	75.71	71.01	76.18	75.05	RD2A_CPSigma	0.79	1.05	0.91	0.92	1.19	2.41	RD2A_P2Mean	51.5	52.07	53.59	50.24	51.29	51.74	RD2A_P2Sigma	0.73	1.07	1.26	0.8	1.24	1.52
Foil Section	1	2	3	4	5	Total Avg.																																
RD2A_CPMean	75.48	77.04	75.71	71.01	76.18	75.05																																
RD2A_CPSigma	0.79	1.05	0.91	0.92	1.19	2.41																																
RD2A_P2Mean	51.5	52.07	53.59	50.24	51.29	51.74																																
RD2A_P2Sigma	0.73	1.07	1.26	0.8	1.24	1.52																																

→ In 2022, Mecaro **sold** its chemical lab away



→ Production **stopped** in August 2022

→ Equipment and expertise to be **relocated to KCMS**

→ GE2/1 foil production not continuing at KCMS:
will **start again for ME0 foils**



New plan: remaining foil production **to complete at MPT workshop**

- Restarted in July 2023
- Expected end in April 2024



INFN PCB production issue

- At end of summer 2023, **98 modules** assembled (24 chambers)
36 needed for 1 endcap
- In summer, assembly team had **issues with 80%** of production modules
 - Many **cleaning iterations** needed during assembly
 - **Shorts** forming while closing detectors
- Could not see issues in drift and R/O PCBs with microscope in QC lab
- However, MPT workshop lab showed **copper dust** (few μm) in PCBs
Cannot be removed by mechanical cleaning



Investigation on PCB quality (September 2023):


- Dust **came from sanding** done by PCB manufacturer (Micropack) on last PCB batch
Issue only for GE2/1
- Copper **passivation was not applied** in all PCBs:
No protection against copper **oxidation**
Affects both GE1/1 and GE2/1; impact on performance yet unknown
- We decided to **refurbish all GE2/1 modules** and redefine PCB validation

INFN PCB refurbishment

Refurbishment procedure established with the help of the **MPT Workshop**:


- Mechanical cleaning with tissue soaked with pure ethanol or isopropyl **alcohol**
- **Water jet** cleaning
- **Micro-etching**
- Chromic-acid **passivation**

Procedure also **applied successfully** by Micropack.
No visible difference now between MPT and Micropack refurbished PCBs



A **validation procedure** is now required **for all new PCBs**:

- Visual inspection
- Microscope inspection (**new**)
Inspection on several points on the PCBs with different light intensity
- Strip continuity/shorts (**updated**)



Still investigating on how to fix contaminated GEM foils

INFN New production plan


GE2/1 refurbishment plan:

- **Opening** all 98 modules
- PCB **refurbishment** at CERN MPT workshop
- **Re-assembly** and QC


Estimated time to complete production: **2.6 to 3.1 years**

Priority shifts to ME0:

- Stopping GE2/1 foil production at CERN and **start with ME0** (2024)
- **KCMS has started** the ME0 foil production already
- Beginning of ME0 **detector production in March** 2024



First production ME0 foil at KCMS




Until ME0 components arrive, **GE2/1 production continues:**



- Assembled **4 GE2/1 chambers**
2 with new modules, 2 refurbished
- Tested at CERN in “**cosmic stand**”
Telescope using final electronics and services
- We will **install the two best** chambers in CMS this year
1 new + 1 refurbished

INFN Outlook on GE2/1 chamber validation

We did a **test round** of chamber validation with cosmics for **non-refurbished** chambers: **still a few surprises** to be understood




Sitting idle
1 year




After opening

Gain dips found in 4 modules 1 year after production (but seems to disappear after opening the detector and flushing)

Instead the **refurbished and new** chambers show good stability and efficiency **uniformity**



Disconnected
HV sectors



Fist chambers almost ready for installation

Long way since beginning of Phase-2 GEM production:

- **GE1/1 lessons** applied to GE2/1 production:
noise, cross-talk, readout protection, efficiency uniformity
Or learning to live with: timing...
- Initially produced **almost 1 GE2/1 endcap**
- PCB **quality issue**: rescheduling project to prioritize ME0
- Defined a GE2/1 refurbishment procedure and first chambers will be installed **this year**

Still training the next generation of experts...

INFN Thank you

