


How to further improve commissioning? Plans for 2024 and beyond...

Kevin Li with input from A. Akroh, D. Cotte,
G.P. Di Giovanni, A. Huschauer, E. Mahner, B. Mikulec,
L. Ponce, J. Ridewood, A. Rodriguez, R. Scrivens,
P. Skowronski , J. Wenninger

Joint Accelerator Performance 23 Workshop
(JAP23)

5 to 7 December 2023






Commissioning introduction


- Every year, after the JAP WS, Christmas, New Year's Eve and Chamonix, when the snowdrops start peaking through the thin snow blankets and the snow begins to melt in increasingly warm sunrays, the CERN accelerator complex starts awakening from its hibernation; in technical terms, we call **this period the “(re-)commissioning phase”** of the accelerator complex...






Commissioning introduction

- Every year, after the JAP WS, Christmas, New Year's Eve and Chamonix, when the snowdrops start peaking through the thin snow blankets and the snow begins to melt in increasingly warm sunrays, the CERN accelerator complex starts awakening from its hibernation; in technical terms, we call **this period the “(re-)commissioning phase”** of the accelerator complex...
- Over the decades, this period has taken many shapes and trends; in recent years, from the experience of the LHC, it has undergone **a large level of rejuvenation and optimization**
 - LHC traditionally very **structured and organized approach** – necessary, to a large extent, due to sheer size and complexity of the machine, its self-termination capabilities and the very large number of expert teams needed!
 - Since post-LS2 adopted LHC-type of approach – **fixed schedule, detailed planning, structured and organized commissioning periods** → is there still room for improvements? What can we propose as next steps?
 - Since post-LS2 commissioning typically categorized into **individual system tests (IST), hardware commissioning (HWC) and beam commissioning (BC)**



Commissioning introduction

- Every year, after the JAP WS, Christmas, New Year's Eve and Chamonix, when the snowdrops start peaking through the thin snow blankets and the snow begins to melt in increasingly warm sunrays, the CERN accelerator complex starts awakening from its hibernation; in technical terms, we call **this period the “(re-)commissioning phase”** of the accelerator complex...
- Over the decades, this period has taken many shapes and trends; in recent years, from the experience of the LHC, it has undergone **a large level of rejuvenation and optimization**
 - LHC traditionally very **structured and organized** approach – necessary, to a large extent, due to sheer size and complexity of the machine, it's self-termination capabilities and the high cost of the machine
 - Since post-LS2 adopted LHC-type of approach – **fixed periods** → is there still room for improvements as next steps?
 - Since post-LS2 commissioning typically categorized into **beam commissioning (BC)**
 - Commissioning length, procedures, equipment expert needs
 - AccTesting / EPA WP7 for HW commissioning
 - Commissioning as test phase for new implementations
 - What OP can do during night shifts and weekends?
 - Ions: how to optimize the ion commissioning to have less impact on other physics?
 - E.g., cycles ready and debugged without beam at beginning of year



Commissioning – how to further improve?

- This topic has already extensively been scrutinized over the last 2 years:
 - Bettina Mikulec et al.: [Commissioning – post-LS2 lessons learned](#) – IEF WS '21

Summary



- The LIU project provided the necessary framework for a **common vision with clear goals and structure**
- Will be a challenge to ensure continuation
- **ISTs** – we must ensure commitment of all equipment specialists for whole complex
- During shutdown period organised by EN-ACE
- Dedicated period at start of HWC with machine closed managed by OP
- **HWC** – comprehensive Checklists and use of Dry Runs are essential
- No carry-over activities from shutdown
- **BC** – need a clear hand-over point from HWC
- Reserve sufficient time for BI checks with beam at start
- Start with simple cycle
- Kick response + aperture measurements routinely where possible
- **Special runs and test facilities are crucial**



B. Mikulec, IEF Workshop 6-9 Dec. 2021

42

Summary




- ✓ **Stop and think how SW management could be improved**
 - Needs to become an integral part of the project planning
 - Integration, test layers, standardisation, collaboration
- ✓ **Facilitate HL SW organisation, automation, tools, synergies**
- **Need for an interlock 'super-agent'**
- Sustained effort for **optics validation and physics modelling**
- Continue effort to improve **power converter regulation and noise issues**
- Special test periods after runs with machine closed?
- Cable routing, shielding, grounding...
- ✓ **Work towards more global organisation everywhere**
 - Shutdown coordination, SW coordination, new commissioning and integration link person per group?



B. Mikulec, IEF Workshop 6-9 Dec. 2021

43





Commissioning – how to further improve?

- This topic has already extensively been scrutinized over the last 2 years:
 - Bettina Mikulec et al.: [Commissioning – post-LS2 lessons learned](#) – IEF WS '21



Conclusions

- There are possibilities to speed up machine restart, that all the teams already actively work on
 - Automatization
 - Optimization
 - Rationalization
- Four aggressive options
 - Running with past year settings
 - Reducing contingencies
 - Scheduling expert activities also outside working hours
 - Transfer selected Expert activities to OP
- These are not exclusive, each of them can be applied independently

31

JAP WS @CERN, Week #35

December 8, 2022



Conclusions

- Each of the aggressive options comes with a price to pay: important consequences
 - Not the best beam performance
 - Uncertainty in time of the activities and the commissioning completion
 - Compensations for outside working hours activities
 - Work on documentation and training
 - Agile planning of the commissioning, YETS and other adjacent activities
 - Increased entropy requires energy to keep the temperature cool, well below boiling point

32

JAP WS @CERN, Week #35

December 8, 2022

- Piotr Skowronski et al.: [Aggressive hardware and beam commissioning in the injectors](#) – JAP WS '22

→ Automation works progressing – EPC tests already optimized for new FGCs,...




Commissioning – how to further improve?

- This topic has already extensively been scrutinized over the last 2 years:

Bettina Mikulec et al.: Commissioning – post-LS2 lessons learned – IFF WS '21


Piotr Skowronski et al.: Commissioning – post-LS2 lessons learned – IFF WS '22

With the same regularity that we recommission, we also have a talk on **how to better recommission** ;)!
(might give the impression we are not re-commissioning well; this is not quite true...)






Traditional post-LS2 commissioning schedules



2023



2024




LHC






Traditional post-LS2 commissioning schedules

2023




2024




• Landscape some time after the “immediate” post-LS2 commissioning for the injectors – after IST period:

- Injectors commissioning period very **complex due to multi-parallel activities** across complex – commissioning for the ‘own’ machine plus preparation for downstream machines and facilities, many dependencies, much less predictable
- Usually, a few weeks before delivery to EA and/or start of physics
 → **critical period to accommodate scrubbing, beam development and optimization as well as tests of new equipment, tools and procedures!**




Traditional post-LS2 commissioning schedules

2023




2024



- Landscape some time after the “immediate” post-LS2 commissioning for the injectors – after IST period:
 - Injectors commissioning period very **complex due to multi-parallel activities** across complex – commissioning for the ‘own’ machine plus preparation for downstream machines and facilities, many dependencies, much less predictable
 - Usually, a few weeks before delivery to EA and/or start of physics
 - **critical period to accommodate scrubbing, beam development and optimization as well as tests of new equipment, tools and procedures!**
 - Staged “coming online” of machines has proven valuable in terms of resource allocations and expert availabilities
 - There is always a “ladies’ and gentlemen’s” agreement, that beam can be sent if ready earlier and useful for downstream machines → good level of flexibility retained





Commissioning – how to further improve?


- As a result of previous work, optimization and accumulated post-LS2 experience in commissioning the injectors complex, from own experience and gathered from interviews across the accelerator chain:
 - Excellent performance achieved, and **very positive feedback received** during and after commissioning throughout the entire complex; not that much more to squeeze out in terms of optimizations
 - When analyzing, some open points can be still identified:

 - Overall, an incredible development from the early days; performance gradient positive since post-LS2 start-up; difficulties encountered:
 - '21: Post-LS2 recommissioning year → delays and some loss of physics (SPS)
 - '22: Flawless commissioning and no delays
 - '23: Ions commissioning spot on and no delays → may want to give some margin to relax stress levels
 - '23: Scrubbing needs much larger than expected – solved with new scrubbing tools and strategies → may want to retain
- **Beam commissioning improvements** – how to make best use of the later stages before experimental areas are ready? Ions or MDs preparations?

- **Hardware commissioning improvements** – what can still be squeezed out

- **ISTs** – can we still improve anything?

- ISOLDE, AD/ELENA are still left somewhat aside → routinely leads to problems, i.e., expert availability conflicts




ISTs – what can be improved?

- With meanwhile 2.5 years of post-LS2 experience and cross-complex optimizations in place, we can recapitulate:
 - ISTs – can we still improve anything:
 - Mostly now **very well planned and followed up**, adopted by all groups and mostly **executed with great care and detail**; cases with room for improvement for quality control can be sorted out on a case-by-case basis
 - “Hybrid” period with tunnel open but restricted access works very well for localized tests (i.e., kickers or RF), but is difficult to manage for distributed tests (i.e., EPC) → mitigated **by integrating a separation** of the two types of ISTs
 - Most recent optimization implemented by adding complementary **IST period at the end of the year**
 - ISOLDE & AD/ELENA also have their ISTs and planning, even using the EN-ACE infrastructure; coordination meetings take place as ITC and ADTC but outside of the EN-ACE coordination framework:
 - Nevertheless, the schedules are **still somewhat separate** as the planning is not fully integrated such as for the LHC injectors
 - Still can lead to **conflicts in case of delays and schedule drifts** as they are not dynamically accommodated – is a tighter link to EN-ACE conceivable?

→ Little room for optimization – better integration of remaining facilities into EN-ACE framework?

HWC – what can be improved?

- With meanwhile 2.5 years of post-LS2 experience and cross-complex optimizations in place, we can recapitulate:
 - HWC – what can still be squeezed out:
 - **Time to save → not much:** large fraction still made up of EPC testing – lateral activities integrated to **parallelize as much as possible**; OP verification of EPC tests could be economized (see P. Skowronski – JAPW '22), gain limited
 - **Coordination to improve → punctual:** sometimes conflict in “fuzzy areas”, i.e., Ti2 / Ti8 HWC from SPS vs. tests in LHC; also, conflicts in ISOLDE, AD/ELENA, which are still somewhat aside of the EN-ACE integrated planning and, hence, risk to **run into a lack of experts**
 - **Automation uses cases existing → yes:** many tests that could profit from automation a la AccTesting in the LHC; got this feedback across the injectors chain for movable devices, interlocks, vacuum, current functions,... → **use case exist for extended AccTesting framework**



HWC – what can be improved?

- Some levels of **automation in the injectors** already in place today:
 - Example SPS: FGC Check (F. Follin)
 - Example PS: sequencer used for more automatic HWC for power converters

SPS FGC Check

Context: SFT_ION_4inj_E380.49_L9086_2022_V1 [SPS.USER.SFTION1]

Filter: RDV

| Device Name | Accelerator Zone | State PC | Mode OP | Check Result |
|-------------|------------------|----------|---------|--|
| RDV.60707 | SPS | CYCLING | NORMAL | FGC LOG I REF doesn't follow the REF.TABLE at Time = 8993 ms; LOG I REF = -0.469 Amps, REF.TABLE (interpolated) = -0.... |
| RDV.62107 | SPS | CYCLING | NORMAL | FGC LOG I REF doesn't follow the REF.TABLE at Time = 9004 ms; LOG I REF = -0.187 Amps, REF.TABLE (interpolated) = -0.... |

Checked: 365 / Errors: 6

Buttons: Check, Stop, Skip, Open Status, Open Graph Viewer

RDV.60707

26.11.2022 05:49:12

Legend: LSA Ref Table (purple), FGC Ref Table (blue), FGC Log I Ref (green), FGC Log I Meas (red)

Graph: Beam In vs Time [ms]

Buttons: Start, Stop

BLRSPS Interlock Test

| Test Name | Hardware Dump | Software Dump | Dump Signal |
|--------------------------|---------------|---------------|--------------|
| No Interlock Test | NO INTERLOCK | NO INTERLOCK | NO INTERLOCK |
| Interlock Test Channel0 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel1 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel2 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel3 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel4 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel5 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel6 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel7 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel8 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel9 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel10 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel11 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel12 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel13 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel14 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel15 | INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel16 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel17 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel18 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel19 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel20 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel21 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel22 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel23 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel24 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel25 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel26 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel27 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel28 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel29 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel30 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| Interlock Test Channel31 | NO INTERLOCK | INTERLOCK | INTERLOCK |
| No Interlock Test | NO INTERLOCK | NO INTERLOCK | NO INTERLOCK |

Buttons: Start, Stop

HWC – what can be improved?

- Some levels of **automation in the injectors already in place today** – example FGC Check (F. Follin) in the SPS
- AccTesting framework as **ideal platform for integrating exactly these (and other) types of tests** for an extended automated testing framework and platform compatible both for the LHC and the injectors complex (including ISOLDE and AD/ELENA)

OP Technical Meeting - Automation of the HWC
 Thursday 2 Mar 2023, 10:00 → 11:30 Europe/Zurich
 774/1-079 (CERN)

- 10:00 → 10:05 Introduction** (5m)
 - Contextualization and scope of the meeting.
 - Speaker: Niels Killian Noal Bidault (CERN)
- 10:05 → 10:20 AccTesting: functionalities and plans** (15m)
 - Speaker: Jean-Christophe Garnier (CERN)
- 10:20 → 10:35 AccTesting: feedback and recommendations** (15m)
 - Speaker: Matteo Soffaroli Camillocci (CERN)
- 10:35 → 10:50 OP needs and discussions** (15m)
 - Results of the survey on the OP needs for automation tools during HWC. Initial discussions.
 - Speaker: Niels Killian Noal Bidault (CERN)
- 10:50 → 11:00 Checklist** (10m)
 - Speaker: Emanuele Matti (CERN)
- 11:00 → 11:10 HWC automation tools at ISOLDE** (10m)
 - Speaker: Jose Alberto Rodriguez (CERN)
- 11:10 → 11:20 Sequencer** (10m)
 - Speaker: Ronaldus Suykerbuyk (CERN)


Accelerator Testing - testbed-gpn

Campaign [Active]: End of LS2 Validation 2
 23 Systems, 20 Tests, 10 Successes, 50% Successful

| System name | Active | Pie Chart | The tests for the system |
|-------------|--------|----------------|---|
| RCD.272B1 | EXE | 0% Successful | PIC2 QPS..., PIC2 PC... |
| RCBXH1.272 | EXE | 57% Successful | PIC2 QPS..., PIC2 PC..., PIC2 PO..., PIC2 CIR..., PIC2 FAS..., PNO.d3, PNO.a3 |
| RCBXV1.272 | EXE | 57% Successful | PIC2 QPS..., PIC2 PC..., PIC2 PO..., PIC2 CIR..., PIC2 FAS..., PNO.d3, PNO.a3 |
| RCSX3.272 | EXE | 50% Successful | PIC2 PC..., PIC2 PO..., PNO.d1, PNO.a1 |


Displayed Test Filter: RUNNING, FAILED, ANALYSIS_PENDING, SIGNING_PENDING, NOT_STARTED, EXCLUDED, SUCCESSFUL

→ Little room for optimization – AccTesting across the complex generally welcomed with a great potential!



BC – what can be improved?

- With meanwhile 2.5 years of post-LS2 experience and cross-complex optimizations in place, we can recapitulate:
 - BC – open points:
 - With the last LIU implementations finalized in the SPS during LS2 and post-LS2 commissioning and the consolidation of all upgrades across the injector chain, we have come a long way in terms of optimization



BC – what can be improved?

- With meanwhile 2.5 years of post-LS2 experience and cross-complex optimizations in place, we can recapitulate:
 - BC – open points:
 - With the last LIU implementations finalized in the SPS during LS2 and post-LS2 commissioning and the consolidation of all upgrades across the injector chain, we have come a long way in terms of optimization

• Lessons learned:

- Acknowledge that **scrubbing, testing of new procedures and tools as well as training** should be an integral part of BC
- Very good feedback from common commissioning periods; would also be useful for other facilities, i.e., AWAKE
- OP tasks during nights and weekends: not so much a problem
 - We do have activities and procedures that can be carried out by OP once machines are running (apertures, kick responses, general cycle setting up, complementary hardware tests, scrubbing,...);
 - Where this is not possible, **rather invest in procedures and tools**, such that they can be carried out by OP
 - Turning on and off the machine every day would be **highly inefficient**


BC – what can be improved?

- With meanwhile 2.5 years of post-LS2 experience and cross-complex optimizations in place, we can recapitulate:
 - BC – open points:
 - With the last LIU implementations finalized in the SPS during LS2 and post-LS2 commissioning and the consolidation of all upgrades across the injector chain, we have come a long way in terms of optimization

Remaining issues:

- Expert dependencies – some items and systems still need intense expert support, e.g.:
 - RF setting up: harvest the **chances that come with system renovations** and focus on hardware abstraction and operational integration!
 - LHC: still often expert driven, thus, potential lack of exploiting flexibility provided by OP shifts
- Ion commissioning – **potential anxiety** when having commissioning allocated during physics and/or so closely to required beam delivery date!
- MDs preparation still **sometimes an issue**, especially for exotic configurations (special beams, modes, equipment)





Ion commissioning problematics




- Example of an ion commissioning using a representative schedule in 2023


- Ion commissioning start ~July – ion run start ~November
- Commissioning time: 6 weeks source / LINAC3 + 1 week LEIR + 1 week PS + 8 days SPS

- Advanced ion commissioning implications per machine – knock on effects:

- SPS:
 - Likely possible – set up cycles and assume machine will come back in same state half a year later → by experience reasonable assumption
- PS:
 - Commissioning expected to be more efficient with lessons learned (start with nominal)
- LEIR:
 - Potential conflict with start-up of AD/ELENA as the facilities share the same pool of experts!


- LINAC3 + SOURCE:
 - full re-commissioning is assumed to be needed → +6 weeks supplemental work; choice to be made






Ion commissioning problematics

- Example of an ion commissioning using a representative schedule in 2023
 - Ion commissioning start ~July – ion run start ~November
 - Commissioning time: 6 weeks source / LINAC3 + 1 week LEIR + 1 week PS + 8 days SPS




• YETS ions:


- Maintenance and start up of LINAC3 + LINAC4 + SOURCES need to **shift from sequential (today) to parallel** with resources shared; this extends over several departments (BE, SY, EN,...) → identified as actual problem
- YETS '24 already fully optimized and scheduled → identified as not implementable for run '24
- DSO tests, etc. not necessarily a problem, inclusive



• Other ions need to be developed


→ Cost: 6 weeks extra + resource doubling during YETS (and potential collision with AD/ELENA commissioning) to gain ~2 days of NA physics – can we get this cheaper?






Ion commissioning problematics

- Example of an ion commissioning using a representative schedule in 2023
 - Ion commissioning start ~July – ion run start ~November
 - Commissioning time: 6 weeks source / LINAC3 + 1 week LEIR + 1 week PS + 8 days SPS



- 2.5 alternative options addressing different issues:
 - Advance start of physics by 1 week** to mitigate loss of physics; recover the week needed for ion commissioning close to where the ion beam will be needed → + 1 week earlier in the year, - 1 week later for ion commissioning
 - Advance MDs into the beam commissioning period** to free up slots, or at least make MDs more efficient later in the year – caution not to cluster MDs too much as some require to be distributed throughout the year
 - Start up ions complex outside of the beam commissioning period, but still earlier;** in particular early enough, to be ready with ions beams few weeks in advance to accommodate for potential issues and delays – maintain the **very useful beam commissioning period** as is



LHC specific items





- Hardware commissioning – making heavy use of AccTesting; appreciating extension of this framework as well
 - SPS HWC Ti2 / Ti8 vs. LHC still in access has led to problems; will be tried next year during LHC powering tests when machine closed
- Beam commissioning – with high availability of OP team due to shifts, could gain more flexibility by offloading expert activities to OP tasks
 - **Optics:** effort to orient OMC tools towards OP, start in 2024 with optics measurements launchable by OP – less optics changes helps of course
 - **Collimators:** alignment & validation (validation, loss maps, etc. already automated, same for crystal alignment, OP measurements followed by expert validation); collimator alignment also automated, but still needs supervision of experts, same for aperture scans → can this be **taken to the next level**?
 - **Transfer lines:** injection setting up & collimator alignment – tools prepared and developed in collaboration with OP; can we automate this further?

A summary on feedback for beam commissioning – overall already discussed extensively in David's talk

ISOLDE & AD/ELENA specific items

- Feedback from both terminal facilities:
 - ISTs and HWC planned within OP and isolated from rest of the complex outside of a global framework
 - Usually need to plan around expert availability constraints; **conflict of priorities** can be a recurring issue
 - Priority conflicts require **allocation of large time windows** to ensure expert availability
- Concrete examples:
 - ISOLDE: since 2015 every year major HW change with certain time allocated for commissioning; since post-LS2 no more significant HW upgrades; still, same amount of time is needed for commissioning...? What can be gained by complex-coherent settings management (LSA)?
 - AD/ELENA has many overlapping expert teams with LEIR – simultaneous startup with LEIR leads to lack of equipment experts
 - Would clearly benefit being **integrated in a global planning** a la EN-ACE



- Today, injectors complex (re-)commissioning already very well optimized
 - Clear structures put in place
 - Usually good cross-complex coordination and planning
 - Frameworks for tests scheduling, execution and validation deployed
 - Idea to establish preparation and planning as part of the FOM before startup (check ISTs, HWC and BC with resource allocations and identification of potential conflicts)
- Feedback from different periods across machines
 - IST – little room for optimization; better integration of ISOLDE & AD/ELENA into EN-ACE framework?
 - Hardware commissioning – little room for optimization; AccTesting across the complex clearly welcomed with a great potential!
 - Beam commissioning – make most **efficient use of time window** between first beam and start of physics program; **some options presented**

Final word:

- Beam commissioning is a **unique development and training period**
- Advanced **tools, procedures and automation** are powerful utilities to enhance operational efficiency, reliability and reproducibility
- From **beam commissioning** onwards OP can provide resources for 24/7 coverage – integration of these tools during this period should help making machines more accessible and **operations to become more effective**



