



# Prévessin Data Centre Powers Up

24 October 2024

CERN IT – Max DUPUIS

# Outline

**CERN Data centre in 2020**

**LHC Needs**

**Increase CERN Data centre capacity**

**PDC: Design**

**PDC: Trial Operation**

**PDC: Operations & Maintenance**


**PDC: 1<sup>st</sup> year of operation**

**PDC: Milestones**

# CERN Data centre in 2020

## Available capacity 5 MW:

- 5M HEPScore [1] CPU processing
- 900 PB Tape Storage
- 320 PB Disk Storage



## Meyrin Data Centre (MDC) – 1973

- 3.8MW for computing in 3 rooms, PUE ~1.5
- full UPS and partial diesel coverage, tape robots

## B613 – 2001

- 100 kW for Backup tape robots
- full UPS and diesel coverage, tape robots

## 2<sup>nd</sup> Network Hub – 2016

- 100kW site network redundancy, PUE ~1.1
- full UPS and diesel coverage

## LHCb containers – 2018


- 2 containers of 500kW for computing, PUE ~1.1
- No UPS or diesel coverage

# LHC needs

The computing needs of CERN are largely driven by the LHC experiments (~85%)

Requirements evolve continuously

Each upgrade of the LHC and/or experiments leads to higher data rates and hence higher computing needs (RUN3 => RUN4 ~ factor of 10)



# Increase CERN Data centre capacity



After several attempts the project has been approved at the FC in 2020. Mid 2021 contract has been signed with a consortium led by EQUANS.

## Tender Solution Logic:

- Maintained the approach for the 2019 tender
- DC design is specialised and has been progressing quickly over the past years
- We wanted to benefit from industry expertise, therefore, a functional specification in the tender with minimal design prescriptions
- 10-year O&M to ensure good design

# PDC: Design

Highly efficient data centre with a Power Usage Effectiveness (PUE) [2]  $\leq 1,15$

Construction in 1 phase

Installation will be in 3 phases over time for a total of 12MW

- **1<sup>st</sup> Phase:** 4MW - 2nd floor
- **2<sup>nd</sup> Phase:** +4MW - 1st floor
- **3<sup>rd</sup> Phase:** +4MW - ground floor




# PDC: Design

Footprint 2250m<sup>2</sup> (70mx37mx19m)

6400 m<sup>2</sup> of which 2100 m<sup>2</sup> for IT rooms

6 IT rooms of 2MW each, two per floor



Transformers and Low Voltage distribution, but High Voltage equipment's are provided by CERN



# PDC: Design

4x 2MW Jaegi dry coolers in 1<sup>st</sup> Phase (2x2MW per additional phase) - N+1 redundancy plus 1 for technical areas

Adiabatic cooling from 20 degrees outside temperature with water recycling to improve Water Usage Effectiveness(WUE)[\[3\]](#)





# PDC: Design

5 x 500kW fan walls per room (Schneider largest in Europe), N+1 redundancy

ASHRAE [4] class A1, temp. environment up to 32 degrees


Heat recovery of 3 MW in 1<sup>st</sup> phase and 4 MW in 2<sup>nd</sup> phase



# PDC: Design

## 90 Racks per room

- **54x** 800mm wide, Non-UPS racks up to 25kW (physics data processing)
- **24x** 600mm wide, UPS racks up to 12kW (business continuity)
- **12x** 800mm wide, 50% UPS racks (network pod)



# PDC: Design


Air-cooled racks with hot-aisle containment

Two redundant power feeds: **red** and **blue**

- Red feed: 20% UPS coverage (Business Continuity)



Two type of Power Distribution Unit (PDUs):

- 63Amps (physics data processing)
- 32 Amps (business continuity)



# PDC: Design



Computational Fluid Dynamics (CFD) has been used to determine the optimal IT room layout and to evaluate various failure scenarios.



# PDC: Trial Operation

At the end of the commissioning of the 1<sup>st</sup> phase, we run a test with servers with the following technical scope:



- Build a full non-UPS POD with batch servers:
  - 576 nodes (144 Quads) for a total of 432 kW
- All other racks sealed with front-panels
- Run standard burn-in for one week



# PDC: Trial Operation

## Several scenarios have been tested:

- Verify operation in nominal mode
- Verify redundancy in power topology - cut a feed and verify
- Verify redundancy in cooling - cut 1 fanwall and verify
- Verify redundancy in cooling - cut 2 pumps of dry cooler and verify
- Verify operation on UPS – cut all fanwalls and let servers running for 5 min



# PDC: Operations & Maintenance

O&M managed by EQUANS has started once the commissioning + trial operation completed successfully in February 2024.


Current contract runs until 2034.

From CERN perspective, the contractor:

- Fulfills roles of CERN technical groups for the infrastructure
- Acts on PDUs failures triggered by us (PDUs are monitored + managed by CERN IT using standard tools)
- Provides access to the Building Management System (PCVue) for detailed internal views of whole infrastructure

## Monthly contract meetings

- Review issues and performance (PUE, WUE)



# PDC: Operations & Maintenance

For O&M at rack level and Electrical distribution, we are using the same model as Meyrin Data Centre (MDC):

- Since Q1 2024, CERN IT is operating remote computing facilities effectively without the CC Operator providing on site corrective action
- DC resilience at a rack level has reached a point that doesn't require immediate CC Operator intervention to maintain service continuity
- Platform and Applications are designed with a high degree of fault tolerance and can withstand a single point of failure
- Critical Function has been reassigned to CERN Control Room (SSB entry following DC infrastructure incident, call IT piquet, monitor and handle network alarms)





# PDC: 1<sup>st</sup> year of operation

Since the beginning of 2024, the two rooms of the 1<sup>st</sup> Phase have been operational. In 6 months, we successfully commissioned the PDC at 50% capacity


**NEXT:** In preparation to Run4, we will need to initiate the installation of the 2<sup>nd</sup> Phase of the PDC and begin procuring additional servers



# PDC: Milestones

- 2008 – 1<sup>st</sup> Tender with 4 concept design
- 2009
- 2010
- 2011 – 2<sup>nd</sup> Tender Remote hosting capacity
- 2012
- 2013 – Wigner (HU) - 2.5MW – 7Y Ops
- 2014
- 2015
- 2016
- 2017 – 3<sup>rd</sup> Tender
- 2018 – LHCb Containers - 1MW – 7Y Ops
- 2019 – 4<sup>th</sup> Tender
- 2020
- Q4 - Approved at the FC
- 2021
- Q2 - Contract Signed
- Q3 - Building Permit
- 2022
- Q2 - Groundbreaking Ceremony
- 2023
- Q4 - Commissioning of the Data Centre
- 2024
- Q1 - O&M Began
- Q4 – 50% Capacity reached





**Thank you!**

Questions?

[home.cern](http://home.cern)

# References

- [1] **HEPScore** is a new CPU benchmark created to replace the HEPSPROC06 benchmark that is currently used by the WLCG for procurement, computing resource pledges and performance studies. [HEPScore A new CPU benchmark for the WLCG](#)
- [2] **Power Usage Effectiveness (PUE)** metric, a tool designed to help boost energy efficiency in data center operations. [PUE A Powering Change Across the ICT Industry Infographic](#)
- [3] **Water Usage Effectiveness (WUE)** metric to address water usage in data centers, which is emerging as extremely important in the design, location, and operation of data centers in the future. [WUE A Green Grid Data Center Sustainability Metric](#)
- [4] **The American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE)** is an American professional association seeking to advance heating, ventilation, air conditioning and refrigeration (HVAC&R) systems design and construction. [Equipment Thermal Guidelines for Data Processing Environments](#)