FD1-HD and FD2-VD FC workshop

Nov. 18, 2023
1st DUNE FC Workshop

Jaehoon Yu University of Texas at Arlington

Workshop Fundamentals

- Goals: To train all group members with DUNE field cage module QC, tooling and assembly procedure
- Tasks to complete in the workshop
 - Understand the scope and tasks involved in the project
 - 2. Complete construction of the HDFC assembly table, including the motor drive and operate
 - 3. Go through the module assembly procedure hands-on and finish constructing one HDFC module
 - Go through the module parts QC procedure and exercise recording them into the QC iPADs

Neutrino fundamentals – 1

- Postulated in 1930 to explain the nuclear β-decay and detected experimentally in 1956 (1995 Nobel)
- Fundamental particles of matter in the current Standard Model of Particle Physics
 - Makes up a quarter of the whole particle table in TSM as massless particles
 - Have three flavors electron (ν_e <u>2002 Nobel</u>), muon (ν_μ <u>1988 Nobel</u>) , and tau (ν_τ) types
 - Charge neutral and only interact via the weak force → do not interact often in matter

Neutrino fundamentals – 2

- Large numbers of low E neutrinos (v_e) produced in the Sun (2002 Nobel) and in reactors
 - − → $65x10^9 v_e/s/cm^2$ (FFT: how many passes throughout your body/sec?)
- Neutrino flavor oscillation (change their flavors in flight!) discovered & confirmed throughout late 1990 and early 2000 (2015 Nobel)
 - Happens because flavor and mass eigenstates differ (oscillation probability dependent on L/E_v)

$$P(\nu_{\mu} \to \nu_{e}) = \sin^{2} 2\theta \sin^{2} \left(\frac{1.27\Delta m^{2}L}{E_{\nu}}\right)$$


Neutrinos have mass! → SM in BIG trouble!

The DUNE Experiment
 Stands for Deep Under Ground Neutrino Experiment


US flagship long baseline (1300km)

✓ experiment

- 1500m underground in an old South Dakota gold mine



Anatomy of DUNE




Nov. 18, 2023

DUNE FD1 & FD2 FC Workshop 1


Images in DUNE LAr-TPC Prototypes








Electromagnetic shower + two muon decays



Multiple hadronic interactions in a shower



DUNE FD1 & FD2 FC Workshop 1


Latest news on DUNE

- Both ProtoDUNE HD and VD cryostats to close by the end of Nov. → LAr fill to follow in Jan. 2024
 - Need to have someone (most likely grad students) out at CERN to help with the fill and the subsequent data taking operation
- FD2 VD installation mechanical mock-up testing in Summer 2024 at CERN
- UTA is expected to undergo 2 production readiness reviews (PRR) successively in summer (FD1 HD done w/ UMN) and fall 2024
- CPB120 renovation progressing well → floor painting to be done over the winter break
- Need to procure necessary tools and parts for tooling and build them

21 60 180 280 20 1


LArTPC HVS Overview

- HVS provides a <u>uniform E field</u> to the active volume for the ionization electrons to drift to anodes
- Consists of three primary components




HVS Consortium Scope - FD1-HD TPC

- Design, fabricate, test and assemble:
 - **100 CPA** resistive panels forming two cathode arrays (1400m²)
 - 100 top + 100 bottom field cage modules, 48 End Wall field cage modules (1728m²)
 - 2 sets of HV power supplies, cables, ripple filters, and feedthroughs



HVS Consortium Scope - FD2-VD TPC

- Design, fabricate, test and assemble:
 - 80 Full Unit Cathode Planes (780m²) with embedded PD
 - 192 field cage modules 160 Long Wall and 32 End Wall modules (~1781m²)
 - One set of HV power supply, cable, ripple filter, and feedthrough
 - Digitizers for HVPS and current monitoring
 - Cameras for HV monitoring



Installation: 2027 – 2028@SURF

Field Cage & the Scope of the Work

- FC surrounds the active volume and help provide a uniform E field
- The Scope: Construct the field cage (FC) for the FD1-HD and FD2-VD, integrate it into the HVS
- Teams
 - FD1-HD: UT Arlington, U. of Minnesota, LSU and CERN
 - FD2-VD: UT Arlington, William & Mary and CERN
- This entails to
 - Procure all the FC parts and devise the necessary tools
 - CERN is responsible for design and the aluminum profile electrodes
 - UTA is responsible for FRP and other parts
 - QC the FC parts
 - Package and ship QCed parts to SURF at least 6mo prior to the start of the construction
 - Assemble FC modules, including the HVDB mounting underground at SURF
 - Install FC into FD1-HD (Mar. 2027 Dec. 2027) and FD2-HD (Feb. 2028 June 2028)
 - Commission the HV system

Parts for UTA to Process – FD1-HD

- Process parts for 100 BFC w/ 10% spare & deliver by 11/1/26
- Parts and numbers to process
 - For BFC Modules
 - FRP I-beams: 2/BFC + 10% spare → 200+20 = 220
 - FRP Latch Beams: 2/BFC + 10% spare → 200+20 = 220
 - G10 Reinforcement plates: 4/BFC + 10% spare → 400+40 =440
 - BFC Lifting Bar: 1/BFC + 2% spare → 100+2 → 102
 - Lifting Plates: 2/FC → 8 total (already in hand)
 - All necessary hardware : screws, lock washers, flat washers, nuts
 - Tooling
 - 2 FC assembly tables : One to be shipped to SURF
 - Any tools for installation

FD1-HDI-Beam (process 220)

[50.8]

ш.

[101.6]

BREAK CORNER-


BOTH SIDES

1.500


[38.10]


C


R1.00 [R25.4]




FD1-HD Latch – Beam (process 220)











FD1-HD Reinforcement Plates (process 440) & Lift Bars (make 102)



Parts for UTA to Process – FD2-VD

- Process parts for 192 FC w/ 10% spare & deliver by 9/1/27 → 2*3 different types of modules , long wall/end wall * top/middle/bottom
- Parts and numbers to process
 - FC Module
 - FRP Box-beams: 2/FC + 10% spare → 384 + 38 = 422
 - FRP Box beam insert for inter-module connection :2/FC+10% spare → 384+38
 - Bottom stabilizers : 2/FC column + 10% spare: 2*48*1.1=106
 - Top stabilizers: 2/FC column + 10% spare: 2*48*1.1=106
 - Top yoke: 1/FC column + 10% spare: 1*48*1.1=53
 - Top SM I-beams: 1/SM + 10% spare: 1*24*1.1=26
 - All necessary hardware: screws, lock washers, flat washers, nuts, etc.
 - Tooling
 - 2 profile bending tools: stay at UTA
 - 3 FC assembly stands: Two to be shipped to SURF, 1 at UTA
 - 28 FC Storage carts: all to be shipped to SURF
 - 3 scaffolding structure for module assembly: 2 to be shipped to SURF
 - 4 installation tripods: all to SURF
 - 1 gantry crane for completed module lifting and insertion into the storage cart
 - 4 module installation carts: all to SURF

FD2-VD Long-wall Bottom Module (48)




FD2-V


BILL OF MATERIALS EDH SCEM DESIGNATION REFERENCE MATERIAL SQ beam : L=3240 mm **VETRONIT ®** FD2 FC Bottom part SQ beam 01 ST1684965 EP GC 201 Epoxy FR-4 2 Bottom Constraint Bracket ST1684889 ALUMINIUM PROFILE 3DI13133 : L=3308 mm Alu EN AW-6061 03 54 Aluminum beam A 03 ST1688567 (T6) 04 114 Slip Nut Narrow ST1683412 Thin FC Profile cap deep tabbed PE-UHMW 05 108 Cap 01 (for Aluminum beam A) ST1682479 06 54 Slip Nut Narrow Nonlocking ST1683948 CENBNFVD0005 07 RDB ST1690348 27PIF0045 NYLON @ (PA) 08 216 Push-In Rivets ST1681574 St. Steel A4 ISO 4762 HEX SKT HD SCREW M3x6 -09 59 ST1682302 St. Steel A4 BOSSARD : BN 6 DIN433-1 WASHER M3X6 -A4 10 59 DIN433-1 RONDELLE M3X6-A4 ST0399238 BOSSARD : BN 610 (1233130) St. Steel A2 ISO 4762 HEX SKT HD SCREW M3x12 108 11 ISO 4762 VIS CHC M3x12 ST1568803 St. Steel A2 Spring washers without nose DIN 108 12 127B-A2 B 3 ST1681945 St. Steel A2 Washers without chamfer DIN 433-A2 13 108 3,2/6/0,5 ST1681951 ISO 4014 M10x80-A4 St. Steel A4 HEX HD screw M10x80 14 OLD 47.62.82.371.2 Vis Tete Hexa M10x80 CAN BE HEAD SIZE DIN 933 ISO 4032 M10-A4 St. Steel A4 HEX NUT STYLE1 GRADE A M10 15 47.43.77.100.6 ECROU H STYLE1 GRADE A M10 ISO 7089_10x20-A4 St. Steel A4 NORMAL PL WASHER 10X20 16 47.78.15.010.4 RONDELLE PLATE NORMALE 10X20 CENBNFVD0002 WHERE USED [Last checked at 2023-03-20 11:18] DESIGNED E.SELETSKAYA DESIGNATION FD2 FC Long wall Bottom part A0 CHECKED RELEASED SCALE 1:20 APPROVED DESIGNED \oplus 2023-03-20 EQUIPMENT CODE CENBNFVD Vertical Detector Doc No: ST1688678_02 REFERENCES LABEL QAC SHEET CENBNFVD0013 NOT VALID FOR EXECUTION

com FC


FD2-VD Box Beams (process 422)





FD2-VD Assembly Stand (make 3)



FD2-VD FC Storage Cart (make 28)









Nov. 18, 2023

DUNE FD1 & FD2 FC Workshop 1

What do we need to do?

- Exercise, learn and adhere to the QA/QC procedures
- Procure all FRP and other parts
- Construct all tools for module assembly and installation
- Train for profile bending
- Train and get used to the different types of parts
- Exercise the parts preparations, along with the QA/QC procedure and the use of the QA/QC tool
- Construct the HD and VD assembly tables and exercise module constructions for training
- Exercise the 3D printing of the thin profile caps and the necessary QA/QC jigs
- Prepare for production readiness review (PRR) for both HD and VD parts production

Field Cage Installation Test Configuration


Two dummy LW modules with fiber conduits, and top profiles to demonstrate new fiber connection scheme

Make cathode/HV bus connections

Two full(?) LW modules with fiber conduits to demonstrate old fiber connection scheme.

Time and motion study on assembly speed.

Remaining LW modules are dummies with sparce profiles




What do we need to build for Mock-up?

Process and QC


- FRP Box beams: 2*16 + spare = 40
 - TFC Box beams: 2*4 + spare = 10
 - MFC Box beams: 2*8 + spare = 20
 - BFC Box beams: 2*4 + spare = 10
- FRP Box beam inserts: 3*2*4 + 10% = 24 + 2 = 26
- Al FC Column box beam top connector: 2*4 + 10% = 8+2
- SS FC Column yoke connector: 1*4 + 10% = 4+1
- TFC support plates: 2*2*4+spare = 20
- BFC constraining bracket: 1*2*4+spare = 10
- Steel Bottom stabilizer structure : 1*4 = 4
- Module installation cart: 1

Top VD FC Structures and Inserts






VD Top and Mid FC Module Parts



VD Bottom FC Module Parts




VD Field Cage Tools


One assembly station Modified NP02 version @ CERN



One installation cart → UTA to build one and ship to CERN



2 storage carts Available @ CERN with minor updates



Summary Table

Deliverable	Earliest Available Date	Relevant PRR Date
Full size FC assembly station	April 2024	June 2024
FC installation cart	May 2024	June 2024
FC storage cart	April 2024	June 2024
2 EW bottom FC modules	May 2024	June 2024
One middle corner FC module	May 2024	June 2024
One bottom corner FC module	May 2024	June 2024
12 dummy FC modules	June 2024	
4 sets of FC support FT	April 2024	June 2024
2 sets of FCSM beams	May 2024	June 2024

Group's 3E Motto

Demand Yourself Excellence!

Demand Each Other Excellence!

Help Each Other Become Excellent!