



# IFAST 3<sup>rd</sup> Annual meeting, April 2024

Nuria Catalan Lasheras. CERN


# OUTLINE

Reminder at the aim and objectives. HL-LHC needs

Progress report on the design and construction

Schedule and next steps

Conclusions




# High efficiency klystrons?

Klystrons in the market limited by an empirical dependence to perveance

Major CERN involvement on higher efficiency klystrons since 2017 led by I. Syratchev

New design rules for higher efficiency validated by powerful simulations (KLYC)

Industrial prototypes are being manufactured around the world



I. Syratchev


# Current LHC klystrons

- Total 16+14 THALES TH2167 klystrons
  - 300kW, CW saturated output power at 58kV 8.4A (62% efficiency)
  - Presently operated at ~220kW (-1.5dB below saturation)
- High Luminosity LHC upgrade will require more RF power
- At least 350 kW saturated output RF power per klystron
- At an operating point compatible with the existing power supplies ( ~58 kV x 9A)
- Need to increase the klystron efficiency to 67% min.





# Objective of I.FAST WP 11.2

- Design and build an industrial prototype of the LHC klystron reaching ~70% efficiency, in collaboration with THALES.
- In order to control the costs, the choice was made to retrofit the existing LHC klystrons, TH2167, with the aim of reusing some components (e.g. solenoid).
- Kick off meeting in Sept 2021



# Design and simulations

- Twelve months effort by CERN and THALES teams.
- Final design converged end 2022
  - Saturation at 70 W,
  - Voltage 57.7 kV
  - beam current 9A
  - reduced magnetic field on last two coils
- RF Efficiency = 69.84%
- PIC simulations verified by THALES






Figure 48 : Pumped TH2167 klystron view

Figure 49 : Pumped TH2167 HE klystron view

## New TH2167 HE klystron

Core Oscillation Mode (CS) method with six cavities including a second and third harmonic

Same electron gun and window

Slightly modified solenoid

New collector

Same frame and dressing as possible

# Hardware modifications

New collector:







- New design to stand a larger power and reduce local heat deposition
- Slightly longer length. Still compatible with frame and installation in LHC
- Modification of the piping

Solenoid:

- Re-distribution of coils longitudinally to adapt to the new geometry

Changes to the assembly technology

New tooling





# Updating the support frame

- Current frame needed modification to adapt to new radiation norms at CERN
  - 1uSv/h at 10cm from any accessible surface
- Lead and gridded panels added to the frame
- Connectors, cable routing, feedthroughs needed updating




Figure 72 : Removable shielding and grids



# Fabrication

St Paul sent back to Thales after a vacuum failure (SN.001)

Striped and dismantled


Vehicle test: Last two cavities fabricated and assembled

Successfully tested in vacuum and RF for tunability

Procurement of the dressed tube parts ongoing

Collector and gun ready





# Schedule


Assembly well advanced.  
Some procurement still on-going

Priority at Thales for assembly and procurement

CDR review initially split in two.  
Both done now

Klystron expected at CERN in July


Maintenance in Thales test facility may require the prototype to be tested directly at CERN



# Power balance (SAC recommendation)


**TH2167**

**AC/RF source efficiency 55.2%**





**HE TH2167**


**AC/RF source efficiency 60.3%**



# Power balance for pulsed RF sources



Transient losses



# Conclusion and Next steps

- Effort required to produce the prototype somehow underestimated
  - New norms, techniques, obsolescence, procurement difficulties...
- Prototype expected in summer and tested in Autumn
  - Still compatible with IFAST time frame
- Monthly follow-up meetings between CERN and THALES
- Maintenance of the Thales test facility to be monitored closely
- At CERN: Preparation of test facility in building 112
- Mutual interest in future collaborations beyond the current project

iFAST



Thanks



This project has received funding from the European Union's Horizon 2020 Research and Innovation programme under GA No 101004730.