
Half-Cylinder Thermal Cycling & Testing at Liverpool

Matt Brown, Tim Jones,

Frascati OEC Integration Workshop

31/01/24

Outline



- Use of Integration Cradles at Liverpool
 - Assembly area layout
 - Movements of Integration Cradles
- Integration Cradle Modifications
 - Limitations in length and width
 - Transition into Cold Room
- Half-cylinder Test Enclosure
 - General Requirements
 - Installation of Integration Cradle
 - Type-1 Services connections & Routing
 - Thermal cycling system (-55C)

Use of Integration Cradles at Liverpool

- Intention is to use tooling system designed by Frascati
- We have procured materials for TWO cradles and have plates being manufactured
 - We do need to understand the specification of a few components – particularly relating to the rotation mechanism
 - We also need to understand the precise details of how the system is intended to work and, eventually, to learn from experience at Frascati
- We have not done anything relating to the central support and slider mechanisms for the half-cylinder mating
 - We have a slight concern that the base, as designed, may not fulfil all the requirements we might have coming from space and access restrictions


Integration Cradle Modifications

- Sketch shows cradle located on sliders in 'open' position (136mm)
 - Shorten depth by (up to) 220mm to ease movement around cleanroom
 - Would have to REMOVE wheels before moving sliders to 'closed' position
 - What about the other orientation ?
 - Maybe OK at 100 reduction but not much more – every little helps!




Integration Cradle Modifications

- Beam supporting front wheels extended to avoid clashing with base
 - Extension of 125mm shown




Integration Cradle Modifications


- When the sliders are in their 'open' position – displaced by 136mm there is still 113mm of rail 'free'
 - Could the base be reduced by 2 x 100 mm making it 1700 wide ?




Critical Dimensions – Endcap Integration




Opening & Closing: HC at 880, Sliders at 0 (closed)




Opening & Closing: HC at 880, Sliders at 136



Opening & Closing: HC rolled over Sliders at 136




Opening & Closing: HC at Zero




Assembly of UK Endcap

- In the following I show ...
 - L2 half-cylinders being populated with Type-1 services & test
 - First L2 half-cylinder being populated with half-rings & connectivity checks. Second half-cylinder being populated with Type-1 services & test
 - First complete L2 half-cylinder being fully tested with CO₂. Second L2 half-cylinder being populated with half-rings & connectivity checks. L3 half-cylinders being populated with electrical services & test

L2: Services Loading



L2: Half-ring loading & Services Loading




Half-ring
loading & Test

Services
loading & Test

L2 Half-Cylinder Test & L2 Half-ring Loading

L3 Services Installation

L2 Half-cylinder Test & Thermal Cycle




L2 Half-ring loading & Test

L3 Services loading & Test

L2 Half-cylinder to Integration, 2nd L2 to Half-cylinder Testing, L3 Services Installation & test


L2 Half-cylinder Test & Thermal Cycle



L2 half-cylinder at Integration Station

L3 Services loading & Test


L2 Joining



Both L2 half-cylinders at
Integration Station


L3 Services
loading & Test

1st L2 Cradles to Loading Bay



L3 Cradle to Integration Stand-by, 2nd L3 displaced to allow 2nd L2 to transfer to Loading Bay


L3 cradle




2nd empty L2
cradle

L3 cradle


2nd L2 entering loading bay




L3 Cradles at Integration / Stand-by



First L3 at Half-ring Mounting & Test, 2nd L3 Parked, L4s - Services assembly & Test





Half-Cylinder Test Enclosure in -20°C Cold Room



Lukasz

DAQ

Half-Cylinder Test Enclosure




Access hatches
(1300 x 800)
for services
connections

Services feed-thru's

Top and front
removed for
clarity

Services Routing



-55°C Chiller

- Julabo Presto A70
 - Min temp = -70°C
 - Cooling power > 0.4kW @ -60°C



Cooling capacity 1								Medium: Ethanol
°C	20	0	-20	-40	-50	-60	-70	
kW*	1.12	1.1	0.98	0.9	0.69	0.45	0.23	

Cooling capacity 2								Medium: Ethanol
°C	20	0	-20	-40	-50	-60	-70	
kW*	1	0.91	0.8	0.75	0.55	0.38	0.12	

Cooling capacity 3								Medium: Thermal HL90
°C	20	0	-20	-30	-40	-50	-60	-70
kW*	0.96	0.87	0.8	0.76	0.72	0.61	0.35	0.12

Test Enclosure Mechanics

- Available cooling power sets the specification for the thermal enclosure
 - Need Heat leak < 0.6kW @ -60°C
 - $Q = k \cdot A \cdot \Delta T / t$
 - $Area = 2 \times (4 \times 1.7) + 2 \times (4 \times 1.5) + 2 \times (1.5 \times 1.7) = 24 \text{sqm}$
 - $t = 0.1 \text{m}$
 - $\Delta T = -35 \text{ }^\circ\text{C}$
 - $k = 0.05 \text{ W/mK}$
 - $Q = 420 \text{W}$
- Modular construction using metal-skinned foam cored sandwich panels would work well
 - Typical quoted $k < 0.03 \text{ W/mK}$
 - Need to watch for heat-leaks at joints
- Main issue is that what we want is very non-standard but early indications are positive – at a price !

