

# Construction and Operation of **DHCAL** prototype @ Fermilab **T**est **B**eam **F**acility

Lei Xia  
ANL\_HEP

# 1 m<sup>3</sup> – Digital Hadron Calorimeter Physics Prototype

## Description

Readout of 1 x 1 cm<sup>2</sup> pads with one threshold (1-bit) → **Digital Calorimeter**

38 layers in DHCAL and 14 in tail catcher (TCMT), each ~ 1 x 1 m<sup>2</sup>

Each layer with 3 RPCs, each 32 x 96 cm<sup>2</sup>

~480,000 readout channels

Layers inserted into the existing CALICE Analog (scintillator) HCAL and TCMT structures

## Purpose

Validate DHCAL concept

Gain experience running large RPC systems

Measure hadronic showers in great detail

Validate hadronic shower models

## Status

Started construction in 2008 - 09



**Finally, DONE! (produced 38+14 layers)**



# Collaboration and Responsibilities

Task	Institutes
Project coordination	Argonne
RPC construction	Argonne
Cassette structure	Argonne
Mechanical structure	DESY
Overall electronic design	Argonne
ASIC design and testing	FNAL, Argonne
Front-end and Pad board design & testing	Argonne
Data concentrator design & testing	Argonne
Data collector design & testing	Boston, Argonne
Timing and trigger module design and testing	FNAL, Argonne
DAQ Software	Argonne, CALICE
High Voltage system	Iowa
Low voltage system	Argonne
Gas mixing and distribution	Iowa
Cables	Argonne, Iowa
Data analysis	Argonne, FNAL, IHEP, Iowa, McGill, Northwestern, UTA

DHCAL Personnel	Heads
Engineers/Technicians	22
Students/Postdocs	8
Physicists	9
<b>Total</b>	<b>39</b>



# Outline

- RPC construction and testing
- Readout system fabrication and testing
- Cassette assembly and cosmic ray test
- Peripherals
- Operation at Fermilab test beam



# RPC Construction

## RPC design


- 2 – glass RPCs (**chosen for construction**)
- 1 – glass RPCs (developed at Argonne)
- Gas gap size 1.1mm
- Total RPC thickness < 3.4mm
- Dead area ~5% (frame, spacer)

## Chambers needed

~114 for DHCAL + 42 for TCMT + spares  
at the end, produced ~ **205** RPC's

## Assembly steps

- Spraying of glass plates with resistive paint
- Cutting of frame pieces
- Gluing frame
- Gluing glass plates onto frame
- Mounting of HV connection, etc.



# Spraying of the glass sheets

## Challenge

Produce a uniform layer with  $R_{\square} = 1 - 5 \text{ M}\Omega$

value affects pad multiplicity

value only critical for thin plate, thick plate can be lower/higher

## New paint (artist paint) identified

Reasonably cheap

Non toxic

2 component mixture (BLACK and GREEN)

Needs to be sprayed (built a spraying booth)

## Production

### Has been a struggle




Poor uniformity in a single plate

Mean value not well controlled from plate to plate

Low yield:  $\sim 60\%$  pass quality cut

Slow – barely match RPC assembly speed

### at the end, it worked out





# RPC Assembly


## Cutting frames

Dedicated (adjustable) cutting fixture  
Cut length to .2mm precision  
Drill holes



## Assembly

Dedicated gluing fixture  
Frame/gap glued to ~0.1mm precision  
Very time consuming process:  
~1 RPC/day/tech, 3 RPC produced/day



## Production

205 final RPC completed  
only ~10 not usable  
(due to glass broken or quality issues)



# Quality assurance



1 mil = 25  $\mu\text{m}$

RPC 001

## Pressure tests

Test with 0.3 inch of water pressure  
Pass if pressure drop < 0.02 inch in 30 seconds  
Chambers not passing 1<sup>st</sup> test are repaired  
All repaired chambers passed 2<sup>nd</sup> test


- Had ~5 leaking RPCs at the test beam (some due to glue damage)




## Gap size measurement

Thickness of all chambers measured along the edges  
(since glass is very uniform  $\rightarrow$  measure of gap size)  
Gap sizes at edges within 0.1 mm  
(central region uniform due to fishing lines)  
Corners typically thicker (up to 0.3 – 0.4 mm)  
(only affects very small region)

- > Only ~5 RPC's have low efficiency regions at corner(s) or along side(s), due to larger gap at those places, all replaced from prototype stack



RPC 012



## HV tests

Tests up to 7.0 kV before placing readout board on top  
(operating voltage is 6.3 kV)

- > NO HV issues at test beam, due to RPCs

HEP Lunch Seminar





# Cosmic Ray Test Stand I

(for first chambers)

Chamber characterization using cosmics and noise

Testing of early FE board versions

## Test stand

Up to 9 RPCs tested at once

## Operation of RPCs

High voltage scans from 5.8 to 6.8 kV



## Data taking

noise and cosmics




Triggered, trigger-less operation




## Triggered Data: Standard tests



## Trigger-less Mode Analyze Cosmic Rays Angle of Incidence Dependence!



# 2. Readout system overview



# The DCAL Chip

## Developed by


FNAL and Argonne

## Input

64 channels

High gain (GEMs, micromegas...) with minimum threshold  $\sim 5$  fC

Low gain (RPCs) with minimum threshold  $\sim 30$  fC



## Threshold

Set by 8 – bit DAC (up to  $\sim 600$  fC)

Common to 64 channels

## Readout

Triggerless (noise measurements)

Triggered (cosmic, test beam)

## Versions




DCAL I: initial round (analog circuitry not optimized)

DCAL II: some minor problems (used in vertical slice test)

DCAL III: no identified problems (final production: used in current test beam)

## Production of DCAL III





11 wafers, 10,300 chips, fabricated, packaged, tested







# DCAL III testing at Fermilab


- Fermilab Chip-Testing Robot
  - 78 parameters measured per chip
  - Test mode:
    - No cuts applied, Measure parameters
  - Checkout mode
    - Apply cuts, Robot sorts
  - Robots sorts good chips & bad chips into trays
  - ~1 minute per chip, ~400chips/day
- Result:
  - Yield 84% in single pass
  - Scanned the 'bad' chips again with loose cut to recover more chips (only need 5472 for the 1m<sup>3</sup> and 1872 for the TCMT)



# FrontEnd/DCON board + Pad board



- Build FE and pad boards separately to avoid blind and buried vias (cost and feasibility issue)
- Each board contains 1536 channels and 24 ASICs
- The data concentrator is implemented into the same board
- Glue the two boards together with conductive epoxy
- FE board need to pass computer test before gluing
  - Extensive tests (S-curves, noise rates...)
  - 3 – 6 hours/board
  - Accepted boards with less than 4/1536 dead channels





# Gluing fixture for Pad- and FE-boards

Goal: 1536 glue dots in less than 3 hours



## Fixture

Designed, built and commissioned

## Production

~25 minutes needed/board  
can glue > 10 boards/day

at the end: 300+ FE board fabricated/tested/glued



Controller



Solenoid valve

x axis motor and driver

y axis motor and driver

z slider


Glue Dispenser



# Data Collector Modules

1 Data Collector Module per 12 front-end boards  
Need 20 for DHCAL and 8 for TCMT

Designed, built and tested at Boston




# Timing and Trigger Module

Master TTM controls to up to 16 Slaves  
Slave TTM controls up to 16 Data Collectors  
Need 1 Master and 2 Slaves for DHCAL+TCMT



Designed and tested at FNAL





# Cassette assembly I

## Design




- 1 x 2mm copper sheet on readout side, in contact with ASIC packaging
- 1 x 2mm stainless steel sheet on RPC side

## Compression needed

- To ensure good thermal contact with ASICs
- To ensure good contact between RPCs and pad boards (minimizes pad multiplicity)

## Solution

- Use tensioned string between plates
- Several candidate strings tested with 4 - 5 pounds tension
- No significant drop over 30 days




# Cassette Assembly II

## Assembly

- Cassette is compressed horizontally with a set of 4 (Badminton) strings
- Strings are tensioned to ~20 lbs each, very few broken strings
- ~45 minutes/cassette

## Cassette Testing

- Cassettes were tested with CR before shipping to FTBF



**38+14 cassettes assembled**

# Peripherals

## Low Voltage Power Supply

Need power to 228+78 front-end boards (+5V)

Acquired 8 Wiener power supplies

← Built 8 power distribution boxes

## High Voltage Power supply

Need 6.3 kV to 38+14 layers (3 RPCs powered by 1 line)

Have 5 LeCroy 4032 power supplies

Have 2 sets of controllers

Developed computer control program

## Gas Supply

Need 19+7 lines (2 layers or 6 RPCs per line)

Built mixing rack for 3 gases

Built distribution rack







## Transportation to FNAL and installation





# Installation into CALICE structure at FNAL





**Installation complete**








## Cabling up

**12 hours of hard work  
(350,000 readout channels  
for the DHCAL alone!)**



# The RPC DHCAL Testbeam Story


Oct 2010

Testbeam  
DHCAL +  
NIU's  
Scintillator  
TCMT




At Fermilab


15-03-2011 11:21:15










# First beam: muons





One muon

Three muon

Four muon




A lot of muons




# Next: pions

60 GeV pions **measured** in DHCa1






# And also positrons



# And occasionally, neutral hadron



# Relatively smooth operation

- Biggest problem was the old LeCroy HV system
  - Consists of 4 Main Frames, 52+ channels
  - Lost in total 2 Main Frames and 22+ channels during last 3 test beam runs
  - At the end, can not repair fast enough → switched some ch's to Bertan supplies
  - In process of testing a new HV system
- Changed 3 FE boards
- Had 2 LV supply failures
  - 1 fuse blow → due to wrong fuse type
  - 1 OVP tripped → due to old supply + too low OVP threshold settings
- 1 LV distribution box channel repair → wrong wiring
  - 5V and GND connection reversed
- 1 DCol failure → some channels lost TS counter reset signal, replaced
- RPC issues
  - 5 replaced by spares: 4 leaky, 2 dead, 1 noisy
  - 2 pairs exchanged position (T  $\leftrightarrow$  B), to move inefficient region (corner, edge) to the outside
  - 14 RPC showed some level of overall inefficiency, after improved cooling
    - 12 in TCMT, 2 in 1m3
    - They are operated at 6.4 – 6.6 kV to compensate the inefficiency (nominal 6.3 kV), some are still bad
    - Considering some replacement before next beam test





# Summary

- The construction of the DHCAL prototype (+TCMT) is complete
- Test beam at Fermilab started last Oct., a lot of good data collected
- DHCAL prototype (+TCMT) works extremely well
- Operation is relatively smooth
- More test beam/more data is on the way

