

# MICE RFCC Module Update

Oxford, UK

July 7, 2011

---

Allan DeMello

Lawrence Berkeley National Laboratory

# Current Status of RFCC Module

---

- **RF Cavities:**

- All ten cavities (two spares) are currently at LBNL and four are measured (physically and for frequency)
- Received and accepted nine beryllium windows
- Ten ceramic RF windows received (4 at LBNL and 6 at University of Mississippi)
- Six full size tuner flexures will be fabricated using wire EDM (exploring vendor options)
- Components for 6 actuators are to be fabricated (not at UM)
- Measurements of the remaining six cavities to start in October
- Cavity inside surface mechanical smoothing and subsequent electropolishing to start in October at LBNL



# Current Status of RFCC Module

---

- **RF Cavities (cont.):**

- The cavities will be “tuned” to each other for a center frequency (10 cavities) by plastic deformation after frequency measurements are complete
- RF power coupler design and drawings are complete
- The single cavity vacuum vessel design has been sent out for fabrication quotes from Fermilab
- Fabrication of the single cavity vessel and associated components (e.g. RF couplers, RF tuners and actuators) will start soon
- Single cavity vessel testing will take place at MTA, Fermilab



# All Ten RF Cavities (Two Spares) at LBNL

Fabrication set-up cavity

One cavity on inspection stand



Six cavities in their shipping crates; three cavities are stored in another location



MICE RFCC Module Update - MICE CM30 at Oxford, UK


Allan DeMello- Lawrence Berkeley National Lab - July 7, 2011

Page 4




# Beryllium Windows

- Eleven Beryllium windows have been fabricated
- Nine are Ti-N coated and accepted
- Two windows were rejected due to excessive distortion
- Two more will be made by Materion Electrofusion (formerly Brush-Wellman) with proposed improved fabrication technique





# Toshiba Ceramic RF Windows



- An integral part of RF power (loop) coupler
- Ten Toshiba ceramic RF windows received by University of Mississippi
- Four delivered to LBNL for inspection, six remain at UM

MICE RFCC Module Update - MICE CM30 at Oxford, UK


Allan DeMello- Lawrence Berkeley National Lab - July 7, 2011

Page 6



# RF Cavity Frequency Tuner Components



- Dual – action actuator



- Flexure tuner arm

- RF cavity


# Cavity Frequency Tuner Flexure



- One tuner flexure has been fabricated at the University of Mississippi
- It has arrived at LBNL and has been inspected
- Water-jet cutting of the part left an unacceptable taper of the part wall
- The search for a suitable EDM machining vendor has started
- Secondary machining may be done at UM



# Actuator Component Fabrication



- Due to machining equipment limitations the actuator mechanical components can not be fabricated at the University of Mississippi
- Options for the fabrication of the actuator mechanical components are being explored by LBNL





# Cavity Tuner Control System



- Emerson ER3000 electronic pressure controllers have been tested at LBNL
- Pierrick Hanlet (Fermilab/IIT) will develop the control software in EPICS

# Cavity Measurements



- Cavity physical measurement
- Cavity frequency measurement
- The remaining six cavities will be measured (both physically and for frequency) starting in October 2011
- Physical measurements for the six remaining cavities expected to take approximately 1-1/2 weeks (60 hours)

MICE RFCC Module Update - MICE CM30 at Oxford, UK

Allan DeMello- Lawrence Berkeley National Lab - July 7, 2011

Page 11







# Cavity Electropolish at LBNL



Jlab EP set-up



Cavity section view



- The inner surface of each cavity will be mechanically smoothed and then electropolished at LBNL using the techniques developed at JLab for the prototype cavity
- EP setup and testing will start in October of this year
- Electropolishing process will take approximately 3 days for each cavity or 6 weeks to complete all 10 cavities




# Cavity Frequency Tuning

- Cavities must be “tuned” to each other for a center frequency (10 cavities) by plastic deformation if necessary
- Will be done at LBNL after frequency measurements and electropolishing are complete
- A 12 ton press will be used for adjusting the frequency
- Design of fixturing is ongoing




12 ton press




Press from outside

# RF Power (loop) Coupler



- MICE RF power coupler design is complete and ready for fabrication
- Fabrication of the couplers will start soon
- Testing/experience of the prototype cavity at MTA: sparking at the coupler
- The coupler design will have a slightly increased gap spacing
- The sparking region can be Ti-N coated if necessary (will be tested at MTA using the prototype cavity)
- Adding diagnostics: arc detector at the coupler region



# Single RF Cavity Vacuum Vessel



Single Cavity Vacuum Vessel Exploded View

# Single RF Cavity Vacuum Vessel

- Design drawings have been sent out to vendors for fabrication quote (from Fermilab)
- Fermilab has received quotes and will award fabrication contract soon
- Kept the same dimensions and features of the MICE RFCC vacuum vessel (as much as possible)
- One vessel designed to accommodate two types of MICE cavities (left and right)




Single cavity vessel in Fermilab MTA configuration with the MUCOOL coupling coil



# Advantages of Single RF Cavity Vacuum Vessel for MICE

Prior to having MICE RFCC module, the single cavity vessel will allow us to:

- Check engineering and mechanical design
- Test of the RF tuning system with 6 tuners and actuators on a cavity and verify the frequency tuning range
- Obtain hands-on experience on assembly and procedures
  - Cavity installation
    - Beryllium windows
    - RF couplers and connections
    - Water cooling pipe connections
    - Vacuum port and connections
    - Tuners and actuator circuit
  - Aligning cavity with hexapod support struts
  - Vacuum vessel support and handling
  - Verify operation of the getter vacuum system
- Future LN operation



Single cavity vessel in Fermilab MTA configuration with the MUCOOL coupling coil

# RFCC Future Work

---

- **Vacuum Vessel:**

- Vessel design is complete but needs to be updated to incorporate changes to the interface with the new coupling coil cryostat design
- Fixturing for the assembly process needs to be finalized and drawings for fabrication generated

- **RFCC Module:**

- Finalize fixturing for module assembly and shipping
  - for aligning the frequency tuners onto cavities
  - for inserting the cavities into vacuum vessel
  - shipping skid/tilt fixturing for shipping RFCC to RAL



# Plan and Schedule

---

- RFCC module schedule is mainly determined by the schedule of CC magnets and available funding
  - See Derun Li's and Steve Gourlay's talks from yesterday
- RF cavity work has been on-hold to save resources for SS (highest priority) and CC magnets and will resume October 2011
  - RF cavities, post processing and associated accessory components are under control at LBNL
- Schedule of RFCC fabrication is being developed, testing of the 1<sup>st</sup> CC cold mass dominates the current schedule

