



Cryogenics for the IFMIF-DONES deuteron accelerator

Industry Workshop on Cryogenics in Big Science | 16th April 2024

César Caballero Pérez (IFMIF DONES)
Arnaud Madur (CEA)




This work has been carried out within the framework of the EUROfusion Consortium, funded by the European Union via the Euratom Research and Training Programme (Grant Agreement No 101052200 — EUROfusion). Views and opinions expressed are however those of the author(s) only and do not necessarily reflect those of the European Union or the European Commission. Neither the European Union nor the European Commission can be held responsible for them.

**1****Introduction to the IFMIF-DONES Facility****2****Accelerator Engineering Validation: LIPAc****3****DONES Cryomodules****4****DONES Cryoplant and Cryodistribution****5****Next steps and conclusions**

Main Objective: material qualification for fusion reactors.


International Fusion Materials
Irradiation Facility - DEMO
Oriented Neutron Source



- 40 MeV Deuteron Accelerator. 125mA.
- 25 mm-thick Liquid Li target to produce neutron flux $> 10^{18} \text{ m}^{-2}\text{s}^{-1}$
- Test modules to irradiate samples of materials.



IFMIF DONES Facility

The site is located at Escúzar -18 km southwest from Granada city- Spain






Accelerator Systems

Operational at least 255 days/year
(70% Operational Availability).



~100m total

- D+ CW beam
- 125 mA / 40 MeV
- Windowless liquid Li target
- 30 years of Operation,
- Hands-on maintenance, almost all.
- RH target and near rooms



**1**

Introduction to the IFMIF-DONES Facility

2

Accelerator Engineering Validation: LIPAc

3

DONES Cryomodules


4

DONES Cryoplant and Cryodistribution




5

Next steps and conclusions

Liner IFMIF Prototype Accelerator (LIPAc) for the engineering validation. Currently on-going.
 D+ CW beam 125 mA / 9 MeV



Already achieved **5 MeV - 125 mA**
625 kW, pulsed (up to 0.1 % duty)
 in Phase B



In Phase C. The cryomodule will be assembled in the Vault.


Cavity-coupler connection by Research Instrument in Sep 2022




© 2024 IFMIF/EVEDA Project

Cryogenics circuits

- LHe 4.5K He saturated conditions.
 - Each RF and solenoid cavity.
- GHe 4.5K He from phase separator.
 - RF couplers.
 - Current Leads cluster.
- GHe 50K He.
 - Thermal Shield



Side Loading of Cavity String





Cold Mass: 2000kg



- 1** Introduction to the IFMIF-DONES Facility
- 2** Accelerator Engineering Validation: LIPAc
- 3** DONES Cryomodules
- 4** DONES Cryoplant and Cryodistribution
- 5** Next steps and conclusions


Five Cryomodules in DONES



Design of the cryomodule very similar to LIPAc and to SARAF.




Cryomodule	CM1	CM2	CM3	CM4	CM5
HWR beta optimum	Low 0.116	Low 0.116	High 0.179	High 0.179	High 0.179
Elementary sequence	1 solenoid + 1 cavity	1 solenoid + 2 cavities	1 solenoid + 2 cavities	1 solenoid + 2 cavities	1 solenoid + 2 cavities
Number of elementary sequence	8	5	4	4	4
Inlet section	none	1 solenoid + 1 cavity	1 solenoid + 1 cavity	1 solenoid + 1 cavity	1 solenoid + 1 cavity
Output energy (MeV)	8.3	13.9	21.3	30.3	40

Differences with LIPAc



Design of Cryomodules is well advanced

Cryogenic Circuits




Same Cryogenics Circuits as in LIPAc:

- LHe 4.45K He saturated conditions.
 - Each RF and solenoid cavity.
- He 4.45K He from phase separator.
 - RF couplers.
 - Current Leads cluster.
- GHe 60K He.
 - Thermal Shield


Thermal Budget

Cryomodule: Heat Loads in 4K Circuit						
	CM1		CM2		CM3 - CM4 - CM5	
Static Heat Loads	32.7 W	9.63l/h	36.6 W	9.594 l/h	32.1 W	7.916 l/h
Dynamic Heat Loads	56 W	6.42 l/h	77 W	6.396 l/h	66.6 W	5.277 l/h
Total Heat Loads	88.7 W	16.05 l/h	113.6 W	15.99 l/h	98.7 W	13.19 l/h
Cryomodule: Heat Loads in 60K Circuit						
	CM1		CM2		CM3 - CM4 - CM5	
Static Heat Loads	173.7 W		178.6 W		177.7 W	
SRF Linac Requirement			Without margins	With margins		
Total Heat Loads on 4K	Refrigeration Part		498 W	648 W		
	Liquefaction Part		72 l/h	99 l/h		
Total Heat Loads on 60K			885 W	1328 W		




Cryogenic Studies: Cool-down time and Flow Rates

- Cool-down time calculation. 65 hours
- Flow Rates calculation.
- Valve Opening Studies



Cold mass temperature (K)		Helium flow rate (g/s)		ΔT (K)
		To the shield	To the cold mass	
300	> 230	9.0	20.0	50
230	> 100	10.5	20.0	50
100	> 60	22.0	20.0	50
60	> LHe	30.0	20.0	50

Safety Devices in the Cryomodules



Currently Simulations of accident scenarios of Helium release are being performed.

- MELCOR
- OpenFoam

**1**

Introduction to the IFMIF-DONES Facility

2

Accelerator Engineering Validation: LIPAc

3

DONES Cryomodules

4

DONES Cryoplant and Cryodistribution

5

Next steps and conclusions

Cryoplant Preliminary Design

Still in preliminary design of the cryoplant and cryo-distribution.

- Design will advance from conceptual to detailed design.
- Review of the design performed by experts of other facilities.




Cryomodules




Cryoplant

Sample Picture



Cryoplant Preliminary Design





Cryo-production:

- Compressor Station. Two He compressors with oil removal system to supply the ColdBox with Helium.
- Cold Box: Where the liquefaction of Helium occurs. Claude Cycle.

Cryo-distribution:

- LHe Dewar. Storage of LHe in case of failure of Cold Box.
- Valve Boxes. Where the Joule Thomson Valves are located with the rest of the valves that connect to the cryomodules.
- Valve Panels: Used in the cool down process only, it allows a connection from the 60K GHe line.


Cryoplant Claude Cycle T-S diagram




Typical Claude Cycle:

- 7 Heat Exchangers in series
- 2 turbines in series
- One last expansion super critical Helium
- Phase change done in the JT valve in valve box.

From preliminary Study. Still needs to be determined.



Cryodistribution of Cryomodule 1




Valve Box in LIPAc




© 2024 IFMIF/EVEDA Project

Cryo Transfer Line in LIPAc



Cooling Down Principle



1. From 300K to 110K
2. From 110K to 60K
3. From 60K to 5K
4. Nominal Operation

**1**

Introduction to the IFMIF-DONES Facility

2

Accelerator Engineering Validation: LIPAc

3

DONES Cryomodules

4

DONES Cryoplant and Cryodistribution

5

Next steps and conclusions



- Cryomodule design is well advanced, including part of the cryo-distribution.
- Cryoplant still in preliminary design. Steps towards a detailed design must be taken.
 - 3D models
 - Detailed P&IDs
 - Thermal budget requirement including the cryo-distribution.
- Still awaiting final feedback from LIPAc, when the cryomodule is installed and the first cool down is performed. However, a lot of feedback has already been considered in the design.

Many Thanks for your attention!