



Cryogenic Insertion Devices at SOLEIL



I) Generalities

- Undulators at SOLEIL
- Cryogenic Undulators

II) Design

- Magnetic
- Mechanical

III) Construction & optimisations

- At room temperature
- At cryogenic temperature

IV) Installation on the ring

- Electron beam measurements
- Photon beam measurements





Figure 1 : Photon beams from a standard in-vacuum ID and a cryogenic ID

SOLEIL I parameters

- 3rd generation light source
- Energy : 2.75 GeV
- Current : 500 mA
- Emittance: 3.9 nm.rad
- Energy spread : 0.1%
- Coupling : 1%



SOLEIL II parameters

- 4th generation light source
- Energy : 2.75 GeV
- Current : 500 mA
- Emittance: 80 pm.rad
- Energy spread : 0.1%
- Coupling : 1%



Figure 2 : Synchrotron SOLEIL buildings



Figure 3 : HU640



Figure 4 : HU256

Beamline	Source	Period (mm)	Nb. periods	Gap (mm)	Bz (T)	Bx (T)
Désirs	HU640	640	14	19	0.11	0.09
Cassiopée	HU256	256	12	50 (H) 15 (V)	0.40	0.28
Pléiades	HU256	256	12	50 (H) 15 (V)	0.40	0.28
Antarès	HU256	256	12	50 (H) 15 (V)	0.40	0.28
Deimos	HU65	65	24	15.5	0.25	0.25 (PM)

Table 1 : List of electromagnetic devices installed on SOLEIL I storage ring

Beamline	Source	Type	Period (mm)	Nb.	Gap (mm)	Bz (T)	Bx (T)	PM Grade
Tempo	HU80	Apple II	80	19	15.5	0.98	0.75	NdFeB
Pléiades	HU80	Apple II	80	19	15.5	0.98	0.75	NdFeB
Sextants	HU80	Apple II	80	19	15.5	0.98	0.75	NdFeB
Hermès	HU64	Apple II	64	25	15.5	0.86	0.62	NdFeB
Cassiopée	HU60	Apple II	60	27	15.5	0.8	0.55	NdFeB
Antarès	HU60	Apple II	60	27	15.5	0.8	0.55	NdFeB
Deimos	HU52	Apple II	52	31	15.5	0.77	0.52	NdFeB
Lucia	HU52	Apple II	52	31	15.5	0.77	0.52	NdFeB
Tempo	HU44	Apple II	44	36	15.5	0.64	0.4	NdFeB
Sextants	HU44	Apple II	44	36	15.5	0.64	0.4	NdFeB
Sextants	HU42	Apple II	42	34	15.5	0.58	0.37	NdFeB
Sirius	HU36	Apple II	36	44	15.5	0.75	0.53	NdFeB

Table 2 : List of PM devices providing helical polarization installed on SOLEIL I storage ring



Figure 5 : APPLE II ID




Figure 6 : 8-axis APPL EII ID

Beamline	Source	Type	Period (mm)	Nb.	Gap (mm)	Bz (T)	Bx (T)	PM Grade
PX2	U24	In-vacuum	24	80	5.5	0.84		NdFeB
PX1	U20	In-vacuum	20	106	5.5	0.96		SmCo
Cristal	U20	In-vacuum	20	106	5.5	0.96		SmCo
Swing	U20	In-vacuum	20	106	5.5	0.96		SmCo
Sixs	U20	In-vacuum	20	106	5.5	0.96		SmCo
Spare (x1)	U20	In-vacuum	20	106	5.5	0.96		SmCo
Spare (x2)	U20	In-vacuum	20	106	5.5	1.06		NdFeB
Galaxies	U20	In-vacuum	20	106	5.5	1.06		NdFeB
Psyché	WSV50	In-vacuum wiggler	50	40	5.5	2.1		NdFeB
Puma	W164	Out-vacuum Wiggler	164	20	15.5	1.8		NdFeB
Nanoscopium	U18	Cryogenic	18	106	5.5	1.16		PrFeB
Anatomix	U18	Cryogenic	18	106	5.5	1.16		PrFeB
Coxinel	U18	Cryogenic	18	106	5.5	1.16		PrFeB
R&D	U15	Cryogenic	15	200	3	1.16		PrFeB

Table 3 : List of PM devices providing linear horizontal polarization installed on SOLEIL I storage ring



Figure 7 : In-vacuum Wiggler



Figure 8 : Cryogenic undulator

High energy photons produced by the in-vacuum undulators IVUs




Figure 9 : Brightness produced by SOLEIL IIDs

How to gain brightness at high energies?

Reaching more brightness at high energies implies

- ➔ more interferences : increasing the total nb of periods
 - ❑ building longer IDs
 - ❑ Reducing the period length
- ➔ higher peak field : **cryogenic undulators**




Figure 10 : Brightness of a 20 mm period NdFeB undulator compared with a 18 mm period PrFeB cryogenic undulator

Factor of 3 at 30 keV on the brightness

Cryogenic undulators at SOLEIL

- CPMU18 n°1 : installed for Nanoscopium long beamline in 2011
- CPMU18 n°2 : used for COXINEL since 2015 and will be installed on Cristal beamline in 2024
- CPMU18 n°3 : installed for Anatomix long beamline in 2017
- CPMU15 : under construction




Figure 11 : CPMU18 undulators in the SOLEIL I ring, dedicated to Anatomix & Nanoscopium beamlines

Magnetic design




Figure 12 : Dependence of magnets remanent field with temperature

NdFeB magnets

- Undergoes SRT below 120 K
- Coercivity keeps increasing
- Heaters have to be installed along the ID
- B_r variation at 77 K : -0.1%/K




Figure 13 : Dependence of magnets coercivity with temperature

PrFeB magnets

- Can be cooled down directly to 77 K
- Reaches higher field
- Coercivity keeps increasing
- B_r variation at 77 K : -0.02%/K

CPMU18 mechanical design




Figure 14 : Radia model of the CPMU18 n02 and 3 with magnets (blue) and half poles (green)




Figure 15 : Magnetic field of the CPMU18 generated at 300 K and 77 K

Item	Unit	Value
Technology		Hybrid
Magnet material		CR53
Remanence	T	1.35 @ 300 K 1.57 @ 77 K
Coercivity	T	1.63 @ 300 K 7.6 @ 77 K
Magnet size (x, z, s)	mm ³	50 × 30 × 6.5
Pole material		Vanadium Permendur
Pole size (x, z, s)	mm ³	33 × 22 × 2.5 33 × 22 × 1.25
Period	mm	18 @ 77 K
Gap range	mm	5.5 to 30
Length	m	2
Peak field	T	1.155

Table 4 : Main characteristics of the CPMU18

- At 300 K, $B_z = 1.005 \text{ T} @ 5.5 \text{ mm}$
- At 77 K, $B_z = 1.155 \text{ T} @ 5.5 \text{ mm}$

CPMU18 mechanical design





Figure 16 : Drawing of the CPMU18 undulator



Figure 17 : In-vacuum girders of CPMU18

- Out/in-vacuum girders connected by 24 rods
- Cooling down by injecting LN2 through a 10mm hole in the aluminium girders
- No baking



CPMU15 mechanical design




Figure 18 : Drawing of the CPMU15 undulator

- Out/in-vacuum girders connected by 36 rods
- Cooling down by injecting LN2 through a 10mm hole in the aluminium girders
- No baking

Item	Unit	Value
Technology		Hybrid
Magnet material		CR53
Remanence	T	1.32 @ 300 K 1.55 @ 77 K
Coercivity	kA/m	1016 @ 300 K 1906 @ 77 K
Magnet size (x, z, s)	mm ³	50 × 30 × 5.5
Pole material		Vanadium Permendur
Pole size (x, z, s)	mm ³	33 × 22 × 1
Period	mm	15 @ 77 K
Gap range	mm	3 to 30
Length	m	3
Peak field	T	1.735

Figure 19 : Main characteristics of the CPMU15

- At 300 K, $B_z = 1.59 \text{ T @ } 3 \text{ mm}$
- At 77 K, $B_z = 1.735 \text{ T @ } 3 \text{ mm}$

CPMU18 modules design




Figure 20 : Radia model of the full pole structure of CPMU18 n°1




Figure 21 : Radia model of the half-pole structure of CPMU18 n°2, 3 and CPMU15

Advantages of the half-pole structure :

- All identical modules
- Increased number of possibilities during the assembly
- Enables swapping for magnetic corrections




Figure 22 : Mech. Design of holders for CPMU18 n°2, 3 and CPMU15

Assembly at room temperature

Objective : Build an ID with an optimized phase error directly after the assembly without doing any shimming/swapping




Figure 23 : Relative difference of the total magnetic moment on magnet batch of CPMU18 n°2 & 3




Figure 24 : North/South effect on magnets batch of CPMU18 n°2 & 3

Assembly at room temperature



Figure 25 : Hall probe and rotating coil meas.

- Poles adjusted with 10 um copper shims
- Modules removed if
 - > 1% on average peak field
 - > 1% on N/S diff.




Figure 27 : Magnetic measurements using a robotic arm



Figure 26 : Robotic arm in action

New magnet holder : Super-module




Figure 28 : Supermodule design

LEAPS funding WP6.2 : Construction of a short period cryogenic permanent magnet undulator

- Magnets are assembled first
- Then poles inserted by the bottom
- Poles can be adjusted in angle or altitude thanks to magnets using 2 screws



Figure 29 : Prototypes of supermodules

New magnet holder : Super-module



Figure 30 : Robotic arm adjusting a Supermodule



This Supermodule has been designed to be fully optimized thanks to a robotic arm

- 3 lasers to measure magnets/pole
- 1 screw driver

Adjustment below 5 μm with very good agreement thanks to our standard meas. tools




Figure 31 : Comparison of the altitudes on a Supermodule using different tools

New magnet holder : Super-module



Figure 32 : Robotic arm scanning the supermodule with a 3D Hall probe

Magnetic adjustment using a 3D Hall probe to correct for magnetic errors





Figure 33 : Reconstructed magnetic field profile

Assembly of the undulator

Period by period modules are sorted and assembled on the two girders:

- 2 modules on the lower girder and 2 on the upper one
- Adjusted at +/-15 um
- Shimmed with specific values (function of the long. pos. and magnet errors)
- Measurement of all the periods
- IDBuilder >> choose the 4 convenient consecutive modules that fit defined tolerances and weight

Evaluation:



Variation Operators for Permutations:

Mutation : - e.g. swap items (magnets) at two randomly chosen positions - [5 4 8 1 7 2 6 3]

Crossover : - e.g. «order 1» - [1 2 3 4 5 6 7 8]
 [3 5 6 8 1 2 7 4] ⇒ [??? 4 5 6 7 ?]

Figure 34 : IDBuilder scheme

Assembly of the undulator

CPMU18 n°1

- 100 periods @ 5.5 mm
- Tapper correction
- Rods adjustments
- 92 elements shimmed

>> phase error : 2.8°

CPMU18 n°2

- 100 periods @ 5.5 mm
- Tapper correction
- Rods adjustments
- No shimming

>> phase error : 2.3°

CPMU18 n°3

- 100 periods @ 5.5 mm
- Tapper correction
- Rods adjustments
- No shimming

>> phase error : 2.45°

CPMU15 n°1

- 200 periods @ 3 mm
- Tapper correction
- Rods adjustments
- No shimming

>> phase error : 3.5°




Figure 35 : Trajectories of the CPMU18 at room temperature

Cooling/Warming undulators using a Cryotherm cryo-cooler




Figure 36 : Cooling down of the undulator

- 36 hours to reach 77K
- More than a decade gain on the vacuum pressure




Figure 37 : Warming up

- Natural warming : 72 hours
- Warming using nitrogen gas : 24 hours

In more than 10 years of operation only one incident impacting the beam (not due to cryo-cooler)

Embedded measurement benches: ID correction in final configuration at 77 K




Figure 38 : CPMU18 with in-situ Hall probe bench

- Hall probe installed on a carriage
- Stepper motor via magn. Coupling
- Girder thermalized
- Heidenhein encoder for long.pos
- Triggers from Renishaw interferrometer




Figure 39 : CPMU18 with in-situ stretched wire bench

- 100 um tungsten wire
- Stretched under 10 N
- Keithley 2182A nanovoltmeter

Mechanical changes at 77 K

- Gap opening due to rods contraction : 1.3 mm (wire measurements)
 - Magn. gap @ 300 K : 5.5 mm
 - Mech. gap @ 300 K : 5 mm with stretched wire
 - Mech. gap @ 77 K : 6.3 mm with stretched wire
- Girders long. contractions (12 mm) : period reduced from 18.16 to 18.04 mm




Figure 40 : Vertical magnetic field profiles @ 330 K and 77 K after gap correction

Rods adjustments

>>. Phase error reduction from 10 to below 3°





Figure 41 : Abs. values of the peak field versus long. position before rods adjustments




Figure 42 : Abs. values of the peak field versus long. position after rods adjustments




Figure 43 : Vert. peak field vs gap at 300 K and 77 K




Figure 44 : H and V trajectories at 300 K & 77 K




Figure 45 : Radiation spectrum of the CPMU18#3 at 77 K




Figure 46 : Pointing variations between 5.5 to 30 mm gaps

Electrons beam based alignment

- Mech. Alignment for meas bench
- Electron beam alignment
 - Electron beam decay
 - Vertical betatron tune shift variations




Figure 47 : Betatron tune shift variations while moving the offset of the CPMU18#1




Figure 48 : Vertical emittance variations versus gap of CPMU18#3




Figure 49 : Lifetime variations versus gap of CPMU18#3

Photons beam based alignment : offset adjustment

- Observation at 77 m from the source point
- Observation slit : 100 μm x 100 μm
- 11th harmonic at 16.5 keV





Figure 50 : 11th harmonic of the CPMU18#1 while moving offset from -0.1 to 0.4 mm



❖ New offset : 100 μm

Figure 51 : Energy and bandwidth of the 11th harmonic of the CPMU18#1 while moving the offset from -0.1 mm to 0.4 mm

Photons beam based alignment : taper adjustment

- Change the peak field along the longitudinal axis
- Taper can be changed between +/-500 μm




Figure 52 : 11th harmonic of the CPMU18#1 while changing the taper from -0.05 mm to 0.05 mm




Figure 53 : Energy and bandwidth of the 11th harmonic of the CPMU18#1 while moving the taper from -0.05 mm to 0.05 mm




Figure 54 : Comparison of the spectra of CPMU18#1 calculated from magnetic meas. using SRW and the one measured on Nanoscopium beamline at 5.5 mm gap




Figure 55 : Comparison of spectra of an ideal CPMU18 and the one measured on Nanoscopium beamline at 5.5 mm gap

CPMU18#1

- First full-scale PrFeB CPMU in operation since 2011 for Nanoscopium beamline
- Photon beam alignment with the beamline have been performed
- The quality of the CPMU is in good agreement with the calculations

CPMU18#2

- Low phase error value has been achieved directly after assembly
- Radiation has been observed on COXINEL experiment with a LPA beam after 8m of controlled electron beam transport
- Will be installed on the ring this summer 2024

CPMU18#3

- Low phase error value has been achieved directly after assembly
- Installed on the ring since 2018
- Electrons and photons beams measurements are in good agreement with what was expected

CPMU15#1

- Low phase error value has been achieved directly after assembly
- Has to be cooed down

CPMU12 (LEAPS)

- New design implemented with Supermodules (can be optimized and measured with a robot)
- 1m long prototype will be ready T4 2024
- New Hall probe bench is under design to be tested on this prototype