

# Estimated beam characteristics from the upgraded injectors

R. Garoby for the LIU Project Team





- **Planned actions**
- Status of investigations
- Estimated beam characteristics
- Planning
- Summary



# Principles of action

## To increase performance

### Brightness ↗

- ⇒ Increase injection energy in the PSB from 50 to 160 MeV, Linac4 (160 MeV H<sup>-</sup>) to replace Linac2 (50 MeV H<sup>+</sup>)
- ⇒ Increase injection energy in the PS from 1.4 to 2 GeV, increasing the field in the PSB magnets, replacing power supply and changing transfer equipment
- ⇒ Upgrade the PSB , PS and SPS to make them capable to accelerate and manipulate a higher brightness beam (feedbacks, cures against electron clouds, hardware modifications to reduce impedance...)

## To increase reliability and lifetime (until ~2030!) (tightly linked with consolidation)

- ⇒ Upgrade/replace ageing equipment (power supplies, magnets, RF...)
- ⇒ Procure spares
- ⇒ Improve radioprotection measures (shielding, ventilation...)




- Planned actions
- **Status of investigations**
- Estimated beam characteristics
- Planning
- Summary




# Present focus: debugging of transverse emittance measurement – Emittance evolution from PSB to SPS

A. Guerrero  
§ H. Bartosik



Emittance preservation (?) between PS @ 26 GeV and SPS flat bottom



Emittance preservation (?) between PSB and SPS flat bottom



# Puzzle: SPS performance in 2011 wrt 2010?

H. Bartosik

No dedicated measurements of emittance as function of intensity in 2010


- In 2010, emittance blow-up in PS was necessary in order to reduce blow-up in the SPS nominal optics
- In low  $\gamma_t$  optics, no blow-up in PS was necessary

Dedicated measurements in 2011


- 2010 results for low  $\gamma_t$  optics confirmed (or outreached)
- No additional blow-up in PS needed for nominal optics – in general beam is more stable
- First measurement of emittance for high intensity in nominal optics shows promising results

## What is different in 2011? Why is beam is so much more stable?

Emittances measured 2010, intensity corrected for losses



Nominal SPS optics, end of flat bottom (26 GeV/c)





- Planned actions
- Status of investigations
- **Estimated beam characteristics**
- Planning
- Summary


# Caveat...

- Beam parameters are given at injection in LHC: beam loss and blow-up inside the LHC are not accounted for.
  
- All necessary improvements are implemented in the injectors (Linac4, PSB to PS transfer at 2 GeV, coupled bunch instabilities suppressed, e-cloud suppressed, hardware upgraded...)
  
- Estimated beam degradation in the accelerator chain (based on observations in 2010):
  - ✓ PS: 5 % beam loss, 5 % transverse blow-up
  - ✓ SPS: 10 % beam loss, 5 % transverse blow-up.
  
- RF gymnastics being kept, imperfections are unchanged:
  - ✓ +/-10 % fluctuation of all bunch parameters within a given PS bunch train.
  - ✓ Traces of ghost/satellite bunches.






# Beam parameters: Comments




# Beam parameters at LHC injection [50 ns]






# Beam parameters at LHC injection [50 ns]






# Beam parameters at LHC injection [25 ns]





# Beam parameters at LHC injection [25 ns]





- Planned actions
- Status of investigations
- Estimated beam characteristics
- **Planning**
- Summary



# Overall LIU Planning

	Linac4	PS injector, PS and SPS	Beam characteristics at LHC injection
<b>2011 - 2012</b>	Continuation of construction...	<ul style="list-style-type: none"> <li>• Beam studies § simulations</li> <li>• Investigation of RCS option</li> <li>• Hardware prototyping</li> <li>• Design § construction of some equipment</li> <li>• TDR</li> </ul>	25 ns, $1.2 \cdot 10^{11}$ p/b, <b>~2.5 mm.mrad</b> 50 ns, $1.7 \cdot 10^{11}$ p/b, <b>~2.2 mm.mrad</b> 75 ns, $1.2 \cdot 10^{11}$ p/b, $\leq 2$ mm.mrad
<b>2013 – 2014</b> (Long Shutdown 1)	<ul style="list-style-type: none"> <li>• Linac4 beam commissioning</li> <li>• Connection to PSB ?</li> </ul>	<ul style="list-style-type: none"> <li>• PSB modification (H<sup>-</sup> injection) ?</li> <li>• PSB beam commissioning ?</li> <li>• Modifications and installation of prototypes in PS and SPS</li> </ul>	
<b>2015 - 2017</b>	<ul style="list-style-type: none"> <li>• Progressive increase of Linac4 beam current</li> </ul>	<ul style="list-style-type: none"> <li>• If Linac4 connected: progressive increase of PSB brightness</li> <li>• Some improvement of PS beam (Injection still at 1.4 GeV)</li> <li>• Equipment design § construction for PS injector, PS and SPS</li> <li>• Beam studies</li> </ul>	<ul style="list-style-type: none"> <li>• Limited gain at LHC injection (pending PSB (or RCS), PS and SPS hardware upgrades)</li> </ul>
<b>2018</b> (Long Shutdown 2)		<ul style="list-style-type: none"> <li>• Extensive installations in PS injector, PS and SPS</li> <li>• Beam commissioning</li> </ul>	
<b>2019 –2021</b>			After ~1 year of operation: beam characteristics for HL-LHC...



- Planned actions
- Status of investigations
- Estimated beam characteristics
- Planning
- **Summary**



# Summary

- ➡ **MDs during 2011-2012 are essential to refine the knowledge and understanding of the injectors and to check the potential of upgrades.**
- ➡ **Preliminary requirement/First goal: getting confidence in beam instrumentation => Extensive debugging: progressing well, but time – consuming...**
- ➡ **Recent observations in 2011 tend to demonstrate that the accelerators perform better than in the previous years. Not fully understood.**
- ➡ **Need to interact with HL-LHC for selecting reachable beam parameters. Main purpose of the present meeting!**
- ➡ **Irrelevant to the decision to connect Linac4 to the PSB during LS1 and to the choice between PSB/RCS, the beam characteristics specified for LIU will be met some time after the end of LS2 (~2020).**



**THANK YOU  
FOR YOUR ATTENTION!**





# Reference



# Why is today's beam better than nominal?



*Simple! No more blow-up along the accelerators cascade...*

- PSB:
  - Improved (achromatic) optics in the Linac2 to PSB transfer line since 2005  
[\[http://khanke.home.cern.ch/khanke/papers/2006/ab\\_note\\_2006\\_001.pdf\]](http://khanke.home.cern.ch/khanke/papers/2006/ab_note_2006_001.pdf)
- PS:
  - Injection trajectories
  - Working point along the whole cycle
  - Transition
- PS to SPS:
  - Transverse matching with better optics in TT2-TT10

**WARNING: NO MARGIN LEFT!**



# Spare slides




- **Planned actions**
- Status of investigations
- Estimated beam characteristics
- Planning
- Summary



# Linac4: Commissioning schedule

M. Vretnar



Start of beam commissioning (3MeV): May 2013  
 End of beam commissioning (160 MeV): April 2014

(version November 2010)

5 commissioning stages: 3 MeV 10 MeV 50 MeV 100 MeV 160 MeV

In 2013/14 (15 months), 6.5 months of beam commissioning, 3 months of HW tests, 5.5 months of installation



# PS injector - option 1: PSB Upgrade

K. Hanke

							LS1				LS2		
		BC	Group	WBS	2011	2012	2013	2014	2015	2016	2017	2018	Total kCHF
<b>PSB</b>	Management (M resources)	67020	BE-OP	LIU-PSB 1	40	80	80	80	80	80	80	40	560
	Beam Dynamics	61020	BE-ABP	LIU-PSB 2		10	10	10	10	10	0		50
	Magnets	99281	TE-MSD	LIU-PSB 3		165	65	65	660	1080	90		2125
	Magnetic Measurements			LIU-PSB 3	20	40	60	60	60	60	60	60	
	RF	69020	BE-RF	LIU-PSB 4									0
	Beam Intercepting Devices		EN-STI	LIU-PSB 7	25	45	50	50	25	25	25		245
	Power Converters (PSB)	99237	TE-EPC	LIU-PSB 5.2		745	450	5590	6370	1660	1190		16005
	Power Converters (Injection)	Existing*	TE-EPC	LIU-PSB 5.1	330	1045	105			45	45		1570
	Vacuum System	99271	TE-VSC	LIU-PSB 8		390	290						680
	Beam Instrumentation	64020	BE-BI	LIU-PSB 6	20	368	710	157					1255
	Commissioning		BE-OP	LIU-PSB 21							75	75	150
	Injection	Existing*	TE-ABT	LIU-PSB 9	1000	1000	1500	2125	1500	1000	155		8280
	Extraction, Transfer	99236	TE-ABT	LIU-PSB 10			360	1000	750	450			2560
	Controls	66020	BE-CO	LIU-PSB 11							500		500
	Electrical Systems		EN-EL	LIU-PSB 12		1100	500				100		1700
	Cooling & Ventilation		EN-CV	LIU-PSB 13						100	900		1000
	RP and Safety		DGS-RP	LIU-PSB 16									0
	Transport and Handling		EN-HE	LIU-PSB 14			25	25		30	200		280
	Survey	61021	BE-ABP	LIU-PSB 20	5		25	5	5		10		50
	<b>PSB Total</b>				<b>1440</b>	<b>4988</b>	<b>4230</b>	<b>9167</b>	<b>9460</b>	<b>4540</b>	<b>3430</b>	<b>115</b>	<b>37370</b>

+ Consolidation (Dipoles Power Supply, RF, Cooling & Ventilation) >20 MCHF





# PS injector - option 2: RCS

## Tentative RCS parameters

=> Same beam characteristics than PSB @ 2GeV

=> Shorter PS & SPS injection flat bottoms

Energy range	160 MeV to 2 GeV
Circumference	$(200 \times 4/21) \pi \text{ m} \approx 119.68 \text{ m}$
Repetition rate	$\sim 10 \text{ Hz}$
RF voltage	60 kV
Harmonics	
Frequency range	
Beam parameters (for...)	... cycle ( $3.25 \times 10^{12} \text{ p/p}$ )
	$2 \times 0.27 \text{ eVs}$ (determined by ... for most cases)
	... symmetry
	21 cells, 5 cells/arc, 2 cells/straight section
	$3.5 < Q_{H,V} < 4.5$
Length of straight section (4x)	2 x 2.35 m
Relativistic gamma at transition	$\sim 4$
Maximum magnetic field	$< 1.3 \text{ T}$

### Benefits:

- Competitive cost wrt PSB consolidation and upgrade (? Study in progress...)
- Reliability (new hardware / modern design)
- Commissioning decoupled from physics operation

K. Hanke



# PS Upgrades

							LS1				LS2		
		BC	Group	WBS	2011	2012	2013	2014	2015	2016	2017	2018	Total kCHF
<b>PS</b>	Management (M resources)	61030	BE-ABP	LIU-PS 1	40	80	80	80	80	80	80	40	560
	Beam Dynamics	61031	BE-ABP	LIU-PS 2		10	10	10	10	10	10	10	70
	Magnets	99282	TE-MSD	LIU-PS 3			670	330					1000
	RF	69030	BE-RF	LIU-PS 4	110	305	1230	1330	3500	3500	3200		13175
	EPC	99263	TE-EPC	LIU-PS 5	70	140	1110	580	70	210	180		2360
	Beam instrumentation	64030	BE-BI	LIU-PS 6									0
	Intercepting device		EN-STI	LIU-PS 7		100							100
	Vacuum system	99272	TE-VSC	LIU-PS 8	25	125					3850		4000
	Injection	99253	TE-ABT	LIU-PS 9		135	300	820	780	560	90		2685
	Controls		BE-CO	LIU-PS 11			25						25
	Electrical system		EN-EL	LIU-PS 12									0
	Cooling and ventilation		EN-CV	LIU-PS 13									0
	Transport		EN-HE	LIU-PS 14							880		880
	Civil engineering	76800	GS-SE	LIU-PS 15	30		700						730
	RP	57393	DGS-RP	LIU-PS 16		225	225						450
	Machine Interlocks		TE-MPE	LIU-PS 17									0
	Alarms			LIU-PS 18									0
	Access doors			LIU-PS 19									0
	Survey		BE-ABP	LIU-PS 20							90		90
	OP	67030	BE-OP	LIU-PS 21	140								140
	<b>PS Total</b>				<b>415</b>	<b>1120</b>	<b>4350</b>	<b>3150</b>	<b>4440</b>	<b>4360</b>	<b>8380</b>	<b>50</b>	<b>26265</b>

**+ Consolidation (Cooling & Ventilation, cables replacement...) ~43 MCHF**



# SPS Upgrades

							LS1			LS2			
		BC	Group	WBS	2011	2012	2013	2014	2015	2016	2017	2018	Total kCHF
<b>SPS</b>	Management (M resources)	99241	TE-ABT	LIU-SPS 1	40	80	80	80	80	80	80	40	560
	Beam dynamics studies and	69042	BE-RF	LIU-SPS 2	10	10	10	10	10	10	10	10	80
	MKDV/H impedance reduction	99242	TE-ABT	LIU-SPS 9.2		50	100						150
	Beam instrumentation	64040	BE-BI	LIU-SPS 6	200	600	500	500	300				2100
	Extraction protection upgrade	99243	TE-ABT	LIU-SPS 9.1		100	200	350	300	150			1100
	New high bandwidth damper				150	150	600	600	300				1800
	Existing damper power upgrade	69040	BE-RF	LIU-SPS 4.3		100	450	300	150				1000
	Existing damper removal to					200	300						500
	RF 200 MHz upgrade	69041	BE-RF	LIU-SPS 4.2	850	1400	2400	9850	7450	3650	600	300	26500
	ecloud mitigation: aC coating	99273	TE-VSC	LIU-SPS 8.2	145	350	550	505	620	1050	1800	600	5620
	New collimation system	99244	TE-ABT	LIU-SPS 7		100	200	800	2700	2700	1500	1200	9200
	New MKE and extraction channel upgrade	99245	TE-ABT	LIU-SPS 9.4		200	300	600	1800	1700	1200	600	6400
	Beam dump upgrade	99246	TE-ABT	LIU-SPS 9.5		150	250	800	2500	2100	1300	1000	8100
	TL protection upgrade	99247	TE-ABT	LIU-SPS 9.3		100	200	1500	1500	1500	1000	200	6000
	<b>SPS Total</b>				<b>1395</b>	<b>3590</b>	<b>6140</b>	<b>15895</b>	<b>17710</b>	<b>12940</b>	<b>7490</b>	<b>3950</b>	<b>69110</b>

+ Consolidation ~ ? MCHF



- Planned actions
- **Status of investigations**
- Estimated beam characteristics
- Planning
- Summary




# PS injector: RCS feasibility study

## Beam characteristics:

- for all PS users: equivalent to PSB at 2 GeV
- for ISOLDE:  $\sim 7 \cdot 10^{13}$  p/s @ 2 GeV (today:  $\sim 10^{13}$  p/s @ 1.4 GeV)

Feasibility report with  
cost estimate: end of July





# Principle of Working Point Scans


E. Benedetto

GOAL: Identify dangerous resonance lines in tune diagram

Loss measurement for different WPs:

- Low intensity beam (not SC-dominated)  $\rightarrow 130 \times 10^{10}$  protons
- Large emittance (to fill the chamber & provoke immediate losses)
- Long flat bottom @ 1.4 GeV
- Tune program:
  - Scan between (0.1 - 0.4)
  - Vertical tune constant
  - Sweep of the horizontal tune

Slope in the intensity signal indicates importance of the crossed resonance line








# PS Transverse: Tune Scans

2 GeV

E. Benedetto

⇒ w/o PFW : no surprises

⇒ with PFW ongoing






# PS Longitudinal: Batch Compression (1/2)

## Batch Compression Schemes in the PS Compression to $h_{PS} = 10$ and generation of 64 bunches



- Injection and first acceleration with  $h_{PS}=8$  or  $h_{PS}=9$
- Potential brightness increase:  $12/8 = 1.50^*$ 
  - ◆ Corresponds to PSB upgrade: 1.4 GeV to 1.77 GeV
  - ◆ Brightness per bunch for 25 ns trains out of PSB
    - $\epsilon^*=2.5 \mu\text{m}$  and  $2.23 \cdot 10^{11}$  or
    - $\epsilon^*=1.90 \mu\text{m}$  and  $1.7 \cdot 10^{11}$
- Estimate of longitudinal parameters at injection for 25 ns trains
  - ◆ Every bunch split into 8 LHC bunches with 0.35 eVs
  - ◆ 1.6 eVs per injected bunch allows a factor 1.75 blow-up

\*) With  $h_{PS}=8$  at injection, compared to present situation with Linac2 and double batch PSB to PS transfer




RF gymnastics at an appropriate intermediate energy (hypothesis 2.5 GeV)  
(Injection and first acceleration with  $h_{PS}=8$  or  $h_{PS}=9$ )

MD tests – H. Damerou, S. Hancock – May 2011




# PS Longitudinal: Batch Compression (2/2)

Simulation (C. Carli)



MD result at 2 GeV (H. Damerau, S. Hancock)





- RF gymnastics OK up to intermediate energy
- Significant effort required to reach 26 GeV and make beam available for the SPS (RF preparation & beam adjustment) => **Need for precise measurement of transverse emittances before continuing**



# SPS Transverse: Tune Scans

H. Bartosik

- Identified resonances in the low  $\gamma_t$  optics
  - normal sextupole resonance  $Q_x+2Q_y$  is the strongest
  - skew sextupole resonance  $2Q_x+Q_y$  quite strong !!??
  - normal sextupole  $Q_x-2Q_y$ , skew sextupole resonance at  $3Q_y$  and  $2Q_x+2Q_y$  fourth order resonances visible
- Identified resonances in the nominal optics
  - normal sextupole resonance  $Q_x+2Q_y$  is the strongest
  - Coupling resonance (diagonal, either  $Q_x-Q_y$  or some higher order of this),  $Q_x-2Q_y$  normal sextupole
  - skew sextupole resonance  $2Q_x+Q_y$  weak compared to Q20 case
  - It seems that the stop-band width of the vertical integer is stronger than in Q20 optics





# SPS Transverse: Single Bunch Emittances



H. Bartosik

## Measurement of single bunch emittances

- In scan with “reference” wire scanner BWS.519 at flat top
- Long cycle (~10s injection plateau, ~10s acceleration)
- Losses along the cycle extracted from DC-BCT measurement

## PS bunch length increasing with intensity

- $T=2.9\text{ns}$  @  $1.5 \times 10^{11}$  p/b,  $T=3.5\text{ns}$  @  $3 \times 10^{11}$  p/b
- Emittances in PSB:  $\sim 1\mu\text{m}$  <  $1.5 \times 10^{11}$  p /  $\sim 1.1\mu\text{m}$  @  $2 \times 10^{11}$  p /  $\sim 1.3\mu\text{m}$  @  $3 \times 10^{11}$  p (Well adjusted beam in the PSB!)




# SPS: 50ns bunch train – Double PSB batch

Intensity  $1.65 \cdot 10^{11}$  p/b

- Up to 4 batches injected
- **Very low losses** along the cycle (measured 3%)
- $E_h = 2.0 \mu\text{m}$  and  $E_v = 1.0 \mu\text{m}$  at flat top (sum 3.9)

**Measured on 1st batch – to be confirmed**






# SPS: e-cloud with 25 ns bunch train

M. Taborelli

- Electron cloud measured at all the liners
  - Signal already visible with 1 batch on both stainless steel liners
  - No signal visible on the a-C coating liner
  - Half signal clearly visible on the half coated chamber
  - Effect of the clearing electrode checked scanning points on a grid of voltage vs. magnetic field values




Clearing electrode: it was switched off in the middle of cycle

Half-coated liner, only stripe on StSt visible



# Present focus: debugging of transverse emittance measurement – Error source inventory

J.J. Gras







# Emittance blow-up in SPS with low $\gamma_t$

H. Bartosik

- MD4 beam in PSB with 1.1 turns injected (slightly smaller transverse emittances)
- Simultaneous measurements of vertical emittance in PS and SPS
  - ✓ At extraction (just before bunch rotation) in PS using PS-65.V
  - ✓ At end of flat bottom using SPS-BWS.519
  - ✓ Here RF-voltage of 5.75 MV in SPS
- If calibration of wire scanners between machine is believed  $\rightarrow$  emittance blow-up for intensities above  $1.5e11$  p/b with peak values of 25% at  $3e11$  p/b





- Planned actions
- Status of investigations
- Estimated beam characteristics
- **Planning**
- Summary





# Linac4 connection to the PSB

- High interest of connecting Linac4 to the PSB during LS1:
  - ✓ **Staged upgrade spread between LS1 and LS2 (shorter LS2 ?)**
  - ✓ **Timely termination of the Linac4 project**
- Reasonable scenario (with 20 months LHC shutdown) if LHC stops in May 2013
  - ⇒ **Possibility to run the injectors until the end of 2013**
  - ⇒ **No beam for physics before early 2015**

TENTATIVE SCHEDULE - CONNECTION LINAC4 DURING LONG SHUT-DOWN 2013/2014 - version B 06.04.11


2013												2014												COMMENTS			
1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12				
				Linac4 commissioning																							L4 commissioning original schedule
															Reliability run											Reliability run 5 months	
																			Transfer line commissioning								
																		PSB modifications									
																				PSB commissioning							
																						PS/SPS commissioning					
			LHC Shut-down (20 months beam-to-beam)																								

M. Vretenar

- Scenario based on LHC stop at end 2012 is more risky / not recommended: when physics resumes after 20 months interruption, users will expect similar performance § reliability than before the shutdown...



# PSB Upgrades



## Injection, magnets, power converters...

System	Elements
Injection elements	Injection septum Injection bumpers Eventual extra kicker
Low energy correctors	100 horizontal correctors 30 vertical correctors
Low energy skew quadrupoles	45 magnets
Low energy quadrupoles	40 magnets
Transverse damper	Power part of existing system
e-cloud attenuation system	Chamber coating or electrode Installation
Instrumentation	BWS, BCT, Orbit system, profile monitors.
<b>Improved shielding on top of route Goward and on top of SMH16</b>	Shielding elements

## RF


S. Gilardoni

Priority	Item	When
[1]	New coupled-bunch FB	2012
2	Dedicated kicker cavity	2015-2020
<b>10 MHz</b>		
[1]	1-turn delay FB	2011
1	Renovate FB amplifiers	2011-2015 (?)
1	Slow phase loops around each cavity	2013-2014
2	New power amplifier (1 tube/gap)	2014-2018 (?)
<b>20 MHz</b>		
1	1-turn delay FB	2012
2	Slow phase loops around each cavity	2012
<b>40 MHz</b>		
[1]	Automatic tuning system	2011
1	1-turn delay FB	2012
2	New feedback amplifier in grooves	2014
2	Slow phase loops around each cavity	2012
3	Study more voltage per cavity	2013
3	New power supplies	2014-
<b>80 MHz</b>		
1	1-turn delay FB	2012
1	Automatic tuning system - PLC, prot./ions switching	2011-2012
2	Slow phase loops around each cavity	2012
2	New feedback amplifier in grooves	2014
2	Fast ferrite tuner	2016
3	Study more voltage per cavity	2013
3	New power supplies	2014-
3	Extra 80 MHz cavity	???



# SPS Upgrades (1/2)

**B. Goddard**





# SPS Upgrades (2/2)

B. Goddard

