



Status of the Accelerator Complex

Matteo Solfaroli BE/OP


Plenary RRB 58th Meeting

April 22nd, 2024

Outline

- **Main issues from 2023: status and impact**
- 2024 beam commissioning status
- Outlook for rest of Run3

2023 luminosity production vs main faults




Vacuum module

IMPACT in 2023


- ~5 days lost
- **Bunch intensity limited** to $1.6e^{11}$ p/b
- Difficult to identify **intensity limitation** (strong dependence on contact quality)
- **2024 LHC operation** presently limited to $1.6e^{11}$ p/b
- **Simulations ongoing** to assess impact of beam parameters on power deposition

VISUAL INSPECTION

annealed/plasticised spring on the 212 mm vacuum module due to localized temperature increase to more than 500°C



EM simulations show localized heating




Consolidation plan:

- 47 replaced during 23/24 EYETS
- 24 foreseen in 24/25
 - No failure expected with ideal contact

IT.L8

- Electrical glitch triggered Inner Triplet (IT) magnets **protection**
- **Fast pressure rise** in the cold mass
- **Leak** in vacuum vessels → atmospheric pressure in ~8h
- Fast repair thanks to **special cryo procedure**



Equivalent risk of failure on others ITs

- Similar bellow extension
- Multiple pressurisations since their installation: NO fault


Mitigation measures

- **No intervention** planned (IT maintained at cold)
- **Consolidation planned** for LS3



Target Dump Injection Segmented (TDIS)

- **TDIS**: absorber meant to protect downstream equipment during injection phase
- **High-Luminosity compliant** devices were installed during LS2
- **2 vacuum leaks**, due to NON-conform bellows led to end of pp operation
- During EYETS 23/24 **both TDIS replaced** with spare (“non-compliant”)




NO limitation expected

- Mechanical stress reduced
- Conform spares expected by **September 2024**


Outline

- Main issues from 2023: status and impact
- **2024 beam commissioning status**
- Outlook for rest of Run3

Reversed Polarity (RP) optics





Excessive dose deposition on magnets of Inner Triplet region (close to interaction point) can lead to damage and failure



Solutions to **redistribute the radiation**, allowing for longer lifetime of the equipment:

- Local optics change (implemented in P1, as most critical)

Example for IP1






Configuration	Peak dose [MGy] at end of 2025 (430 fb ⁻¹)	
	IT	MBXA (D1)
NO change	26.5 (IR1) 26.5 (IR5)	105 70
2024 - IP1-RP 2025 - Full RP	20.5 (IR1) 22.5 (IR5)	70 60
2024 - IP1-RP 2025 - NO change	22 (IR1) 26.5 (IR5)	70 70

Estimated damage limit:

- 30 MGy for IT
- 90 MGy for D1


2024 LHC schedule ver. 2.0 + Q1+Q2




- **Hardware commissioning** completed in time
- **First injection** on 8th March (3 days ahead of schedule)
- **First STABLE BEAMS** at 6.8 TeV on 5th April (3 days ahead)
- **Scrubbing** succesful
- **Intensity ramp-up** ongoing (presently physics with 1983 bunches)

Establishing physics production

- **Beam commissioning** completed in the 4 weeks allocated:
 - Well established baseline, effective knowledge and control: **early start** (3 days) -> **early stable beams** (3 days)
 - Optics change accounted for ~1 week (as expected)
- Step-wise approach for **intensity ramp-up**:
 - Monitor behavior during >15h in stable beams
 - Validate progressively correct functionality of machine-protection system and operational tools
 - Bunch intensity $\sim 1.55e^{11}$ p/b





3/12 - 75 - 400 - 800 - 1200 - 1800 - 2400 - full machine*



Heat load


- Heat load (HL) deposited by the beams **can become a limitation** when not enough cryo capacity (presently well beyond the Design Report value)
- Gradual conditioning** helps to increase the beam intensity
- Degradation observed** when sectors are vented to air (LS)
- Non-homogeneous distribution** across the machine
 - Sector 78 is the highest sector in Run3

Geographical HL distribution



Heat load in Run3



- **2023:** Kept under control thanks to **hybrid filling scheme** (8b4e and 36 bunch trains) – e-cloud suppressed but penalization on number of bunches
- **2024:** Modified cryogenic configuration (capacity rebalanced between S78 and S81) allows to operate LHC without hybrid scheme at $1.6e^{11}$ p/b:
 - **Larger number** of bunches
 - Better beam quality
- **Dedicated scrubbing session** with long trains (72b) allowed to inject for the first time **2676 bunches** in each beam (at injection energy!)



LHC injectors performance

Year-by-year intensity goals of the ramp-up at SPS extraction

- **2021: $1.3e^{11}$ p/b** – Recover Pre-LS2 beam parameters
- **2022: $1.8e^{11}$ p/b** – Set base for LHC 2023 operation
- **2023: $2.1e^{11}$ p/b** – Toward LIU targets (HL parameters)
- **2024: $2.3e^{11}$ p/b** – LIU target for HL-LHC operation



LIU intensity and bunch length at SPS extraction **achieved**:


- 4x72 bunches at $2.3e^{11}$ p/b with bunch length of 1.65 ns
- Transverse emittances did not yet satisfy LIU specification (optimization will be done in the next high intensity sessions)

Outline

- Main issues from 2023: status and impact
- 2024 beam commissioning status
- **Outlook for rest of Run3**


LHC schedule - changes

- **Injectors YETS** shifted by 5-weeks
 - 3-weeks reduction, more physics
- **LHC YETS** shifted by 4-weeks (Start date 28.10 -> 25.11)
 - 19 weeks length (beam-to-beam) maintained
 - Extended time used for proton physics
- **2025 run** shortened by 4 weeks -> one Technical Stop removed
- NO additional technical stop for **2024 run**






Activity	2024+2025 v1.0 [days]	2024+2025 v2.0 [days]	Diff [days]
Proton physics	269	274.5	+5.5
Ion physics & p-p ref. run (Oxygen included)	44.5	45	+0.5
Scheduled stops & recovery	28.5	22.5	-6

2024 LHC schedule




Activity	Duration [days]	Ratio [%]
Beam Commissioning & Intensity ramp-up	41	15.8
Scrubbing	3	1.2
25 ns physics (>1200 bunches)	147.5	56.9
Special physics runs (incl. setting-up)	2	0.8
Pb-Pb ions & p-p ref. setting-up	6	2.3
Pb-Pb ions physics & p-p ref. run	23	8.9
Technical stop	9	3.5
Technical stop recovery	2	0.8
Other scheduled stops	2.5	1.0
Machine Development	23	8.9
Total:	259	100%




Performance

2023 production rate reached $\sim 0.8 \text{ fb}^{-1}/\text{day}$ in stable periods (2 weeks only) with $1.6e^{11}$ p/b and $\sim 50\%$ time in SB




[Generated at: 2024-04-18 16:18:17]

Delivered Luminosity 2023



Record
1.2 fb⁻¹/24h

2023 integrated Lumi (ATLAS) per 24h




Availability

- Availability is THE key factor for accelerator performance
- Accelerator Fault Tracking (**AFT**) systems allows for analysis and cataloguing of down time
- **LHC availability factor** was constant through Run2 and Run3 for small (<24h) faults
- “Long faults” have been so far dominant for Run 3

Facility	Overall availability [%]			
	2021	2022	2023	2024*
LINAC4	97.3	96.8	98	93.2
PSB	94.5	94.8	96.1	90.9
PS	88.1	89.6	92	88.6
SPS	73.4	74.1	86 (94.3 LHC)	85.1 (92.2 LHC)
LHC		76.3	43.7**	75.2

* Affected by Klystron replacement and extraction kicker repair in PSB

** Includes RF finger module exchange & Cold mass to insulation vacuum repair



Conclusions

- **2024 Run** has started and NO limitation is identified
- **Bunch intensity** presently limited to $1.6e^{11}$ p/b for risk mitigation
 - Until **further understanding** of heat deposition dynamics
 - Pushing bunch intensity in Run3 is important to unveil any **potential limitations**, before LS3
- **Heat load** should be kept under control in 2024
- **YETS shift** (4 weeks forward) will result in a net gain of about 6 days (dedicated to pp physics)


Thanks for your attention

SPARE

FASER/SND background

- **FASER and SND background rates** are ~doubled wrt 2023 (non-RP optics)
 - Implies more frequent emulsion exchanges (if available!)
- Background tests for FASER demonstrated **little impact of collimation system** on background, as increase is driven by TeV-scale muons, originating from IP
 - Agreement with FLUKA simulations which indicate an origin before TCL4
 - More simulations ongoing

Momentum distribution (signed by charge), $r < 100\text{mm}$



Courtesy of B. Petersen


2024 LHC schedule

Activity	Version 2.0		Version 1.0		Gains & Losses
	Duration [days]	Ratio [%]	Duration [days]	Ratio [%]	
Beam Commissioning & Intensity ramp-up	41	15.8	42	18.2	=
Scrubbing	3	1.2	3	1.3	=
25 ns physics (>1200 bunches)	147.5	56.9	124	53.7	+ 23.5
Special physics runs (incl. setting-up)	2	0.8	2	0.9	=
Pb-Pb ions & p-p ref. setting-up	6	2.3	6	2.6	=
Pb-Pb ions physics & p-p ref. run	23	8.9	22.5	9.7	+ 0.5
Technical stop	9	3.5	9	3.9	=
Technical stop recovery	2	0.8	2	0.9	=
Other scheduled stops	2.5	1.0	0.5	0.5	=
Machine Development blocks (incl. floating MDs)	23	8.9	20	8.7	+ 3
Total:	259	100 %	231	100 %	+28

2025 LHC schedule

Activity	Version 0.6		Version 0.4		Gains & Losses
	Duration [days]	Ratio [%]	Duration [days]	Ratio [%]	
Beam Commissioning & Intensity ramp-up	36	16.1	37	14.7	=
Scrubbing	2	0.9	2	0.8	=
25 ns physics (>1200 bunches)	123	54.9	141	56	-18
Special physics runs (incl. setting-up)	2	0.9	2	0.8	=
Oxygen ion setting-up	4	1.8	4	1.6	=
Oxygen ion physics	4	1.8	4	1.6	=
Oxygen ion recovery	0.5	0.2	0.5	0.2	=
Pb-Pb ions & p-p ref. setting-up	6	2.7	6	2.4	=
Pb-Pb ions physics & p-p ref. run	18	8.0	18	7.1	=
Technical stop	8	3.6	13	5.2	- 5
Technical stop recovery	2	0.9	4	1.6	- 2
Other scheduled stops	1.5	0.7	0.5	0.2	+1
Machine Development blocks (incl. floating MDs)	17	7.6	20	7.9	- 3
Total:	224	100%	252	100	- 28

Recommendations based on a precautionary approach



Simulations and lab measurements to assess the impact of vacuum equipment on beams and vice-versa




12.02.2024

7


P. Chiggiato @ LMC #479



HL-LHC readiness



- LS3 installation schedule shows ~1 **year float** for most equipment
- The overall critical paths appear **credible** and the associated schedule margins **adequate**
- The potential delays are **well covered**




2023 HL-LHC Cost and Schedule review, CMAC report:
 “Although schedule risks remain in several areas, the CMAC is convinced that the project will be ready for implementation in LS3.”

Heat load expectations

Beam screen cryo capacities during HL-LHC era

- LHC cryoplants are supplying many devices in parallel at different temperatures

- Thermal shields between 50 K and 75 K
- Main superconducting magnets at 1.9 K (ARC dipoles/quadrupoles)
- Stand Alone superconducting magnets at 4.5 K (D2, D3, Q4, Q5, Q6)
- RF cavities at 4.5 K
- DFB at 4.5 K with their current leads and superconducting links
- Inner Triplet at 1.9 K around experiments (dynamic heat loads, depending on luminosity)
- Beam Screens (BS) between 4.5 K and 20 K (dynamic heat loads, depending on beams)



- All LHC cryoplants are slightly different and have different capacities & loads (RF, SAM, DFB, triplets, etc.)

Expected changes in Run 4++	Helium massflow	Q @ 1.9 K [per sector]	BS Capa 4.5 K - 20 K [per ARC]	BS Capa 4.5 K - 20 K [per half-cell]	Concerned sectors
Removal of IT at P1 & P5 in LS3 (Run4)	-12 g/s	-280 W	+1.3 kW	+25 W/hc	S12, S81, S45, S56
Increase of Lumi at P8 with LHCb++ after LS4 ? (Run5)	+11 g/s	+260 W	-1.2 kW	-23 W/hc	S78, S81

➔ The available beam screen cryogenic capacities will change from Run 4

Beam screen treatment

Risks:


- **Degradation** of un-treated half-cells during future LS
 - Extremely difficult to quantify and impossible to localize
- **Higher than expected heat loads** of treated half-cells
- **Low(er) number** of treated half-cells in LS3

Possible mitigations?

- Treat **larger number** of half-cells (more margins)
- Produce **less e-cloud**
 - Filling scheme (36b/48b (2022), hybrid (2023))
 - Continue the beam screen treatment in future LS


OBJECTIVES

- Remove CuO and/or increase surface carbon concentration on selected BS
- Beam Screen (BS) surface passivation (robustness against re-oxidation)



A scenario treating **100 half-cells** looks realistic

Heat load expectations



HL-LHC prediction in S78
for 5x48b @ $2.3 \times 10^{11} \text{ ppb}$ & 7 TeV
→ 280 W/hc > Cryo limit [225 W/hc]

Simulations performed for **main beam injection schemes** without any Beam Screen treatment

- 4x72b, 5x48b and 5x36b