


Nb₃Sn High Field Magnet (HFM) activities at Saclay

E. Rochepault, V. Calvelli, G. Campagna, M. Durante, H. Felice,
J. Faucheux, T. Guillo, G. Lenoir, G. Minier, S. Perraud, Y. Perron,
F. Rondeaux - CEA

J.C. Perez - CERN

HFM meeting – 29/05/2024

Development Plan towards 16 T Nb₃Sn Dipoles







1 ■ Powered samples

deBOnding eXperiment n°1 - deBOX1

PhD Thesis
Guillaume
Campagna




New instrumentation: two pick-up coils
and a 7 kN load cell for cryogenic use



Twente sample holder : 11 T background, 100
kA transformer, up to 200 MPa compression




deBOnding eXperiment n°1 - deBOX1



1. Regular training at 10 MPa → training to 100% of I_c



deBOnding eXperiment n°1 - deBOX1




1. Regular training at 10 MPa → training to 100% of I_c

2. Unloading quenches:

- Current maintained at 98% I_c
- Pressure decreased until the cable quenches
- “control” quench = reaches again I_c (+sometimes 1 training quench)

deBOnding eXperiment n°1 - deBOX1



1. Regular training at 10 MPa → training to 100% of I_c


2. Unloading quenches:

- Current maintained at 98% I_c
- Pressure decreased until the cable quenches
- “control” quench = reaches again I_c (+sometimes 1 training quench)

3. Low compression quenches at ~3 MPa

- Long training with erratic current values.
- Not able to reach I_c

deBOnding eXperiment n°1 - deBOX1



1. Regular training at 10 MPa → training to 100% of I_c

2. Unloading quenches:

- Current maintained at 98% I_c
- Pressure decreased until the cable quenches
- “control” quench = reaches again I_c (+sometimes 1 training quench)

3. Low compression quenches at ~3 MPa

- Long training with erratic current values.
- Not able to reach I_c

4. Recovery at 10 MPa → perfect memory




2 ■ SMC-11T

SMC-CEA#101


- SMC-CEA #101 fabricated at Saclay in 2021
- Assembled and tested at CERN in 2022



SMC-CEA#101 – training




Quench	Bbore T	Bpeak T	I cable kA	%SS	location
1	7.34	10.98	12.375	75.0	U5-U7
2	7.44	11.14	12.60	76.4	L6-L7 L7-L8
3	7.54	11.29	12.81	77.7	U7-U8 U8-U9
4	7.58	11.36	12.90	78.2	L7-8 L8-L9
5	7.62	11.42	12.98	79	L12-L11
6	7.80	11.71	13.38	81	U7-U8
7	7.92	11.90	13.64	83	U5-U7
8	7.95	11.95	13.71	83	U2-U3
9	7.92	11.91	13.65	83	U2-U3
10	7.99	12.01	13.80	84	U2-U3
11	7.93	11.91	13.66	83	U2-U3




1. Training at 1.9 K

- Limitation at 84 % SS
- Close to 'top' splice
- 12 T peak on the coil

SMC-CEA#101 – training




Quench	Ramp	Bpeak	I cable	%SS	location
	A/s	T	kA		
12	5	11.77	13.47	82	U2-U3
13	50	11.99	13.76	83	U9-U10
14	100	12.17	14.01	85	U5-U7
15	100	12.03	13.83	84	U5-U7
16	1	11.98	13.75	83	U2-U3
17	100	11.88	13.62	83	U5-U7
18	200	11.94	13.70	83	U14-U15




2. Ramps at 1.9 K

SMC-CEA#101 – training




	Ramp	Bpeak	I cable		location
Quench	A/s	T	kA	%SS	
12	5	11.77	13.47	82	U2-U3
13	50	11.99	13.76	83	U9-U10
14	100	12.17	14.01	85	U5-U7
15	100	12.03	13.83	84	U5-U7
16	1	11.98	13.75	83	U2-U3
17	100	11.88	13.62	83	U5-U7
18	200	11.94	13.70	83	U14-U15




2. Ramps à 1.9 K

- Fast ramps allows « bypassing » the limiting zone U2-U3
- 85 % SS at max

SMC-CEA#101 – training



	Bbore	Bpeak	I cable		location
Quench	T	T	kA	%SS	
19	7.86	11.80	13.51	90	U5-U7
20	8.13	12.25	14.12	95	U5-U7
21	8.12	12.22	14.08	94	L6-L5






3. Training et 4.5 K

- No limiting zone
- **95 % SS !**
- Unfinished training?
Test station unavailable

SMC-CEA#101 – training



Other observations:

- No VI increase observed = no I_c degradation
- Joint resistances $< 0.25 \text{ n}\Omega$ at 12 kA
- Linear stress on the pole, no observable detachment



SMC-CEA#102

- Introduction of the CTD flexibilizer
- **2 shortcuts detected after impregnation**
- **repaired, electrical tests passed !**
- Fabrication finalized April 2024
- Coil delivered to CERN in may
- Assembly in the structure foreseen in the coming weeks







3 ■ R2D2

Conductor production and qualification

- 2 Nb₃Sn RRP conductors for grading
- Same cables for all magnets
- Strand characterization @ CERN
- Cable production @ CERN
- Cable and strand characterization @ Saclay




Parameter	Unit	HF cable	LF cable
Strand type		DEM-1.1	DEM-0.7
Strand layout		RRP® 162/169	RRP® 60/91
Strand diameter	mm	1.1	0.7
Number of strands		21	34
Cable mid-thickness	mm	1.969 ± 0.010	1.253 ± 0.010
Cable width	mm	12.579 ± 0.050	12.579 ± 0.050
Pitch	mm	84 ± 3	79 ± 3
Core		No core	No core

Overview of the R2D2 design


- CEA conceptual design validated by an external committee
- Fabrication, assembly and pre-stress at Saclay
- Tests at cold at CERN
- **Main goal: demonstrate feasibility of grading**
 - Winding two cables on top of each other
 - Heat treating two different cables together
 - Junctions of the 2 cables → 1st option: external Nb₃Sn-NbTi joints

R2D2 = Research Racetrack Dipole Demonstrator



Aperture	None
Outer diameter	480 mm
Structure length	2.0 m
Nominal central field	11.1 T
Ultimate central field	12.0 T
Nominal peak field	12.7 T
Ultimate peak field	13.7 T

Overview of the R2D2 design







*warning: no SF correction
 **to be updated with recent I_c data

Parameter	Nom. 4.2 K	Nom. 1.9 K	Ultimate 1.9 K	SS 4.2 K	SS 1.9 K	Unit
Current	14.6	15.9	16.8	18.2	19.8	kA
LL Margin HF	20.5	21.9	17.5	0.7	2.3	%
LL Margin LF	20.3	20.4	16.0	0.3	0.5	%
B center	10.89	11.62	12.12	12.96	13.87	T
B peak HF	12.37	13.24	13.83	14.83	15.92	T
B peak LF	8.089	8.73	9.17	9.92	10.74	T
Hotspot HF	91	152	189	255	1058	K
Hotspot LF	132	264	351	506	1333	
J block HF	474.0	515.8	544.3	592.5	644.8	
J block LF	694.9	756.1	797.8	868.6	945.1	

R2D2 Cu prototype coil fabrication

- ✓ Winding / heat treatment
- ✓ Junctions and operations pre-impregnation
- ✓ Impregnation
- ✓ Operations post-impregnation
- ✓ Qualification tests



Fabrication of R2D2 Nb₃Sn coil CR01

- ✓ Winding
- ✓ Heat treatment
- Junctions ongoing
- Impregnation for mid-June
- Operations post-impregnation for end of June
- Qualification tests for July

- Start of CR02 for July




Dimensional changes during Heat Treatment

- Measurements on short coils :




	Short coils	
	Length variation /L ₀ (mm)	Central gap variation /M1 (mm)
HF coil	-0.06%	-0.35%
LF coil	-0.34%	-0.55%

- Extrapolation on CR01:




- Preliminary measurements on CR01:



R2D2 coils			
Coil total length (mm)	Mandrel length (mm)	Expected Coil length variation (mm)	Expected Central gap variation (mm)
688	631	-0.39	-2.19
1300	1250	-4.36	-6.81

R2D2 structure procurement

- ✓ Shell segments received at CERN
- Structure components (yoke, pads, rods, endplates)
- opening of the bids today
- Delivery expected ~September



- Connection box:
 - ✓ 3D design finalized
 - To be validated with a mockup
- Magnet schedule :
 - Dummy assembly at Saclay to validate the mechanical behavior of the structure → Q4 2024
 - Selection of the 2 best coils for assembly → Q1 2025
 - Delivery at CERN for cold tests → mid-2025




4 ■ FD/F2D2

F2D2 16T demonstrator magnet


- **Conceptual design stage**
- Fabrication, assembly and pre-stress at Saclay
- Tests at cold at CERN
- **Main goal: demonstrate all technologies**
 - Representative of high field magnets: grading, joints, flared-ends, high field and high stress
 - Representative of accelerator magnets: 50 mm bore, field quality

F2D2 = Future Flared Dipole Demonstrator



Aperture	50 mm
Outer diameter	650 mm
Structure length	2.0 m
Nominal central field	15.5 T
SS central field	17.8 T
Nominal peak field	16.2 T
SS peak field	18.6 T

F2D2 16T demonstrator magnet




Parameter	Nom.	Nom.	SS	SS	Unit
	4.2 K	1.9 K	4.2 K	1.9 K	
Current [kA]	10.4	10.4	11.1	12.1	kA
LL Margin HF	5.6	14.6	-1.0	0.3	%
LL Margin LF	6.9	15.1	0.4	0.9	
B center	15.54	15.54	16.48	17.81	T
B peak HF	16.20	16.20	17.04	18.58	T
B peak LF	11.85	11.85	12.63	13.62	T
J block HF	337.2	337.2	360.7	393.8	
J block LF	494.3	494.3	528.7	577.2	

FD 14T demonstrator magnet


- **Conceptual design stage**
- Fabrication, assembly and pre-stress at Saclay
- Tests at cold at CERN
- **Main goal: demonstrate key technologies**
 - Representative of high field magnets: grading, joints, flared-ends, high field and high stress
 - Some simplifications: 1 type of coils, no bore

FD = Flared Dipole



Aperture	None
Outer diameter	650 mm
Structure length	2.0 m
Nominal central field	14.0 T
SS central field	17.2 T
Nominal peak field	14.7 T
SS peak field	17.9 T

FD 14T demonstrator magnet



Parameter	Nom.	Nom.	SS	SS	Unit
	4.2 K	1.9 K	4.2 K	1.9 K	
Current [kA]	10.9	11.7	12.9	13.9	kA
LL Margin HF	15.3	16.1	0.0	0.4	%
LL Margin LF	15.5	15.7	0.2	0.0	
B center	12.89	14.04	15.72	17.18	T
B peak HF	13.47	14.67	16.42	17.95	T
B peak LF	9.61	10.52	11.87	13.00	T
J block	354.2	380.2	418.2	451.2	
	519.2	557.3	613.0	661.4	

Future steps after R2D2: FD and F2D2

1. In parallel of the fabrication of R2D2:

→ detailed design of F2D2

• **FD magnet = intermediate assembly of F2D2**

- Same F2D2 structure

- Only 1 type of coil (layers 3-4)

- Flared-ends, but no bore

→ validation of the grading with flared-ends

- **Faster design and turnover** compared to F2D2 (1 type of coil and tooling)


2. If R2D2 test is validated:

→ fabrication of coils 3-4 for assembly in FD

3. In parallel → finalization of detailed design of coils 1-2 (aperture)


4. If FD test is validated:

→ fabrication of coils 1-2 for assembly in F2D2





irfu



Merci !
Thank you !



■ Backup slides