



# BBWC commissioning and operation for 2024<sup>1</sup>

G. Sterbini, P. Bélanger, S. Fartoukh, M. Hostettler and A. Rossi

*We thank G. Iadarola for his help with xsuite's matching module, J. Wenninger and S. Redaelli for the discussions, D. Mirarchi for the wires polarity check at injection. We acknowledge BE-ABP/CEM/OP, EN-MME and SY-BI/STI for their technical support.*

1. Introduction and context
2. Proposal for the B1/2 and IR1/5 knobs
3. Summary

---



<sup>1</sup><https://www.overleaf.com/read/fpjdrkktjtmw#daf6a5>

# HL-LHC wire demonstrators

→ **4 demonstrators** installed in LHC since 2017 for Run 2 MDs [1],

# HL-LHC wire demonstrators

- **4 demonstrators** installed in LHC since 2017 for Run 2 MDs [1],
- **embedded in operational TCTs**
  - **L1B1** and **R1B2** (V-TCT,  $s_{IP}^{center} = -145.945$  m)
  - **L5B1** and **R5B2** (H-TCT,  $s_{IP}^{center} = -147.945$  m)
- each jaw has a **1 m** long,  $\varnothing=2.48$  mm Cu wire carrying **350 A**.



From EDMS 1705791 and 2054712.

## A bit of history

- ▶ After a successful MD campaign in Run 2 [1], MPP scrutiny (MPP 193) and Evian 2021 proposal [2], wires compensators were used in production fills in Run 3 (since 2022).

## A bit of history

- ▶ After a successful MD campaign in Run 2 [1], MPP scrutiny (MPP 193) and Evian 2021 proposal [2], wires compensators were used in production fills in Run 3 (since 2022).
- ▶ At LBOC 135, D. Jaquet presented the LSA implementation of the Q-feedforward. The matching strategy (base on the Q4s' trims) was discussed at the Run 3 Configuration WG (8 April 2022).
- ▶ In 2022, following the **failure of B1 (F8146) and B2 (F8399)** wires, a consolidation studies was launched by EN-MME, SY-BI/STI, BE-ABP (LMC 456). Results presented at Chamonix 2023.

## A bit of history

- ▶ After a successful MD campaign in Run 2 [1], MPP scrutiny (MPP 193) and Evian 2021 proposal [2], wires compensators were used in production fills in Run 3 (since 2022).
- ▶ At LBOC 135, D. Jaquet presented the LSA implementation of the Q-feedforward. The matching strategy (base on the Q4s' trims) was discussed at the Run 3 Configuration WG (8 April 2022).
- ▶ In 2022, following the **failure of B1 (F8146) and B2 (F8399)** wires, a consolidation studies was launched by EN-MME, SY-BI/STI, BE-ABP (LMC 456). Results presented at Chamonix 2023.
- ▶ **B2 wires were repaired** in EYETS22-23 (8-9 March 2023, after LHC-BBLR-EC-0001 approval at LMC 457). **They were used successfully in 2023** in production fills (see 13<sup>th</sup> HL CM).

## A bit of history

- ▶ After a successful MD campaign in Run 2 [1], MPP scrutiny (MPP 193) and Evian 2021 proposal [2], wires compensators were used in production fills in Run 3 (since 2022).
- ▶ At LBOC 135, D. Jaquet presented the LSA implementation of the Q-feedforward. The matching strategy (base on the Q4s' trims) was discussed at the Run 3 Configuration WG (8 April 2022).
- ▶ In 2022, following the **failure of B1 (F8146) and B2 (F8399)** wires, a consolidation studies was launched by EN-MME, SY-BI/STI, BE-ABP (LMC 456). Results presented at Chamonix 2023.
- ▶ **B2 wires were repaired** in EYETS22-23 (8-9 March 2023, after LHC-BBLR-EC-0001 approval at LMC 457). **They were used successfully in 2023** in production fills (see 13<sup>th</sup> HL CM).
- ▶ **B1 wires were repaired** in EYETS23-24 (20-24 Nov 2023, after LHC-BBLR-EC-0002 approval at LMC 474). The **B1 wires powering commissioning** was done in the tunnel by A. Rossi's team.



# 2024 Run and wire compensation

We propose to use the **B1 and B2 wires** in

1. **2024 production fills** as done in 2023 for B2 wires (at the end of the fill with  $\beta^*=30$  cm),
2. **2024 MD** to explore their potential for  $22 \text{ cm} < \beta^* < 30 \text{ cm}$ , and depending on the results, consider their use also in this segment (e.g., after TS1).

---

<sup>2</sup>2022/23 knobs were based just on tune correction using Q4L/R.

# 2024 Run and wire compensation

We propose to use the **B1 and B2 wires** in

1. **2024 production fills** as done in 2023 for B2 wires (at the end of the fill with  $\beta^*=30$  cm),
2. **2024 MD** to explore their potential for  $22\text{ cm} < \beta^* < 30\text{ cm}$ , and depending on the results, consider their use also in this segment (e.g., after TS1).

Following the decision of deploying RP optics in 2024, the IR1 Q4s were locked-out ([LMC 479](#)). We reconsidered the Q-feedforward knobs, and we propose a **full-fledged matching**<sup>2</sup> using the following 9 quadrupoles (on the **TCT's IP side**)

- ▶ Q5-6-7-8-9-10-11-12-13 for IR1,
- ▶ Q4-5-7-8-9-10-11-12-13 for IR5.

---

<sup>2</sup>2022/23 knobs were based just on tune correction using Q4L/R.

## These knobs

- ▶ are **tele-index independent** (e.g., see  $\beta^* < 30$  cm segment),
- ▶ are **very linear and local** perturbation,
- ▶ do **not affect the IP** → **Roman-Pots matrices**,
- ▶ Crossing and separation bump extends up to Q4-5. Trimming those quadrupoles will have an **effect on the closed orbit**. We assume that the closed orbit feedback will be active and correct it,
- ▶ in 2024, R1B1 IPQs used for the  $\beta^*$  reconstruction<sup>3</sup>.

---

<sup>3</sup>In 2023, the L1B1 IPQs were used: **J. Wenninger** modified the 2023 approach to avoid “cross-talk” with these knobs.

<sup>4</sup>see [EDMS 2384198](#).

These knobs

- ▶ are **tele-index independent** (e.g., see  $\beta^* < 30$  cm segment),
- ▶ are **very linear and local** perturbation,
- ▶ do **not affect the IP** → **Roman-Pots matrices**,
- ▶ Crossing and separation bump extends up to Q4-5. Trimming those quadrupoles will have an **effect on the closed orbit**. We assume that the closed orbit feedback will be active and correct it,
- ▶ in 2024, R1B1 IPQs used for the  $\beta^*$  reconstruction<sup>3</sup>.

At **LBQC 164**, the knobs' strategy was endorsed and the use of the BBCWs in 2024 operational cycle (at  $\beta^*=30$  cm) was approved at **LMC 482**.

We will focus on the wires beam **readiness for STABLE BEAMS** and the MPP **BBCW checklist**<sup>4</sup>.

---

<sup>3</sup>In 2023, the L1B1 IPQs were used: **J. Wenninger** modified the 2023 approach to avoid “cross-talk” with these knobs.

<sup>4</sup>see **EDMS 2384198**.

# WIC commissioning

All the **WICs of the 4 BBWC were tested** on the 26 March 2024.


Following the procedure, the wire current was set to 375 A (removing during the test the SIS interlock and the FGC limit to 350 A.)

The WIC behaved as expected (see [TIMBER snapshot](#)).

# 5th axes' alignments

The 5th axis alignment scan was performed on 30 March evening.<sup>5</sup>

- ▶ TCTPV.4L1.B1: from -0.36 to 0.00 mm
- ▶ TCTPV.4R1.B2: from +0.50 to +0.60 mm
- ▶ TCTPH.4L5.B1: from +1.16 to +1.35 mm
- ▶ TCTPH.4R5.B2: from +0.02 to +0.35 mm



**Alignment was deployed on the 3 April<sup>6</sup>.**

<sup>5</sup>See [TIMBER snapshot and https://github.com/sterbini/5th\\_axis\\_tct\\_alignement/](https://github.com/sterbini/5th_axis_tct_alignement/).

<sup>6</sup>See TIMBER snapshot.

# Interlock chain test with beam

The **TCTPH.4L5.B1** interlock chain with beam was tested in FILL9456 (3 April).

The **TCTPV.4R1.B2** interlock chain with beam was tested in FILL9461 (4 April).

# Summary

- ▶ After the decision to lock-out the Q4s in IR1, we reconsidered the knobs for the wire demonstrators. We propose matching **4 knobs using 9 quads on the TCT sides**
  - ▶ Q5-6-7-8-9-10-11-12-13 for IR1,
  - ▶ Q4-5-7-8-9-10-11-12-13 for IR5. We had the green light from LMC to power the BBCW at  $\beta^*=30$  cm pending MPP's OK.
- ▶ We show the **linearity** of the knobs with respect to  $I_W$  and the  $\beta^*$ .



# Summary

- ▶ After the decision to lock-out the Q4s in IR1, we reconsidered the knobs for the wire demonstrators. We propose matching **4 knobs using 9 quads on the TCT sides**
  - ▶ Q5-6-7-8-9-10-11-12-13 for IR1,
  - ▶ Q4-5-7-8-9-10-11-12-13 for IR5. We had the green light from LMC to power the BBCW at  $\beta^*=30$  cm pending MPP's OK.
- ▶ We show the **linearity** of the knobs with respect to  $I_W$  and the  $\beta^*$ .
- ▶ **First beam tests of the wires** took place: polarity check at 450 GeV done (17 March, D. Mirarchi), first check of knobs at 6.8 TeV done (25 March, 3 and 4 April). Optics measurement scheduled today.

# Summary



- ▶ After the decision to lock-out the Q4s in IR1, we reconsidered the knobs for the wire demonstrators. We propose matching **4 knobs using 9 quads on the TCT sides**
  - ▶ Q5-6-7-8-9-10-11-12-13 for IR1,
  - ▶ Q4-5-7-8-9-10-11-12-13 for IR5. We had the green light from LMC to power the BBCW at  $\beta^*=30$  cm pending MPP's OK.
- ▶ We show the **linearity** of the knobs with respect to  $I_W$  and the  $\beta^*$ .
- ▶ **First beam tests of the wires** took place: polarity check at 450 GeV done (17 March, D. Mirarchi), first check of knobs at 6.8 TeV done (25 March, 3 and 4 April). Optics measurement scheduled today.
- ▶ HW test **done** on the repaired B1 BBCWs, WIC test **done** of the 4 BBCWs, 5th axis alignment **done**, L5.B1 and R1.B2 interlock chain with beam **done**, LM **done** (**to be analyzed**), **optics measurement to be done** (some residual tune shift).

Thank you for your attention.



[home.cern](http://home.cern)

# References (I)

-  A. Poyet, A. Bertarelli, F. Carra, S. D. Fartoukh, N. Fuster-Martínez, N. Karastathis, Y. Papaphilippou, M. Pojer, S. Redaelli, A. Rossi, K. Skoufaris, M. Solfaroni Camillocci, and G. Sterbini.  
First Experimental Evidence of a Beam-Beam Long-Range Compensation Using Wires in the Large Hadron Collider, April 2023. [arXiv:2203.08066 \[physics\]](https://arxiv.org/abs/2203.08066).
-  S Kostoglou, S Fartoukh, G Sterbini, H Bartosik, I Efthymiopoulos, G Iadarola, Y Papaphilippou, A Poyet, X Buffat, and M Hostettler.  
Beam-beam effects in Run 3, November 2021.

# Wires configurations considered

- ▶ The optics considered is the  $\beta^* = 30$  **cm** (courtesy of S. Fartoukh).
- ▶ The TCT opening assumed is **8**  $\sigma_{coll}$  (to be confirmed during commissioning), and the beam total energy 6.8 TeV.
- ▶ With the wire retraction with respect to the jaw's face of 3.0 mm, the wire's center to beam's center distance is  $\rightarrow$  **7.71 mm for IR1** and **11.82 mm for IR5**.

# Wires configurations considered


- ▶ The optics considered is the  $\beta^* = 30$  **cm** (courtesy of S. Fartoukh).
- ▶ The TCT opening assumed is **8**  $\sigma_{coll}$  (to be confirmed during commissioning), and the beam total energy 6.8 TeV.
- ▶ With the wire retraction with respect to the jaw's face of 3.0 mm, the wire's center to beam's center distance is  $\rightarrow$  **7.71 mm for IR1** and **11.82 mm for IR5**.
- ▶ if the beam is centered in the TCT and the 5th-axis is aligned, **no dipolar effect** is expected by the wires.

# Wires configurations considered

- ▶ The optics considered is the  $\beta^* = 30$  **cm** (courtesy of S. Fartoukh).
- ▶ The TCT opening assumed is **8**  $\sigma_{coll}$  (to be confirmed during commissioning), and the beam total energy 6.8 TeV.
- ▶ With the wire retraction with respect to the jaw's face of 3.0 mm, the wire's center to beam's center distance is  $\rightarrow$  **7.71 mm for IR1** and **11.82 mm for IR5**.
- ▶ if the beam is centered in the TCT and the 5th-axis is aligned, **no dipolar effect** is expected by the wires.
- ▶ a **quadrupolar effect** is expected (for  $I_w = 350$  A,  $K1L_{IR1} = 1.05E-4$  m<sup>-1</sup>,  $K1L_{IR5} = -0.44E-4$  m<sup>-1</sup>) and the knobs we are discussing aim to compensate for it.




# Tune shift induced by the wires (w/o correction)




Effect on the tunes of **wires in IR1**.

# Tune shift induced by the wires (w/o correction)




Effect on the tunes of **wires** in IR5.

# $\beta$ -beating induced by the wires (w/o correction)




$\beta$ -beating induced by  $I_W=350$  A in IR1.

# $\beta$ -beating induced by the wires (w/o correction)




$\beta$ -beating induced by  $I_W=350$  A in IR5.

# Correction in IR1




The proposed knobs consist in a **local correction**.

# Correction in IR1




Matching  $\beta_{X,Y}$ ,  $\alpha_{X,Y}$ ,  $dx$ ,  $dpx$  at the IP and  $\mu_{X,Y}$  in Q13-IP (TCT side).

# Correction in IR1



Matching  $\beta_{X,Y}$ ,  $\alpha_{X,Y}$ ,  $dx$ ,  $dp_x$  at the IP and  $\mu_{X,Y}$  in Q13-IP (TCT side).


# Correction in IR5



The proposed knobs consist in a **local correction**.




# Correction in IR5



Matching  $\beta_{X,Y}$ ,  $\alpha_{X,Y}$ ,  $dx$ ,  $dpx$  at the IP and  $\mu_{X,Y}$  in Q13-IP (TCT side).


# Correction in IR5




Matching  $\beta_{X,Y}, \alpha_{X,Y}, dx, dp_x$  at the IP and  $\mu_{X,Y}$  in Q13-IP (TCT side).

# Linearity check vs $I_W$

$I_{W,IR1}=350$  A,  $I_{W,IR5}=0$  A




$I_{W,IR1}=0$  A,  $I_{W,IR5}=350$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $I_W$

$I_{W,IR1}=300$  A,  $I_{W,IR5}=0$  A




$I_{W,IR1}=0$  A,  $I_{W,IR5}=300$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $I_W$

$I_{W,IR1}=250$  A,  $I_{W,IR5}=0$  A




$I_{W,IR1}=0$  A,  $I_{W,IR5}=250$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $I_W$

$I_{W,IR1}=200$  A,  $I_{W,IR5}=0$  A




$I_{W,IR1}=0$  A,  $I_{W,IR5}=200$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $I_W$

$I_{W,IR1}=150$  A,  $I_{W,IR5}=0$  A




$I_{W,IR1}=0$  A,  $I_{W,IR5}=150$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $I_W$

$I_{W,IR1}=100$  A,  $I_{W,IR5}=0$  A



$I_{W,IR1}=0$  A,  $I_{W,IR5}=100$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).




# Linearity check vs $I_W$

$I_{W,IR1}=50$  A,  $I_{W,IR5}=0$  A




$I_{W,IR1}=0$  A,  $I_{W,IR5}=50$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $I_W$

$I_W, IR1=0$  A,  $I_W, IR5=0$  A




$I_W, IR1=0$  A,  $I_W, IR5=0$  A




- ▶ The knob is matched at  $I_W=350$  A.
- ▶ It is **very linear wrt the  $I_W$**  ( $\beta$ -beating leakage  $<0.2\%$ ).

# Linearity check vs $\beta^*$

$I_{IR1/IR5} = 350/0$  A,  $\beta^* = 30$  cm




$I_{IR1/5} = 0/350$  A,  $\beta^* = 30$  cm




As expected, the knobs are **tele-index independent**.

# Linearity check vs $\beta^*$

$I_{IR1/IR5} = 350/0$  A,  $\beta^* = 28$  cm




$I_{IR1/5} = 0/350$  A,  $\beta^* = 28$  cm




As expected, the knobs are **tele-index independent**.

# Linearity check vs $\beta^*$

$I_{IR1/IR5} = 350/0$  A,  $\beta^* = 26$  cm




$I_{IR1/5} = 0/350$  A,  $\beta^* = 26$  cm




As expected, the knobs are **tele-index independent**.

# Linearity check vs $\beta^*$

$I_{IR1/IR5} = 350/0$  A,  $\beta^* = 24$  cm




$I_{IR1/5} = 0/350$  A,  $\beta^* = 24$  cm




As expected, the knobs are **tele-index independent**.

# Linearity check vs $\beta^*$

$I_{IR1/IR5} = 350/0$  A,  $\beta^* = 22$  cm




$I_{IR1/5} = 0/350$  A,  $\beta^* = 22$  cm



As expected, the knobs are **tele-index independent**.


# Orbit effect of the knobs



With the crossing angles in IP1/5, knobs affect the orbit (mostly for IR5 knobs). We assume it will be corrected by the CO-feedback.




# Orbit effect of the knobs




With the crossing angles in IP1/5, knobs affect the orbit (mostly for IR5 knobs). We assume it will be corrected by the CO-feedback.

# PC current limits and IR1 B1 knob




The trims are small if compared with the PCs capabilities.

# PC current limits and IR5 B1 knob




The trims are small if compared with the PCs capabilities.

# PC interlock and IR1 B1 knob (preliminary)



The trims are comparable with the PC Interlock limits but OUTSIDE.

# PC interlock and IR5 B1 knob (preliminary)



The trims are comparable with the PC Interlock limits.