

Rey.Hori / KEK

Civil Engineering Status

Nobuhiro Terunuma, KEK


On behalf of the CFS group

AWLC2020, October 20, 2020

Contents

- Anticipated schedule
- Civil Engineering activity in Japan
- Overall of the civil engineering design of ILC
- Summary

Civil Engineering related Schedule for ILC-250GeV



References; (1) TDR, (2) Recommendations on ILC Project Implementation, 2019.

ILC Civil Engineering Activity in Japan

Premise:

- Civil works are the responsibility of the host country.
- Proceed the civil design using a model route in the Kitakami Mountains and examine the issues of civil works for the ILC.

● KEK and universities in Japan, with oversea collaboration

● Experts from Industry


- WG of AAA for underground issues; experts from civil engineering companies
Advanced Accelerator Association (AAA); An organization of industrial sector to aim to make a leap in science and technology through the development of cutting-edge accelerators jointly by industry and academia.

● Enhanced activity in the Tohoku region

- **Upgrade the promotion body in Aug. 2020, “Tohoku ILC project development center”**
 - consists of **Local governments(18)**, universities(3) and Iwate ILC promotion council.
 - **Examination of issues that the region should address** in terms of environmental improvement and research facility construction around the ILC candidate site
 - Natural environment, Social and Economic impacts of ILC construction
 - System and town development for researchers and their families, ...


● Validation of Civil Engineering Design at Kitakami Mountains

- 2019/7-2020/3 by the **Rock Mechanics Committee, the Japan Society of Civil Engineers**
- **It is the first validation by 3rd party based on the real candidate site** and concluded that the “Civil Engineering Plan for ILC at Tohoku” is technically feasible.



Geological Surveys for ILC: Kitakami Mountains


ILC-250 (20.5 km)



Continuous **granite region**


HITOKABE, SENMAYA and ORIKABE bedrock

Have capability to extend the ILC up to 50 km in future

Boring geological survey 
 → Direct sampling down to the accelerator depth


Electromagnetic prospecting
 → Cracks in the rock

Seismic prospecting
 → Rock hardness




Scale of the ILC-250GeV

Here, the access tunnel of the model route assuming the Kitakami Mountains is shown. The average length of access tunnels is about 1 km.




Laser Straight Section

- BDS: “laser straight” in vertical
- ML: Cryomodule will be aligned to the geoid.



- ILC optics DECK has been updated to incorporate corrections for **geoid** and **straight sections** around the IP.
- Asymmetric straight sections
 - The e- side is longer to include undulator and dog-leg.
 - If e+ and e- MLs are at the same altitude, the IP is tilted by 0.1 mrad.
 - If e- ML is placed 0.6 m higher than e+, the IP has no tilt and BDSs are symmetrically sloped to the IP.


Main Linac (ML) tunnel




- 15 km in (e+e-) total
- follow the geoid in vertical
- **Kamaboko 9.5m X 5.5m**
- **1.5m central radiation shield**
- Further optimization will be done.



- 66 kV distribution cables
- Colling water pipes
- Fan Coil Units
- Low power and signal cables
- **RF klystrons and modulators**
- **Electric Power Stations**



- **ML Cryomodules**
- **RTML**
- Low power and signal cables




Rev.Hori / KEK


Damping Ring

- Circumference: 3.2km
- Start with two rings
- Arc section: **single tunnel, no central shield.**
- Straight section: **Kamaboko** with a central shield (3.5m in TDR).

Arc Section




Straight Section



Interaction Point (IP)

IP surface area
about 78,500 m²

Layout will be optimized.



AC Power distribution
154 kV Main Power Station at IP
→ 66 kV → tunnel → Access points


PM-10

PM-8




**4000t
Gantry Crane**

PM+8

PM+10



Detector Hall



Layout of the detector hall and around will be optimized with detector groups.




Rey.Hori / KEK

Access Points x 5 (other than IP)

Surface Station

about 16,600 m²



The ground layout is optimized by the station.



Underground Hall
about 3,800 m²
& 38,500 m³

Underground Access/utility Halls


TDR Hall



Updated Design

- Separated halls by function
- Optimized cross section according to the equipment
- advantage on civil engineering and installation work

Cavern for Main Beam Dump




■ Three big caverns

- Two main beam dumps
- e- dump for undulator, low energy collision (5 x 5 Hz)

■ The main beam dump has been designed for **1 TeV collisions**.

- 5 m thick concrete shield in all directions
- 17 MW power cooling (wider utility hall)
- **¼ volume of detector hall**

■ The civil engineering design is updating with experts from Industry (AAA).



Civil Engineering Design for Positron Source

Since civil engineering (CE) work will start immediately after the preparation period, a lot of detailed design work is expected during the preparation period, so the CFS Group will proceed with the basic design of the CE for the positron source in advance.

■ Have the CE design to **include the undulator scheme in any scenarios.**


- **TDR based layout**
- and have **Photon dump line** in the BDS tunnel

■ **E-driven source** will be in **separated dedicated tunnel.**

- **add on to the TDR based design**
- From the CE view, sharing of BDS tunnel is not realistic.
- e-driven study group is developing this design.
- Access tunnel should be considered.

Design study for e-driven positron source

- Figure shows the length of the linac, taking into account the size and placement of devices.
- Positron injection into the DR uses RTL.
- Joint angle to the BDS tunnel will be optimized for local conditions.



Summary

- The CFS Group is proceeding with studies assuming that the ILC construction work will begin immediately after the ILC main preparatory phase.
- The civil engineering design of the ILC is being studied using a model route in the Kitakami Mountains. It examines local challenges in ILC construction.
- These efforts are being implemented in collaboration with KEK, universities in Tohoku, local governments, and industry.

appendix

Appendix

Major Changes related on Civil Engineering after the TDR

Change Request: approve process of the design change from the TDR


- CR-003: Detector hall with vertical shaft access
- CR-004: Extension of the ML tunnel
- CR-007: Adoption of the Asian design as sole baseline
- CR-009 and CR-014: Cryogenic Layout
- CR-012: Reduction of width of Linac Shield Wall and Tunnel Cross-Section
- CR-015: Kamaboko shaped positron BDS tunnel
- CR-017: Orientation of electron/positron linacs

BDS tunnel

TDR: Twin tunnel (accelerator and service)



2017: Single tunnel for e+ BDS
(Change Request CR-015:)




CR-015: Fig.5 tunnel cross-section model for cost estimation




2019:
Unified tunnel cross-section along the BDS
is proposed

- Civil engineering point of view
- Avoid many change of the cross-section

The **11m-wide kamaboko tunnel** along the BDS will involve the undulator positron source, photon dump line and e- BDS.



Turn-around



- For future ML extensions, the Kamaboko Tunnel should extend longer than the turnaround section.
- This will allow for external extension work to be done even during the operational period of the ILC.
- The extension will also serve as an evacuation route for the turnaround section.
- Turnaround has been enlarged +10 m in radius by the update of optics, corrected gap between magnets.

ML tunnel prepared for future extension

