

RF power for Eupraxia@SPARC_LAB

David Alesini, INFN-LNF, Frascati

on behalf of the TeX technical team and the EuPRAXIA@SPARC_LAB RF team

2nd Workshop on efficient RF Sources



23-25 September 2024, Toledo, Spain



1. **EuPRAXIA@SPARC_LAB Project**

- X Band LINAC
- X BAND RF MODULE

2. **TEX FACILITY STATUS AND PERSPECTIVES**

- TEST OF X BAND ACCELERATING STRUCTURES
- TEST OF THE RF COMPONENTS



3. **S BAND INJECTOR**

⇒ The project EuPRAXIA@SPARC_LAB is the **pillar** of the **European Project EUPRAXIA** (<http://www.eupraxia-project.eu/>) and is project based on beam driven plasma wakefield acceleration (**PWFA**). It aims at constructing a FEL radiation source ($\lambda_{\text{FEL}}=4 \text{ nm}$) combining:

- **1 GeV RF X-band Linac with an high brightness S band photo-injector**
- **Plasma module for PWFA.**

⇒ The project is currently in the preparatory phase of the **Technical Design Report** (end 2025).

⇒ A **new building**, now under executive design phase, will host the new Facility at LNF, the construction should start in September 2026.



⇒ The Linac uses an **S-band photo-injector** followed by an **X-band LINAC** to produce a high brightness electron beam up to an **energy of 1 GeV** ($Q = 200\text{-}500\text{ pC}$, $\epsilon_{\text{RMS}} \leq 1\text{ mm}\cdot\text{mrad}$, $\text{PRF} = 100\text{Hz}$).

⇒ The beam can be either injected directly in the FEL **undulators** or used to drive the **plasma module for PWFA** to further increase the energy.

S-band (2856 MHz)
3x E37314 60 MW Canon
Klystron + Solid State modulator

**Photocathode
RF gun**

S-band Injector

photocathode RF Gun and 4x TW
S-band structure.
(Possible upgrade in C-band)

8+2 X-band (11.994 GHz)
K300 Modulator
Canon E37119


**X-band
modules**


X-band Booster

16x, 0.9m, TW accelerating structures
that has to work at 60 MV/m



**Plasma
module**

Undulators







Power Source: Solid State Pulsed Modulator (K300) + 25 MW Klystron (Canon E37119)



6 m


Transport line: Low loss Circular waveguide



Accelerating module

2.3 m

Pumping units (CERN design) NEXTORR Pumps (SAES)




RF MODULE POWER SOURCES: ORIGINAL OPTIONS

BASELINE

CANON

- » 1x BOC on one line
- » Higher flexibility
- » Lower Modulator power requirements
- » Possible upgrade at high rep. rate of the Linac (400 Hz)




**K300 Modulator
Canon E37119**

CPI

OPTION



- » 2x BOC on one line
- » Less flexibility
- » Different LE and HE module layout
- » Lower power plants number



**K400 Modulator
CPI VKX8311HE
(HIGH EFFICIENCY)**

- » The **TEst-stand for X-band (TEX)** is conceived for **R&D and test** on high gradient X-band accelerating structures, RF components, LLRF systems
- » It has been co-funded by Lazio region in the framework of the **LATINO project** (Laboratory in Advanced Technologies for INnovation).
- » The setup has been done in **collaboration with CERN (that provided the klystron)** and it will be also used to test CLIC structures
- » **The installation and commissioning** of the whole system (Source and RF network, LLRF, vacuum and EPICS control system) have been **completed by the end of 2022** [3,4,5].
- » Then started the testing activity:

Period	Device tested at high power
Jan. - Feb. 2023	3D printed Spiral RF loads and wg
May - Oct. 2023	X-band T24 CLIC structure
Nov. - Dec. 2023	X-band Mode converter and circular wg
Jan. - Feb. 2024	X-band RF waterload from PSI
March 2024	20 cells first EuPRAXIA RF prototype



LLRF system



50 MW RF Source





VKX8311A Klystron







[3] F. Cardelli et al., 13th Int. Particle Accelerator Conf. IPAC22, Bangkok, Thailand, Jun. 2022, paper TUPOPT061

[4] L. Piersanti et al. "RF power station stabilization techniques and measurements at LNF" In Proc. IPAC24 - TUPR01.

[5] L. Piersanti et al. "Design and test of a klystron intra-pulse phase feedback system for electron linear accelerators" Photonics 2024, 11(5), 413.





PARAMETER	Value	
	CG	CI
Frequency [GHz]	11.9942	
Average acc. gradient [MV/m]	60	
Structures per module	2	
Iris radius a [mm]	3.85 - 3.15	3.5
Tapering angle [deg]	0.04	0
Struct. length L_s act. Length [m]	0.94	
No. of cells	112	
Shunt impedance R [$\text{M}\Omega/\text{m}$]	93-107	100
Effective shunt Imp. R_{sh_eff} [$\text{M}\Omega/\text{m}$]	350	347
Peak input power per structure [MW]	70	
Filling time [ns]	130	
Peak Modified Poynting Vector [$\text{W}/\mu\text{m}^2$]	3.6	4.3
Peak surface electric field [MV/m]	160	190
Repetition Rate [Hz]	100 (400)	



TEST AND REALIZATION OF X-BAND WAVEGUIDE COMPONENTS

COMPONENT	DESIGN BY	STATUS	LEVEL OF POWER TO BE TESTED FOR EUPRAXIA MODULE	TEST DONE SO FAR
Pump units (rect. Wav.)	CERN	Fabricated and installed @ TEX	25 MW 1.5 μ s and 70-35 MW 0.13 μ s Compressed pulse 100 Hz	45 MW, 1 μ s, 50 Hz, $P_{avg} = 2.25$ kW
Directional coupler	CERN	Fabricated and installed @ TEX	25 MW 1.5 μ s and 70-35 MW 0.13 μ s compressed pulse 100 Hz	45 MW, 1 μ s, 50 Hz, $P_{avg} = 2.25$ kW
Splitter	CERN	Fabricated and installed @ TEX	70-35 MW, 0.13 μ s Compressed pulse 100 Hz	35 MW, 0.6 μ s, 50 Hz, $P_{avg} = 1$ kW
RF load	CERN	Fabricated and installed @ TEX	18-9 MW 0.13 μ s compressed pulse 100 Hz	17 MW, 0.6 μ s, 50 Hz, $P_{avg} = 0.5$ kW
Mode converter circular/rect	INFN	Fabricated and Installed @ TEX	25 MW 1.5 μ s 100 Hz	35 MW, 1 μ s, 50 Hz, $P_{avg} = 1.75$ kW
Pump unit (circ. Waveg.)	INFN	Fabricated and Installed @ TEX	25 MW 1.5 μ s 100 Hz	35 MW, 1 μ s, 50 Hz, $P_{avg} = 1.75$ kW
3dB hybrid	CERN	Delivered	140-70 MW 0.13 μ s Compressed pulse 100 Hz	
BOC pulse compr.	PSI	Delivered	140-70 MW 0.13 μ s Compressed pulse 100 Hz	



Currently, the test stand TEX is based on **CPI VKX8311A** Klystron **on loan from CERN** already **commissioned and in operation**.

Three other klystrons are being installed at TEX:

1. CANON X Band 25 MW, 400 Hz E37119

Status:

- FAT of the klystron done @ CANON on a PFN modulator 11/2023, 25 MW, 10 Hz, $t=1.5\mu s$
- FAT of the RF source @Scandinova 05/2024, full power in diode mode
- Modulator and klystron positioned at TEX

3. CANON C Band E37217

Status:

- FAT of the klystron done @ CANON on a PFN modulator 11/2023, 20 MW, 10 Hz, $t=2.5\mu s$
- FAT of the RF source @Scandinova 05/2024, full power in diode mode
- Modulator and klystron positioned at TEX


2. CPI X Band 50 MW, 100 Hz High efficiency VKX8311HE

Status:

- Tender has been done, realization phase (expected delivery from CPI Sept 2025)

The **commissioning of these sources** and the waveguide networks is scheduled for January 2025, after the installation of the cooling and power systems that will serve these sources.

Parameter	Unit	Canon E37119	CPI VKX8311HE	CPI VKX8311	Canon E37217
Frequency	MHz	11994			5712
Vk beam voltage	kV	312	415	420	280
Ik cathode current	A	199	201	320	240
Peak RF output Power	MW	25	50	50	20
Average RF output power	kW	15	7,5	7,5	21
Modulator Average power	kW	80	25	48	80
RF pulse length	μs	1,5			2.5
Repetition Rate	Hz	400	100	100	400
Gain	dB	47	50	47	50
Efficiency	%	40	55	38	40
Perveance	μp	1.16	0.75	1.15	1





E37119

Parameters	Symbol	Units	Min.	Max.	Notes
Frequency	f	MHz	11993	11995	
Heater Voltage	Ef	V	---	22	3, 24
Heater Current	If	A	---	22	3
Heater Current (surge)	If(surge)	A	---	28	3
Heater Warm-up Time	tk	minutes	60	---	
Peak Forward Beam Voltage	epy	kV	---	335	4
Peak Inverse Beam Voltage	epx	kV	---	30	
Peak Cathode Current	ik	A	-10	225	
Peak Drive Power	pd	W	---	500	5
Peak RF Output Power	po	MW	---	25.5	
Average RF Output Power	Po	kW	---	15.3	
Collector Dissipation	Pcol	kW	---	100	
Pulse Width(duration) (epy)	t(epy)	μs	---	3.5	6
Pulse Width(duration) (rf)	t(rf)	μs	---	1.5	7
Pulse Repetition Rate	pr	pps	---	400	
Load VSWR (occasionally)	σL		---	1.4:1	8,9
Load VSWR (stable condition)	σL,s		---	1.2:1	9
Coolant Flow (collector)	Qw	l/min	65	---	10
Coolant Flow (body)	Qw	l/min	15	---	10
Coolant Flow (window)	Qw	l/min	1.8	3	10
Inlet Coolant Temperature	Tw,i	centigrade	5	35	10, 11
Outlet Coolant Temperature	Tw,o	centigrade	---	65	10
Coolant Pressure Collector	Pw,c	MPa	---	1	10
Body	Pw,b	MPa	---	0.8	10
Window	Pw,w	MPa	---	0.3	10
Waveguide Pressure (Vacuum)	PW/G	Pa (Torr)	---	1.3x10 ⁻⁵ (1x10 ⁻⁷)	13
Environmental temperature	Te	Centigrade	0	40	12
Environmental humidity	H	%	0	90	11, 12
Ion pump Voltage	Eip	kV	3.1	3.9	2



E37119

Parameters	Symbol	Units	Min.	Max.	Notes
Frequency	f	MHz	5713	5713	
Heater Voltage	Ef	V	---	24	3, 4, 5, 27
Heater Current	If	A	---	24	5
Heater Current (surge)	If(surge)	A	---	30	5
Heater Warm-up Time	tk	minutes	60	---	
Peak Forward Beam Voltage	epy	kV	---	280	6, 7
Peak Inverse Beam Voltage	epx	kV	---	30	7A
Peak Cathode Current	ik	A	-10	240	8, 8A
Peak Drive Power	pd	W	---	500	9
Peak RF Output Power	po	MW	---	21	
Average RF Output Power	Po	kW	---	21	
Collector Dissipation	Pcol	kW	---	100	
Pulse Width(duration) (epy)	t(epy)	μs	---	5.0	10
Pulse Width(duration) (rf)	t(rf)	μs	---	2.5	11
Pulse Repetition Rate	pr	pps	---	400	
Load VSWR (occasionally)	σL		---	1.4:1	11A
Load VSWR (stable condition)	σL		---	1.2:1	11B
Coolant Flow					
Collector	Qw	l/min	65	---	12, 14
Body	Qw	l/min	15	---	12, 14
Waveguide	Qw	l/min	2	3	12, 14
Inlet Coolant Temperature	Tw,i	°C	5	35	12, 12A
Outlet Coolant Temperature	Tw,o	°C	---	65	12, 14
Coolant Pressure					
Collector	Pw	MPa	---	1	12
Body	Pw	MPa	---	0.8	12
Windows and waveguide	Pw	MPa	---	0.3	12
Waveguide Pressure (Vacuum)	PW/G	Pa (Torr)	---	1.3x10 ⁻⁵ (1x10 ⁻⁷)	13
Environmental Temperature	Te	°C	0	40	12A
Environmental Humidity	H	%	0	90	12A, 12B
Ion pump Voltage	Eip	kV	3.1	3.9	2

VKX-8311A3








Communications
& Power Industries

PARAMETER	UNITS	VALUE
RF Frequency	MHz	11994.2
Bandwidth at -1dB	MHz	≥ 10
RF Power:		
Pout - Peak Power at the output flange of the klystron [*]	MW	≥ 45
Average RF Power	kW	≥ 3.75
Maximum Klystron peak Current	A	240
Maximum High voltage applied to the cathode	kV	450
Trf, RF Pulse length (at -3dB) [*]	μs	1.5
HV Video Pulse length (FWHM)	μs	≤ 3.5
Repetition Rate [*]	Hz	100
Tolerable peak reverse voltage	kV	≤ 30
Efficiency at peak power	%	≥ 46
RF gain at peak power	dB	≥ 47
Perveance	μA/V ^{1.5}	≥ 0,67
Variation of anodic current (at klystron peak power) within +/-5% cathode heater power variation	%	±3
Stability of RF output signal over the range of 0.5-1.0 of max. power and 0.75 -1.0 of max. cathode HV to be:		
RF input vs output phase jitter [**]	RF degree	± 0.5 max
RF amplitude jitter	%	± 0.25 max
Fraction of RF power in 2 nd harmonic	dB	≤ -20
Pulse failures (arcs etc.) during 24-hour continuous test period		≤ 1
Radiation at 1 m distance from klystron	μSv/h	≤ 1

C-BAND GUN @ TEX

- ⇒ A new **C band RF photo-gun** with the **brazing free** technology has been designed, built, assembled and installed at PSI (with solenoid and vacuum chamber): **I-FAST project**.
- ⇒ The design is compatible with the **400 Hz** operation
- ⇒ The high power tests showed **~160 MV/m** cathode peak field limited w/o gun limitation.
- ⇒ The C band gun **will be installed in the TEX** facility and used for high beam quality generation and experiments.
- ⇒ The possibility of a full **C band injector for EUPRAXIA@SPARC_LAB** is also being considered for the possibility to operate at 400 Hz.



- ⇒ The Linac uses an **S-band photo-injector** followed by an **X-band LINAC** to produce a high brightness electron beam up to an **energy of 1 GeV** ($Q = 200\text{-}500\text{ pC}$, $\epsilon_{\text{RMS}} \leq 1\text{ mm}\cdot\text{mrad}$, $\text{PRF} = 100\text{Hz}$).
- ⇒ The beam can be either injected directly in the FEL **undulators** or used to drive the **plasma module for PWFA** to further increase the energy.

S-band (2856 MHz)
3x E37314 60 MW Canon
Klystron + Solid State modulator

X-band (11.994 GHz)
K300 Modulator
Canon E37119

Photocathode RF gun

S-band Injector

photocathode RF Gun and 4x TW S-band structure.
(Possible upgrade in C-band)


X-band Booster


16x, 0.9m, TW accelerating structures that has to work at 60 MV/m

X-band modules


Plasma module

Undulators





S BAND INJECTOR RF SCHEMATIC LAYOUT



PARAMETER	Structure lenght	
	3 m	2 m
Frequency [GHz]	2.856	
Average acc. gradient [MV/m]	21	35
Number of Structures	2	2
Iris radius a [mm]	11.76	10.65
Tapering of structure	$2\pi/3$ C.I.	
No. of cells	85	57
Shunt impedance R [MΩ/m]	56	59
Effective shunt Imp. R_{sh_eff} [MΩ/m]	109	114
Peak input power in the structure [MW]	67.2	120
Input power averaged over the pulse [MW]	38.6	69
Average dissipated power [kW]	3	5.1
P_{out}/P_{in} [%]	32	
Filling time [ns]	920	
Peak Modified Poynting Vector [W/μm ²]	0.43	1
Peak surface electric field [MV/m]	70	115
Unloaded SLED/BOC Q-factor Q_0	150000	
External SLED/BOC Q-factor Q_E	21000	
Required Kly input power (w/o att.) [MW]	12.1	21.5
RF pulse [μs]	4	
Rep. Rate [Hz]	100	

Klystron Canon E37314

PARAMETER	Value E37314
Frequency [GHz]	2,856
Maximum ouput power [MW]	60
Average power [kW]	24
Efficiency (%)	41
Gain (dB)	53
Pulse Length (μs)	4
Rep. Rate [Hz]	100
Beam Voltage [kV]	360
Beam current [A]	412

Required klystron powers (considering the waveguide attenuation):

K2 ⇒ ~30-35 MW




K3 ⇒ ~45-50 MW

K1: Modulator k300 + Klystron Canon E37314

K2&K3: Modulator k400 + Klystron Canon E37314




X-band Linearizing Cavity and POLARIX deflectors



X-band	
Resonant frequency	11.9942 GHz
E acc	20 MV/m
E peak	38 MV/m
Number of cells	7
Length	11 cm

a = 4 mm	TW	SW
f	11.9942 GHz	11.9942 GHz
Q	6600	8,600
Vg	3.6 %	-
r	85.3 MΩ/m	80 MΩ/m
Eacc	16.5 MV/m	16.3 MV/m
alpha	0.63 1/m	-
Lt	10 cm	10 cm
Coupling β	-	2
Fill time Tf	9.3 ns	-
Build up τ	-	76 ns*
Pin	3.2 MW	0.37 MW

2 X band klystrons dedicated to this



Requirements phase jitter (compliant with BD requirements):

- **0.02 deg S band** (S-band RF stability state of the art (PSI))
- **0.06 deg X band**

⇒ **We cannot develop the system in house** because of the complexity, dimension, maintenance for a user facility.

⇒ **2 industrial partners** willing to participate to X-band LLRF R&D (Instrumentation Technologies - solid LLRF experience, Safran - new to high frequency applications);

⇒ The **internal procedures** for the tender for the production of the whole LLRF system should **start by the end of 2024**;

⇒ Detailed **jitter studies on X-band power station** carried out at **TEX facility in February 2024** [1] (no klystron loop):

1. Driver added jitter: <0.04 deg rms
2. Klystron added jitter: <0.04 deg rms
3. LLRF added jitter (tender spec.): <0.015 deg rms
4. **Estimated RF station jitter: <0.06 deg rms**

⇒ **Dedicated stability measurements** will be carried out at SPARC in S band after the SABINA upgrade.

⇒ We believe also that **with solid state modulator and klystron loops** we can have an additional jitter reduction from new fast intra-pulse phase feedback system [2] to be evaluated for S-band and X-band stations at SPARC and TEX respectively.

⇒ **Jitter compression down to 0.019 deg rms** already demonstrated for C-band station at SPARC in Dec 2023.

[1] L. Piersanti et al. "RF power station stabilization techniques and measurements at LNF" In Proc. IPAC24 - TUPR01.

[2] L. Piersanti et al. "Design and test of a klystron intra-pulse phase feedback system for electron linear accelerators" Photonics 2024, 11(5), 413.



Figure 3: TEX facility RF block diagram.

- ⇒ **EuPRAXIA@SPARC_LAB** is the next INFN-LNF facility. It is the beam driven pillar of the European EuPRAXIA project
- ⇒ The new machine include **10 X band power stations**: baseline **CANON E37119**
- ⇒ **TEX (Frascati Test stand for X-band)** is of fundamental importance to validate all the X band components, structures
 - A new X-band RF source based on the **E37119 klystron** (25 MW, 400Hz) will be commissioned at TEX in the next months, together with a **C-band** source for C-band photoinjector testing.
 - A **high efficiency klystron 50 MW VKX8311HE** developed by CPI/CERN should be commissioned in end 2025.
- ⇒ Many **X-band RF components** of the EuPRAXIA RF module have been purchased and tested at nominal power other will be tested soon:
 - The X-band BOC from PSI
 - The hybrid
- ⇒ **X-band structures**: An intensive prototyping activity is ongoing exploiting the new vacuum furnace at LNF (Two **full-scale mechanical prototypes**, the **20 cells CI RF prototype**, A **full-scale 0.9m RF prototype** for high power test is in production.
- ⇒ For the S band Injector 60 MW CANON Klystron are foreseen

THANK YOU FOR YOUR ATTENTION!

Aknowledgements:

INFN-LNF: F. Cardelli, S. Bini, B. Buonomo, S. Cantarella, G. Catuscelli, R. Clementi, L. Faillace, M. Ferrario, A. Gallo, C. Di Giulio, E. Di Pasquale, G. Di Raddo, G. Latini, A. Liedl, V. Lollo, L. Piersanti, S. Pioli, B. Serenellini, L. Spallino on behalf of the, INFN-LNF Accelerator Division and Technical Division

CERN: W. Wuensh, N. Catalan-Lasheras, A. Grudiev, G. McMonagle on behalf of the CLIC group

SLAC: V. A. Dolgashev

