**High Efficiency Klystrons** 



## Design, Fabrication, and HV Testing of a HV RF Feedthrough (HVRFT) for a 1 MW CW TS-MBK

Anisullah Baig<sup>1,2</sup>, Graeme Burt<sup>2,3</sup>, Igor Syratchev<sup>1</sup>

<sup>1</sup>CERN (SY-RF-MKS), Switzerland <sup>2</sup>Lancaster University, UK <sup>3</sup>Cockcroft Institute, UK




#### Two-Stage Multi Beam Klystron (TS-MBK) Technology in L-band

#### **Features:**

- 1. Bunching at a low voltage (high perveance). Very compact RF bunching circuit.
- 2. Bunched beam acceleration and cooling (reducing  $\Delta p/p$ ) along the short DC voltage post-accelerating gap.
- 3. Final power extraction from high-voltage (low perveance) beam → High efficiency.

## Additional advantages:

- 1. For pulsed tubes, the second HV stage can be operated in DC mode. Thus, simplifying the modulator topology (cost/volume) and increasing the modulator efficiency.
- 2. Simplified feedback for the first stage pulsed voltage. Improved klystron RF phase and amplitude stability.




Commercial HE MBK ( $\eta \approx 70\%$ )



## **Motivation:**

- ✤ The input RF section of the TS-MBK is held at a potential of approximately -54 kV.
- To inject an RF while isolating the low power RF source from the HV DC side a highvoltage RF feedthrough (HVRFT) is required.







## **Requirements:**

- To do so, a UHF band PCB microstrip filter was envisaged. A high dielectric constant, a high electrical breakdown strength, and a low dissipation factor are key requirements.
- Arlon AD1000 (woven glass reinforced PTFE/ceramic filled) meets these requirements and was selected. Rogers corporation is the sole manufacturer of this material.

ypical Properties:		AD1000	
Property	Units	Value	Test Method
. Electrical Properties			
Dielectric Constant (may vary by thickness)			
@1 MHz	-		IPC TM-650 2.5.5.3
@ 10 GHz	-	10.20	IPC TM-650 2.5.5.5
Dissipation Factor			
@ 1 MHz	-		IPC TM-650 2.5.5.3
@ 10 GHz	-	0.0023	IPC TM-650 2.5.5.5
Temperature Coefficient of Dielectric	-		
TCεr @ 10 GHz (-40-150°C)	ppm/°C	-380	IPC TM-650 2.5.5.5
Volume Resistivity			
C96/35/90	MΩ-cm	1.40x10 <sup>9</sup>	IPC TM-650 2.5.17.1
E24/125	MΩ-cm	5.36x10 <sup>7</sup>	IPC TM-650 2.5.17.1
Surface Resistivity			
C96/35/90	MΩ	1.80x10 <sup>9</sup>	IPC TM-650 2.5.17.1
E24/125	MΩ	3.16x10 <sup>8</sup>	IPC TM-650 2.5.17.1
Electrical Strength	Volts/mil (kV/mm)	622 (24.5)	IPC TM-650 2.5.6.2
Dielectric Breakdown	kV	>45	IPC TM-650 2.5.6
Arc Resistance	sec	>180	IPC TM-650 2.5.1









#### Stripline Layout

#### Arrangement of Layers








Low-power RF output (-53.75 kV side)




Taking Arlon AD1000 as the substrate ( $\epsilon$ =10.2, tan $\delta$ =1.6e-3):

- ✓ Freq: 400.8 MHz,
- ✓  $S_{21}$ : -2.56 dB (with dielectric losses).
- ✓ BW: ~ 3.95 MHz
- ✓ Electric strength: 24.5 kV/mm
- ✓ DC isolation: 60 kV (tested)
- ✓ Compact (UHF band): 218mm x
  167mm x 46mm

#### Simulated S-Parameters









## **Prototyping: A Two(ish)-Pronged Approach**

- (a) HVRFT-I → The prototype for high-voltage tests, built using a resin with similar HV properties to AD1000. The multi-layer fabrication and HV testing steps also provide valuable experience.
- (b) HVRFT-II → The real deal. To be assembled in AD1000 at CERN's PCB lab. Prior to this the assembly process will also be tested with FR-4 to ensure conformity.

#### **Overview:**

Model	Material	Fabrication	Status/HV Testing
HVRFT-I (for HV test only)	SikaBiresin® RE 891-98 RESIN (similar HV specs → 27kV/mm dielectric strength vs Arlon's 24 kV/mm)	CERN's Polymer Lab (3-layer process).	Completed in 2023.
HVRFT-II Rogers Arlon AD1000 (high HV and RF performances)		CERN-MPT (PCB) Lab Stack description: 4-layers thick, 166.75mm x 218mm x 56.565mm.	Material procured and assembly in progress – to be tested in late 2024/early 2025.



## **Prototyping: A Two(ish)-Pronged Approach**

- (a) HVRFT-I → The prototype for high-voltage tests, built using a resin with similar HV properties to AD1000. The multi-layer fabrication and HV testing steps also provide valuable experience.
- (b) HVRFT-II → The real deal. To be assembled in AD1000 at CERN's PCB lab. Prior to this the assembly process will also be tested with FR-4 to ensure conformity.

Overview:			
Model	Material	Fabrication	Status/HV Testing
HVRFT-I (for HV test only)	SikaBiresin® RE 891-98 RESIN (similar HV specs → 27kV/mm dielectric strength vs Arlon's 24 kV/mm)	CERN's Polymer Lab (3-layer process).	Completed in 2023.
HVRFT-II	Rogers Arlon AD1000 (high HV and RF performances)	CERN-MPT (PCB) Lab Stack description: 4-layers thick, 166.75mm x 218mm x 56.565mm.	Material procured and assembly in progress – to be tested in late 2024/early 2025.

#### I'll focus on how we got here first.





•

### **Experiment: Microstrip HV Test in SikaBiresin® RE 891-98**

A preliminary high-voltage test was first conducted with the resin.

- Parallel microstrip lines were embedded, as pictured on the right.
- Gaps of 5 and 10 mm were present in the adjacent lines.








## **Experiment: Microstrip HV Test in SikaBiresin® RE 891-98**

- No substantial leakage current below 60 kV was observed during testing, for sets of parallel strips with gaps of both 5 mm and 10 mm.
- However, for DC voltages of >60 kV, leakage current develops through combination of local discharges and surface conduction.
- After 70 kV, a sharp rise in leakage current was observed.
- $\rightarrow$  Onwards to assembly!





## HVRFT-I (for HV test only): Assembly Process


✤ Copper striplines prepped.




Stripline placement/alignment.




 Mould and slotted ground plane ready for 1<sup>st</sup> layer of resin.



Top plane, and addition of 2<sup>nd</sup> layer of resin.



 After addition of 1<sup>st</sup> layer, resin at room temp/pressure.



 Addition of N-type coaxial connectors.




Thanks to Gianfranco Ravida (MKS) and Sebastien Clement (CERN Polymer Lab)!



## HVRFT-I (for HV test only): Assembly Process

\* Copper striplines prepped.

- Mould and slotted ground plane ready for 1<sup>st</sup> layer of resin.
- After addition of 1<sup>st</sup> layer, resin at room temp/pressure.




Thanks to Gianfranco Ravida (MKS) and Sebastien Clement (CERN Polymer Lab)!



## **HVRFT-I: High-Voltage Test**

#### 60 kV Test




Leakage current = 0.00 mA (supply) Leakage current = 10 nA (ammeter) Almost 100 hrs+ (endurance test !)

#### 80 kV Test setup




#### **80kV Test Results**



- No leakage current observed during 60 kV tests shown on the left (sensitivities of 10 nA at ammeter and 10 μA on supply).
- ✓ 80 kV testing at Partial Discharge (PD) facility showed leakage current/charge close to background values (as in air without DUT).



## **HVRFT-I:** Partial discharge (PD) Measurements





## **Prototyping: A Two(ish)-Pronged Approach**

- (a) HVRFT-I → The prototype for high-voltage tests, built using a resin with similar HV properties to AD1000. The multi-layer fabrication and HV testing steps also provide valuable experience.
- (b) HVRFT-II → The real deal. To be assembled in AD1000 at CERN's PCB lab. Prior to this the assembly process will also be tested with FR-4 to ensure conformity.

Overview	1		
Model	Material	Fabrication	Status/HV Testing
HVRFT-I (for HV test only)	SikaBiresin® RE 891-98 RESIN (similar HV specs → 27kV/mm dielectric strength vs Arlon's 24 kV/mm)	CERN's Polymer Lab (3-layer process).	<u>Completed in 2023.</u>
HVRFT-II	Rogers Arlon AD1000 (high HV and RF performances)	CERN-MPT (PCB) Lab Stack description: 4-layers thick, 166.75mm x 218mm x 56.565mm.	Material procured and assembly in progress – to be tested in late 2024/early 2025.

#### And now, where we're heading next.




Overview

## HVRFT – II (Arlon): Situation Report

- Components and material procured (AD1000 laminate/glue, stacking layout ready).
- Striplines have been prepped and connectors soldered.
- A pre-AD1000 assembly is currently being prepared prior to doing so in Arlon ("one and done" for final assembly).
- A 5x5 cm AD1000 sample is being stacked and prepared for pre-fabrication measurement of dielectric properties (done inhouse at CERN).

 $\rightarrow$  Onwards!






## **Summary:**


- ✓ HVRFT-I prototype has been shown to withstand 60 kV for 100+ hours (completed in 2023).
- HVRFT-II plan: Production is underway at CERN Micropattern technologies workshop (PCB Lab)

	July		Oct	L	ate 2024/Early 2025.	
•	Stripline prep Pin soldering. Mock stacking	•	Stacking at MPT workshop	1	Device completion, then RF and HV tests.	





#### (b) Mechanical drawings prepared.



#### (c) AD1000 laminate/glue stacking layout prepared.




# Thank you !




# **Bonus Slides**



## **HVRFT-I (for HV test only): RF Measurement**




#### Simulation: $\varepsilon = 4$ , tan $\delta = 0.04$ @ 100 Hz





## **HVRFT-I: Testing Configurations**



**Config-B** 





**Config-D** 



Α	centre pin-I to centre pin-II	58 kV – No leakage (res 10µA), <u>Humming sound</u>
В	ground conn-I to ground conn-II	> 50 kV – leakage 10µA (humming)
С	Connector's both pins @ same DC (using cable)	> 39/40 kV – leakage 10µA (humming)
D	Same as C – biased separately	Same as C

- HV Testing in different configurations showed leakage current 0.01 mA (scale in Henzinger supply) = 10 micro Amps (10,000 nA), for HV-applied > 40 kV (full connector engaged)
- \* The leakage/local surface conduction we saw was merely an artifact of the measurement setup.






#### **PD** testing instrument control



For charge calibration




- Striplines in epoxy under test.
- To compare leakage current and PD charge measurements, before actual test on HVRFT-I.




# **Partial Discharge**

What is it?


- Localized electrical discharge that only partially bridges the insulation between conductors ... [IEC 60270].
- Releases energy where the constructor didn't plan.
- Decomposes the surrounding materials.
- Reduces the lifetime.
- Initiating the final breakdown.



Internal discharge in laminated material



Surface Discharge



Cavity / Void discharge



Treeing

Corona discharge

in gaseous media <u>e.g.</u> around conductors

New Coaxial Cable

#### From Tobias, CERN HV team.

Inner Insulation



[1]