


HL-LHC IT String Quality Assurance & Control

N. Heredia García (TE-MPE-SF)
On behalf of WP16

Scope of the talk

- Introduction
- Quality design
- Quality assurance
- Quality control
- Non-conformities
- Lessons learned
- Conclusions





Introduction


- Careful consideration of quality management driven by the diverse components, constraints and required stakeholders.
- Three phases of quality management have been considered, defined by PMI.
- the IT String follows the quality standards and processes established for the HL-LHC project within the quality plan.

Phase	Goal	Description
Quality design	Plan quality management	Understand the specific needs and requirements of the project. It involves the definition of processes, tools and performance metrics.
Quality assurance	Manage quality	Ensure that the project meets the defined quality standards and requirements. It involves regular reviews, and continuous improvement.
Quality control	Monitor, record and control quality	Validation of the system to ensure a qualified output. It involves testing and corrective actions.




Quality design: Requirements & Expectations


Project organization chart



Scope baseline



Safety analysis




Test plan



Quality design: Tools

Project planning



Other tools











Cost tracking




Integration model





Quality Assurance: Process

 The tools developed during the quality design phase have been continually updated.



The IT String coordination team has organized/participated in multiple meetings to present project updates, discuss next steps, address non-conformities, provide lessons learned... String Technical Coordination Meeting

String Validation Program Meeting

String Controls Meeting

String Quality Meeting

String Day

Project Steering Meeting

Technical Coordination Committee

Cost & Schedule Review

HL-LHC Annual Meeting





To enhance project execution, various changes, measures, and tools have been implemented, reflecting engagement to continuous improvement:


Installation sequence
















More info in "HL-LHC IT String Technical Coordination & Safety" by D. Bozzini

To enhance project execution, various changes, measures, and tools have been implemented, reflecting engagement to continuous improvement:

Roles and responsibilities




Cost monitoring








Operational drawings






To enhance project execution, various changes, measures, and tools have been implemented, reflecting engagement to continuous improvement:



Communication strategy








To enhance project execution, various changes, measures, and tools have been implemented, reflecting engagement to continuous improvement:

Communication strategy


IPAC 21



MT 28 (2023)



IPAC 24



ASC 24







Quality Assurance: HL-LHC


The IT String has adhered to HL-LHC processes for requesting and documenting deviations and/or changes with regards to the baseline scenario during project execution, including:

ECR




Ex: <u>EDMS 2102130</u>

SCR



Ex: <u>EDMS 2799934</u>

DMR



Ex: EDMS 2717815

NCR




Ex: EDMS 3025021




Quality Control: Process


- Quality control tests are managed by the equipment owner.
- The String coordination team:
 - Ensure proper conditions for the execution of the tests.
 - Follow up the activities on-site.
 - Check that the test results are documented.
- Tests procedures are defined as part of the String Validation Program.













Quality control: MTF

- For the follow up of the quality checks WP16 proposed a MTF structure that was agreed with the HL-LHC Quality Office.
- The structure is divided in several systems, and steps are defined for each of them.
- Steps are extracted from commissioning and operation procedures.










Quality control: Steps

- Information included in a MTF step:
 - Description
 - Status
 - Executor
 - Activity start date
 - Activity end date
 - EDMS docs.: Test result reports, confirmation emails, non-conformities









Non-conformities: Process

HL-LHC process in place (https://edms.cern.ch/document/1499015):



Detection (QC)

Technical discussions

Decision

Actions ongoing

Closure



Document Draft EDMS Evaluation Review STCM





 Addressing non-conformities: It's imperative to document these instances comprehensively, to prevent their recurrence in the HL-LHC tunnel installation ensuring a meticulous follow-up by the entire IT-String / HL-LHC project teams.



Non-conformities: Template

Information included in the nonconformity:





Page 2 of 3



Template EDMS No.: 1501109

Concession 🛛 2024-02-05

Date Closure 2024-02-05

M. Bajko, TE-MPE-SF

Non-conformities: Table

 Table of non-conformities to keep track of documentation status. Reviewed at the String Technical Coordination Meeting.

Ref.	NCR Description	Status	Ap. Date	EDMS	Criticality	Decision	Manag. team	Equipment	Detect. phase	Det. Year	Class
	NCR of TL02	1. To be Opened	TBD	TBD	Non-Critical	Repair	WP16	Cryogenics	Commissioning	2024	Mechanical
LHC-XMSAD-QN-0003	NCR of water-cooling plates for busbars	2. In Work	TBD	3162382	Non-Critical	Repair	WP16	Warm powering	Commissioning	2024	Manufacturing
LHC-XMSA-QN-0002	NCR - Integration conflict between alignment system and SQXL	2. In Work	TBD	<u>3153667</u>	Non-Critical	Repair	WP16	FRAS	Integration	2024	Integration
LHC-XMSAH-QN-0003	NCR - Acceptance criteria for WCC High Voltage Tests in the HL-LHC IT String	2. In Work	TBD	3045592	Non-Critical	Concession	WP16	Electrical infrastructure	Commissioning	2023	Electrical
LHC-XMSAA-QN-0001	NCR - Excessive Heat Load Detected in Line C within TL01	2. In Work	TBD	<u>3044384</u>	Non-Critical	Repair	WP16	Cryogenics	Operation	2023	Mechanical
LHC-XMSAA-QN-0005	NCR - Leak tightness of the SQXL main volume envelope	2. In Work	TBD	3075007	Non-Critical	Repair	WP16	Cryogenics	Commissioning	2024	Vacuum
LHC-XMSAH-QN-0004	NCR - WCC weight distribution plates at the extremities of the cable trays	4. Closed	15/07/2024	3117788	Non-Critical	Repair	WP16	Electrical infrastructure	Installation	2024	Mechanical
LHC-XMSAH-QN-0002	Non-conformity of cables trays supporting system for WCC	4. Closed with Warnings	15/07/2024	2804269	Non-Critical	Repair	WP16	Electrical infrastructure	Operation	2022	Mechanical
LHC-XMSA-QN-0001	NCR - Conflict between cable trays and ROCLA in the racks zone	4. Closed	07/06/2024	3093233	Non-Critical	Repair	WP16	Electrical infrastructure	Operation	2024	Transport
LHC-XMSAC-QN-0001	Flexible busbars manufacturing for the IT String	4. Closed	13/05/2024	3045423	Non-Critical	Repair	WP16	Cold powering	Installation	2023	Manufact. & instal.
LHC-XMSAD-QN-0001	Cable convention for connecting water flow switches to 14 and 18 kA PC	4. Closed	29/04/2024	3018444	Non-Critical	Repair	WP16	Water distribution system	Commissioning	2024	Electrical
LHC-XMSAH-QN-0001	NCR - Water Flow Switches Functional Range for the Water-Cooled Cables on the 2kA Circuits	4. Closed	29/04/2024	3025021	Non-Critical	Concession	WP16	Water distribution system	Operation	2024	Other
LHC-XMSAA-QN-0002	IT STRING - NCR - SQXL - Shape of service modules	4. Closed	22/03/2024	<u>2961669</u>	Non-Critical	Concession	WP16	Cryogenics	Installation	2022	Mechanical
LHC-XMSAA-QN-0003	IT STRING - NCR - SQXL - Pipe element vacuum vessel reinforcement	4. Closed	22/03/2024	2961672	Non-Critical	Repair	WP16	Cryogenics	Installation	2023	Mechanical
LHC-XMSAA-QN-0004	IT STRING - NCR - SQXL - DN100 Instrumentation Feedthroughs	4. Closed	22/03/2024	<u>2961678</u>	Non-Critical	Repair	WP16	Cryogenics	Commissioning	2023	Manufact. & instal.
LHC-XMS-QN-0001	Non-conformity SM18 floor for jack shims Q3	4. Closed	02/04/2024	2872779	Non-Critical	Concession	WP16	FRAS	Integration	2023	Integration




Non-conformities: Quality Meetings

- A series of meeting have been launched with the HL-LHC Quality Office. Assets codes of the equipment coming to the IT String are been identified.
- Using the asset codes, non-conformities have been extracted using Pentaho tool and some of them reviewed. Also, assets will be attached to the String MTF structure to have full traceability of their installation.
- On a weekly basis, the HL-LHC Quality Office informs WP16 via email about the status of open non-conformities in the HL-LHC project.

Feedback from IT String Day III:


 Handling Non-Conformities: Identifying non-conformities for the String (out of all non-conformities traced across the project), crucial for HL-LHC, presents a challenge. Discussions focused on methods like tagging these issues in databases or Excel sheets. The focus is on comprehensive documentation and ensuring easy accessibility of these records for future reference is crucial.





Non-conformities: Quality Meetings

- For the equipment nonconformities tagged as "electrical", an exercise is being initiated in the coordination team to integrate them as part of the general instrumentation layout drawing.
- Deviations from the baseline will also be signaled in this "As-built" drawing.
- This drawing will help to analyse the test results.







Lessons Learned

- Lessons learned have been transmitted to the HL-LHC project in different forums (WP15 integration meeting, TCC, String Day).
- Non-conformity reports contain a chapter dedicated to lessons learned.
- Working meetings have been organised with the intervening teams after completing an installation to discuss areas of improvement.









Conclusions

- Sound quality processes are in place in the IT String, with improvements in various aspects.
- Effective collaboration and support from the HL-LHC quality office to deal with quality subjects.
- Intervening teams are committed to quality, and they count with experience in quality assurance/control methods.
- WP16 discovered non-conformities up to now are not critical and corrective measurement have been successfully implemented.
- A meeting dedicated to quality is launched to review, among others, equipment non-conformities potentially affecting the IT String.
- Lessons learned from the IT String experience have been gathered and communicated.





Thank you for your attention

Special thanks to all the collaborators for their efforts