

SNO+ Tellurium Purification for $0\nu\beta\beta$



Szymon Manecki, August 8th, 2024



Double Beta Decay

- Are neutrinos their own anti-particles?
- $2\nu\beta\beta$ (Dirac)
 $(A, Z) \rightarrow (A, Z + 2) + 2e^- + 2\nu_e$
 $\sim 10^{18}-10^{21}$ years
- $0\nu\beta\beta$ (Majorana)
 $(A, Z) \rightarrow (A, Z + 2) + 2e^-$
 $> 10^{25}$ years
- We measure:

$$\frac{1}{T_{1/2}} = G g_A^4 \mathcal{M}^2 \left(\frac{m_{\beta\beta}}{m_e} \right)^2$$

↓
↓

Phase space factor Nuclear matrix element





Double Beta Decay


- Are neutrinos their own anti-particles?
- $2\nu\beta\beta$ (Dirac)
 $(A, Z) \rightarrow (A, Z + 2) + 2e^- + 2\nu_e$
~ 10^{18} - 10^{21} years
- $0\nu\beta\beta$ (Majorana)
 $(A, Z) \rightarrow (A, Z + 2) + 2e^-$
> 10^{25} years
- We measure:

$$\frac{1}{T_{1/2}} = G g_A^4 \mathcal{M}^2 \left(\frac{m_{\beta\beta}}{m_e}\right)^2$$

↓ Phase space factor
 ↓ Nuclear matrix element



Neutrinoless Double Beta Decay



Neutrinoless Double Beta Decay

- LEGEND-200

- 200 kg of ^{76}Ge HPGe TPC's

- $T_{1/2}^{0\nu}$ lower limits (90% frequentist C.L.)

Observed	Sensitivity
$> 1.9 \cdot 10^{26}$ yr	$2.8 \cdot 10^{26}$ yr

- CUORE




- 750 kg TeO_2 cryogenic calorimeters

Half-life limit: $T_{1/2}^{0\nu} > 3.8 \times 10^{25}$ yr (90% C.I.)

- KamLAND-Zen

- 800 kg ^{136}Xe scintillator based detector

Combined $T_{1/2}^{0\nu} > 3.8 \times 10^{26}$ yr






Milan '24 $0\nu\beta\beta$:


<https://agenda.infn.it/event/37867/sessions/29923/#20240618>

SNO+ Tellurium-Diol Synthesis

- LAB-soluble TeDiol complexes are formed in condensation and further oligomerization reactions of Telluric Acid with 1,2-Butanediol




- Telluric Acid purification (test batch product)
- 1,2-Butanediol *distillation*
- DDA *distillation*




SNO+ Tellurium Systems

TeA



TeDiol




AV



DDA Distillation



DDA & BD UG Transfer




TeA Purification

- The purification technique relies on solubility of TeA in water based on pH
 - $$\underset{\text{in-soluble}}{\text{Te(OH)}_6} \rightleftharpoons \underset{\text{soluble}}{\text{Te(OH)}_5\text{O}^-} + \text{H}^+$$
- Insoluble contamination
 - Dissolve in water, and filter
- Soluble contamination
 - Force TeA to recrystallize by adding Nitric Acid, let it precipitate out, and drain the “dirty” liquid

Nucl. Inst. Meth. A. 795:132-139 (2015)


Cosmogenic isotope	Counts in Year 1 (no purification)
²² Na	7.04×10^3
²⁶ Al	9.67×10^{-2}
⁴² K	6.55×10^2
⁴⁴ Sc	8.41×10^1
⁴⁶ Sc	5.21×10^{-2}
⁵⁶ Co	1.02×10^{-3}
⁵⁸ Co	2.50×10^{-3}
⁶⁰ Co	6.62×10^3
⁶⁸ Ga	6.20×10^2
⁸² Rb	5.15×10^{-16}
⁸⁴ Rb	8.88×10^{-12}
⁸⁸ Y	2.23×10^1
⁹⁰ Y	5.05×10^2
¹⁰² Rh	1.33×10^3
^{102m} Rh	9.54×10^4
¹⁰⁶ Rh	8.59×10^1
^{110m} Ag	7.96×10^2
¹¹⁰ Ag	1.07×10^1
¹²⁴ Sb	1.77×10^{-2}
^{126m} Sb	3.06
¹²⁶ Sb	2.92×10^{-35}

Free purification factor due to underground cooldown




10kg pilot-scale

Flow Diagram For TeA Plant



Flow Diagram For TeA Plant



TeA Purification



TeA Test Batch

- **Safety** (Process Checklist and Monitoring)
 - Transport and handling of nitric acid and telluric acid
 - Sampling
- **Process** (Plant and Performance QA)
 - Mechanical, Hydraulic, Electrical, Instrumentation, DeltaV
 - Yields and efficiencies
- **Physics** (Process Purification QA)
 - Purifications factor and ICP-MS analysis

TeA Test Batch

- **Safety** (Process Checklist and Monitoring) ✓
 - Transport and handling of nitric acid and telluric acid
 - Sampling
- **Process** (Plant and Performance QA) ✓
 - Mechanical, Hydraulic, Electrical, Instrumentation, DeltaV
 - Yields and efficiencies
- **Physics** (Process Purification QA) ✓
 - Purifications factor and ICP-MS analysis


Safe Reagent Handling Underground

- Nitric acid shipping and logistics
- TeA loading into the plant
- Nitric and telluric acid sampling
- Process systems




Safe Reagent Handling Underground

- Nitric acid shipping and logistics
- TeA loading into the plant
- Nitric and telluric acid sampling
- Process systems





Safe Reagent Handling Underground

- Nitric acid shipping and logistics
- TeA loading into the plant
- Nitric and telluric acid sampling
- Process systems



Safe Reagent Handling Underground

- Nitric acid shipping and logistics
- TeA loading into the plant
- Nitric and telluric acid sampling
- Process systems




TeA Purification

- Redissolved TeA sample after first stages of nitric acid recrystallization will be analyzed with ICP-MS soon
- We've determined that our TeA is much cleaner than what we've been assuming so far (U and Th at the level of a few ppt from two different batches/drums)
- Alternative nitric acid supply also demonstrated to be better than expected: $\sim 5 \times 10^{-15}$ gU/g and $\sim 6 \times 10^{-16}$ gTh/g
- Ultimately the purification factor is determined by the amount of residual nitric acid in the TeA crystal - which we just demonstrated to be satisfactory



TeDiol Plant Flow Diagram



TeDiol Test Batch

- 8g synthesis R&D
- 160g synthesis system
- Pilot Plant (1.5 kg batch size)
- Full Scale plant (~250kg/batch)



TeDiol Test Batch

- **Full Scale** plant (~250kg/batch)
 - Already demonstrated water removal
 - Final commissioning tasks TBC
 - Distilled Butanediol needed




Surface Distillation

- DDA Installation
 - Completed as of last week (piping, mechanical and electrical)
 - Minor adjustments remaining (labelling, etc.)
- DDA Still commissioning
 - Planned shortly
 - Further 'full commissioning' will be done this Fall including distillation runs of LAB, BD and DDA



Surface Distillation

- DDA Installation
 - Completed as of last week (piping, mechanical and electrical)
 - Minor adjustments remaining (labelling, etc.)
- DDA Still commissioning
 - Planned shortly
 - Further 'full commissioning' will be done this Fall including distillation runs of LAB, BD and DDA



Summary

- TeA Test Batch was a success
- TeDiol Synthesis test run is the next major milestone
- In parallel we are building reagent transfer stations and commissioning the surface distillation plant



Backup