

STATUS OF BERLINPRO

The European Laboratory Directors Group Meeting and
Accelerator R&D Workshop

06/07/24,


Brookhaven National Laboratory

A. Neumann for the bERLinPro team @SEALAB



Evolution of bERLinPro

From 4th generation light source prototype (2011), via generic high intensity ERL prototype (2012-2020) towards *application driven* facility (today)



Single turn high intensity ERL
 5 MW beam power
 650 kW injector beam power

test and diagnostic line

beam dump
 6.5 MeV, 100 mA
 = 650 kW

linac module
 3 x 7 cell SRF cavities
 44 MeV


merger dogleg

modified Cornell booster
 3 x 2 cell SRF cavities

srf-gun
 1.4 cell SRF cavities
 1.5-2.3 MeV, single SC solenoid,

- Important aspects:
- Injector beam quality at high current/bunch charge
 - Beam loss control and monitoring → Radiation protection
 - Beam break-up in main Linac
 - Longitudinal control of beams for recovery process (low power margin)

Parameter	bERLinPro
Beam energy recirculator (MeV)	50
Beam current ERL mode (mA)	100
Frequency RF and Laser (GHz)	1.3
Normalized emittance (mm mrad)	1 (< 0.6 in simulations)
Bunch length (ps)	< 2 (ERL mode), 100 fs @ 10 mA
Beam losses	<< 10 ⁻⁵ @ 100 mA


Presently installed facility

- Installed: 10-mA SRF gun + merger + recirculation + dump
 - Installed: Proof-of-principle UED experiment
 - Funded: Booster module. Produced but assembly required
 - Not funded: LINAC module
 - Not funded: 100-mA class photoinjector
- } CW photoinjector studies < 10 mA
 } Long-pulse injector studies < 100 mA
 — High-power beam studies (“long pulse”)
 } High-power energy recovery
 } Energy-efficient RF operation

Stages at bERLinPro

Presently installed facility

Applications



Make use of injector's flexibility for beam parameter range
 → Cover in parallel ERL relevant beam studies

- **Installed:** 10-mA SRF gun + merger + recirculation + dump
 - **Installed:** Proof-of-principle UED experiment
 - **Planned:** Waste water treatment demonstrator
 - **Funded:** Booster module. Produced but assembly required
 - **Not funded:** LINAC module
 - **Not funded:** 100-mA class photoinjector
- } CW photoinjector studies < 10 mA
 Long-pulse injector studies < 100 mA


— High-power beam studies (“long pulse”)

} High-power energy recovery
 Energy-efficient RF operation

Stages at bERLinPro

Presently funded facility

Applications



- **Installed:** 10-mA SRF gun + merger + recirculation + dump
- **Installed:** Proof-of-principle UED experiment
- **Planned:** Waster water treatment demonstrator
- **Funded:** Booster module. Produced but assembly required
- **Not funded:** LINAC module
- **Not funded:** 100-mA class photoinjector

}
—

CW photoinjector studies < 10 mA
 Long-pulse injector studies < 100 mA
 High-power beam studies (“long pulse”)


}
}

High-power energy recovery
 Energy-efficient RF operation

Stages at bERLinPro

Full program (partially funded)

Applications



- **Installed:** 10-mA SRF gun + merger + recirculation + dump
- **Installed:** Proof-of-principle UED experiment
- **Planned:** Waste water treatment demonstrator
- **Funded:** Booster module. Produced but assembly required
- **Not funded:** LINAC module
- **Not funded:** 100-mA class photoinjector

]



—

]

CW photoinjector studies < 10 mA
 Long-pulse injector studies < 100 mA
 High-power beam studies (“long pulse”)
 High-power energy recovery
 Energy-efficient RF operation

Status of bERLinPro@SEALAB

Injector installation at present





Six+ month delay due to severe HZB cyber attack

- SRF photo-injector and diagnostics ready for commissioning
- Final preparation of cathode-laser beam transport
- 1.3 GHz laser demonstrated 23 W CW → sufficient for 100 mA @ 2.5% QE
- **1st Cool-down in Jan. 2024** → prerequisite for rad. permit application for RF operation
- **RF test of photoinjector Q2 2024** → prerequisite for rad. permit application for beam operation
- Cathode-transfer unit ready for installation following RF test
- **Beam operating permit expected Q3 2024** → First beam from SRF Gun around 10-11/2024
- Start of Booster assembly H1/2024 (all parts in house)

Status of bERLinPro@SEALAB

Injector installation at present





Six+ month delay due to severe HZB cyber attack

- SRF photo-injector and diagnostics ready for commissioning
- Final preparation of cathode-laser beam transport
- 1.3 GHz laser demonstrated 23 W CW → sufficient for 100 mA @ 2.5% QE
- **Cool-down in Jan. 2023** → prerequisite for rad. permit application for RF operation
- **RF test of photoinjector Q2 2024** → prerequisite for rad. permit application for beam operation
- Cathode-transfer unit ready for installation following RF test
- **Beam operating permit expected Q3 2024 → First beam from SRF Gun around 10-11/2024**
- Start of Booster assembly H1/2024 (all parts in house)

Status of bERLinPro@SEALAB


Injector installation at present




Six+ month delay due to severe HZB cyber attack

- SRF photo-injector and diagnostics ready for commissioning
- Final preparation of cathode-laser beam transport
- 1.3 GHz laser demonstrated 23 W CW → sufficient for 100 mA @ 2.5% QE
- **Cool-down in Jan. 2024** → prerequisite for rad. permit application for RF operation
- **RF test of photoinjector Q2 2024** → prerequisite for rad. permit application for beam operation
- Cathode-transfer unit ready for installation following RF test
- **Beam operating permit expected Q3 2024 → First beam from SRF Gun around 10-11/2024**
- Start of Booster assembly H1/2024 (all parts in house)

Current activities



- Successful RF test, beam energies up to 2.1 MeV
→ there is room for progress
- Laser system, diagnostics, beam transport optics, beam loss monitoring (several systems) installed and ready
- Cathode transfer system ready



bERLinPro@SEALAB injector studies

Parameter	Injector / UED	ERL
Beam energy (MeV)	6.5 – 10 / 2	50
Max. average current (mA)	10 / 0.0025	100
Bunch charge (pC)	0.05 – 400	77
RF Frequency (MHz)	1300	1300
Norm. Emittance (mm mrad)	0.6 / 0.03	1 (0.6)
RMS bunch length (ps)	0.02 – 2	2 (0.1)

Funded: SRF gun/booster ops & UED mode

Not funded: 100-mA CW gun cavity + couplers
+ LINAC module (existing design)

Medium-power gun (20kW) / booster program

- Explore full parameter space of SRF injector @ $I_b < 10$ mA
- 100 mA can be potentially studied in long-pulse* regime
- Bunch charge up to 0.5 nC with a high QE cathode
- Proof of cathode exchange concept, test of more robust cathode materials: Replace Cs by Na
- Studies of beam loss scenarios by dark current or beam halo formation by bunch tails
- Propagation of beam and unwanted beam from injector to dump
- Beam loss monitoring and machine protection concepts
- High dynamic range diagnostic concepts for low-current start-up to high-power operation ($< \mu\text{A} \rightarrow \text{mA} \rightarrow 100 \text{ mA}^*$)
- Beam arrival time and jitter studies
- Digital twins, ML+AI assisted control methods

bERLinPro@SEALAB injector studies

Parameter	Injector / UED	ERL
Beam energy (MeV)	6.5 – 10 / 2	50
Max. average current (mA)	10 / 0.0025	100
Bunch charge (pC)	0.05 – 400	77
RF Frequency (MHz)	1300	1300
Norm. Emittance (mm mrad)	0.6 / 0.03	1 (0.6)
RMS bunch length (ps)	0.02 – 2	2 (0.1)

Funded: SRF gun/booster ops & UED mode

Not funded: 100-mA CW gun cavity + couplers
+ LINAC module (existing design)

Medium-power gun (20kW) / booster program

- Explore full parameter space of SRF injector @ $I_b < 10$ mA
- 100 mA can be potentially studied in long-pulse* regime
- Bunch charge up to 0.5 nC with a high QE cathode
- Proof of cathode exchange concept, test of more robust cathode materials: Replace Cs by Na
- Studies of beam loss scenarios by dark current or beam halo formation by bunch tails
- Propagation of beam and unwanted beam from injector to dump
- Beam loss monitoring and machine protection concepts
- High dynamic range diagnostic concepts for low-current start-up to high-power operation ($< \mu\text{A} \rightarrow \text{mA} \rightarrow 100 \text{ mA}^*$)
- Beam arrival time and jitter studies
- Digital twins, ML+AI assisted control methods

bERLinPro@SEALAB injector studies

Parameter	Injector / UED	ERL
Beam energy (MeV)	6.5 – 10 / 2	50
Max. average current (mA)	10 / 0.0025	100
Bunch charge (pC)	0.05 – 400	77
RF Frequency (MHz)	1300	1300
Norm. Emittance (mm mrad)	0.6 / 0.03	1 (0.6)
RMS bunch length (ps)	0.02 – 2	2 (0.1)

Funded: SRF gun/booster ops & UED mode

Not funded: 100-mA CW gun cavity + couplers
+ LINAC module (existing design)

Medium-power gun (20kW) / booster program

- Explore full parameter space of SRF injector @ $I_b < 10$ mA
- 100 mA can be potentially studied in long-pulse* regime
- Bunch charge up to 0.5 nC with a high QE cathode
- Proof of cathode exchange concept, test of more robust cathode materials: Replace Cs by Na
- Studies of beam loss scenarios by dark current or beam halo formation by bunch tails
- Propagation of beam and unwanted beam from injector to dump
- Beam loss monitoring and machine protection concepts
- High dynamic range diagnostic concepts for low-current start-up to high-power operation ($< \mu\text{A} \rightarrow \text{mA} \rightarrow 100 \text{ mA}^*$)
- Beam arrival time and jitter studies
- Digital twins, ML+AI assisted control methods

Improve efficiency of ERLs


iSAS


Funded: Demonstrate efficiency gains with cavity in HoBiCaT test cryomodule

Funded: Integrate into bERLinPro LINAC module design

Funded: LLRF (AI/ML) tests at bERLinPro injector

Not funded: Demonstrate operation in bERLinPro




From A. Neumann et al.,
[Phys. Rev. ST Accel. Beams 13, 082001 \(2010\)](#)


Compensation of disturbances in the acoustic frequency regime

Integrated iSAS approach to save grid power for RF

- Digital AI/ML-assisted field and detuning control
- Reduced detuning by piezo and new FE-FRT tuners
- Smart amplifier control



Required power for 25 MV/m of a CW driven XFEL cavity



Improve efficiency of ERLs


iSAS


Funded: Demonstrate efficiency gains with cavity in HoBiCaT test cryomodule

Funded: Integrate into bERLinPro LINAC module design


Funded: LLRF (AI/ML) tests at bERLinPro injector

Not funded: Demonstrate operation in bERLinPro




From A. Neumann et al.,
[Phys. Rev. ST Accel. Beams 13, 082001 \(2010\)](#)

Compensation of disturbances in the acoustic frequency regime



A rough 2024 schedule




- Setup Laser
- Setup transfer system
- Check for beam condition: FOMS, magnets,...

- LLRF ready ✓
- High power RF ready ✓
- Cryo ready ✓
- Module diagnostics ✓
- PSI operational ✓
- Tcav ready ✓

- Readiness cathode transfer system, cathode laser
- Beamline magnets, steerer magnets
- Diagnostics: FOMS, Faraday Cups
- Camera tools, beam loss monitoring
- Control system fully implemented for needed devices, MPS functional

Ongoing



- Commissioning program beam ready, first measurement applications

Thank you!

If there is time left, questions are welcome or contact me at

Axel.Neumann at helmholtz-berlin.de

Thanks and acknowledgements to all partners, who contributed to this project



MAX-BORN-
INSTITUT



JOHANNES GUTENBERG
UNIVERSITÄT MAINZ



The Andrzej Sołtan Institute for Nuclear Studies
PL-05400 Otwock-Świerk
Poland



Funding: Bundesministerium für Bildung & Forschung
Bundesland Berlin, Helmholtz Gemeinschaft 