

EP-DT Group Meeting

DT Contributions to ATLAS ITk Pixel Outer Barrel

26th June 2024

Ricardo Tavares Rego; Abhishek Sharma

On behalf of the DT group ITk OB contributors




EP-DT Detector Technologies




Introduction

- EP-DT Leading role in ATLAS ITk Pixel Outer Barrel Mechanics & Modules
 - Module construction, Local Supports, on-detector cooling and global support structures
 - Detector assembly and integration \rightarrow DT commitments extend up to the end of LS3
 - Close collaboration with EP-ADE, Université de Genève, Bonn, CPPM and EN-MME






Outer Barrel: Local Supports



R.T.Rego

Outer Barrel: Global Support Structures & Services




OB Pixel Module Production

- CERN is one of the production sites for quad modules for the ITk Outer Barrel (up to 1200 modules) – close collaboration between EP-DT and EP-ADE.
- Assembly production line established in DSF cleanroom including test setups, inspection systems and assembly tooling.




Assembly area in DSF cleanroom



Pre-production has now started with 30+ modules assembled:

• Strong contributions towards hybridisation vendor qualifications, module QC and flex pre-production

• Including community common items: OB WBMP canopy validations, silicon tile orders, FE chip debugging





Module Production Assembly Tooling

X-ray scan ITkPixV1.1 module (top right chip)

26/06/2024



Flex PCB

Sensor

4xFEs

EP-DT Group Meeting R.T.Rego


ITk Pixel Sensor & FE Chip Production


Sensors:


- All now in production: >2500 thick quad sensors, 394 thin quad sensors and 600 3D sensors delivered.
- Excessive bow in some 3D sensors is responding well to a new industrial passivation process.

Front-end chips:

- ITkPixV2 wafer probing for 1st Batch of 100 wafers finished
- 700 more production wafers will be probed from late June on









Bare Local Supports (BLS)

- Manufacturing and QC of BLS DT in collaboration with UNIGE, BONN and CPPM
- In production first sub-system to pass the PRR (link)
- Final raw material and commercial components procured
- Good progress in the manufacturing of components and subassemblies (e.g. CFRP parts, inserts, sleeves)
- Assembly of first Functional Longeron units recently completed




Loaded Local Supports

- CERN (DT + ADE) is a Cell Loading and Cell Integration site
- Currently in pre-production FDR passed in March 2023 (link)
- Tool commissioning and site qualification underway (including QC infrastructure)

R.T.Rego

- Deployment & commissioning of DT-developed QC setup at all OB Cell Loading sites
- First pre-production LLS end of Q3; PRR expected early 2025




Global Mechanics – Half Layer Shells (HLS)

- DT plays leading role in design of OB Global Supports and on-detector cooling circuit
- Responsibility for design, validation and production of main structures, i.e. HLS and SSS (FDR passed on May 2024 (<u>link</u>))
- Important step forward in 2023/24 \rightarrow Full-size prototypes of L3-HLS using in-house mould
- Currently finalising design of shells, moulds and gluing tools for inserts to launch production (PRR October 2024)










Global Mechanics – Service Support Shells & Pipe Extensions


- DT plays leading role in design of OB Global Supports and on-detector cooling circuit
- Service Support Shells (SSS) •
 - Optimised design based on new service management approach with clips
 - Documentation in preparation for tender process (SSS will be outsourced)
 - Cooling Pipe Extensions
- Produced in collaboration with EN-MME \rightarrow Joint effort to develop Ti-Ti EB-Brazing
- Ongoing studies to re-size capillaries to adapt to new PP1 routing
- New setup to assess 3D thermo-elastic deformation in pipes using laser scanner






Global Mechanics – CAD Global Model & Service Mock-up

- DT responsible for develop and maintain detailed OB Global CAD Model
- In charge for assembly representative Slice Service Mock-up for design validation
- In 2023, extensive studies to define service routing in OB detector volume
 - Drive design of power & data cable bundles to allow for robust connections to PP0s
 - Assess compatibility with available space/allocated envelopes in different regions
 - Develop appropriate solutions for the service management








Outer Barrel Integration Tooling

- Design and procurement of OB/OS integration tooling (e.g. IU handling frame, reference table, longeron, installation tool, SSS handling frames, service trolleys)
- Finalising design of Rotation Frame and Static Cradle
 - Detailed CAD studies to include interfaces with other tooling items
 - FE analysis for different load cases, including lifting into ITk
 - Expected to launch price enquire in October 2024



Schedule

- CERN EP-DT commitments for construction of ATLAS ITk Pixel extend to end of LS3
- DT activities (modules, bare local supports & loading, global mechanics & integration) run in parallel & require substantial resources until 2028
- Project schedule remains very challenging, with very limited contingency

		2024	2	025	2026		2027		2028		
		May Jun Jul Aug Sep Oct Nov	Jan Feb Mar Apr May	Jun Jul Sep Oct Nov	Jan Feb Mar	Apr May Jun Jul	Aug Sep Nov Dec	Jan Feb Mar Apr	Jun Jul Aug Sep Oct Nov	Jan Feb Mar Apr May	Jun Jul Aug Sep
Module Assembly	Pre-Production										
& Testing	Production										
Bare Local Supports Production											
Loaded Local Supports (Cell Loading & Cell Integration)	Pre-Production										
	Production										
Production Global Mechanics Items			16%	33%	50%	66% 83%	100%				
Outer Barrel Integration											
Outer System (OB+ECs) Integration											
Outer System Insertion into ITk											
Inner System Insertion into ITk											
ITk Ready for Installation											

- Feedback from latest P2UG review in May indicates that current ITk schedule will not be met
 - ATLAS & CMS in discussions with machine and CERN management
 - Joint ATLAS & CMS proposal to extend Run-3 to ~June2026
 - LS3 would finish in ~March providing additional contingency for ITk



Questions?



ITk Integration has begun...

- Outer Cylinder housing ITk
 - Manufactured in US and shipped from Berkley
 - Moved to SR1 clean room last week
 - Installation of L2 and L3 strip barrel cylinders planned for July







LS3 Schedule

