



Science and  
Technology  
Facilities Council

# I.FAST Period 2 Review – Task 11.3

## Permanent Magnet Quadrupoles & Combined Function Magnets for Ultra Low-Emittance Rings

**Ben Shepherd**, Alex Hinton *ASTeC, STFC Daresbury Laboratory*

Dušan Topalović, Jure Počkar, Tadej Milharcic and Mirko Kokole *Kyma*

Alfie Shahveh *Diamond Light Source*

**I.FAST Period 2 Review**

**15 July 2024**

# WP11.3:

## Permanent Magnet Quadrupoles & Combined Function Magnets for Ultra Low-Emittance Rings

### Deliverables


- **D11.3** Prototype adjustable PM quadrupole and combined function magnets: *due ~~M28~~ M44 (Nov 2024)*

### Milestones

- **MS31** Magnets constructed and tested: *due ~~M25~~ M44 (Nov 2024)*
- Late delivery owing to
  - increased cost of blocks → redesign of magnet
  - lack of available resources at Kyma for mechanical design


# Introduction

- Fourth generation synchrotron light sources make use of multi-bend achromat lattices to reduce beam emittance and increase radiation brightness
- Lattices require combined function dipole-quadrupole (DQ) magnets
- Diamond-II upgrade will require 48 DQ magnets drawing 2.3 kW each
- Goal of WP11.3 – test if equivalent field requirements can be met by a permanent magnet based solution





# HEPTO Magnet Prototype

- Hybrid Electromagnet-Permanent Magnet Tuneable Optics (**HEPTO**) to meet same field requirements as DQ electromagnets for Diamond-II.
- Dipole **0.7 T**, Gradient **33 T/m**.
- Effective length **0.870 m**.
- Main source of field: **NdFeB** permanent magnet blocks (originally purchased for an undulator).
- Dipole and gradient fields require independent tuning of **±2.5%** for commissioning purposes.
- Field tuning achieved by **air-cooled trim coils**.
- Yoke and poles made from **XC06 low-carbon steel**.







# Thermal Shunts

- Thermal shunt material can only be purchased from suppliers in large batches.
- Spare **FeNi** thermal shunt material purchased from Soleil (42 sheets for €1600).
- Material cut and glued to type A and F magnet blocks.
- Enough material to produce 26 layers of 0.5 mm thick sheets.
- Predicted thermal stability  $-0.05\%/^{\circ}\text{C}$ .  
0.01% variation typical due to power supply fluctuation in electromagnets.



# Field Tuning




| Change in $\int b_1.ds / \%$ | Change in $\int b_2.ds / \%$ | Main coil current / A | Auxiliary coil current / A |
|------------------------------|------------------------------|-----------------------|----------------------------|
| 0                            | 0                            | -0.05                 | -0.01                      |
| -2.5                         | 0                            | -4.93                 | -1.32                      |
| +2.5                         | 0                            | 4.82                  | 1.32                       |
| 0                            | -2.5                         | -1.65                 | -0.42                      |
| 0                            | +2.5                         | 1.54                  | -0.42                      |

|  |      |
|--|------|
| Main coil turns                        | 64   |
| Main coil pair maximum power / W       | 30.6 |
| Auxiliary coil turns                   | 36   |
| Auxiliary coil pair maximum power / W  | 16.4 |
| Electromagnet DQ power dissipation / W | 2300 |



# Full Mechanical Design

- Mechanical design of the prototype magnet has been completed.
- Design allows mechanical shimming of built prototype to shim field strength and quality.
- Engineering drawings have been completed.
- Procurement of mechanical components is ongoing.



# Conclusions and Future Planning

- Magnetic design of HEPTO prototype magnet using spare undulator magnet blocks is complete.
- Maximum power requirement per magnet (5 A per coil) = 50 W.
- Equivalent electromagnet requires 2.3 kW + water cooling.
- Mechanical design and drawings are complete.
- Procurement of prototype components is ongoing.
- On track to construct the prototype at Kyma by end of October 2024.
- Afterwards, magnetic measurements will be used to verify the performance of the prototype with respect to magnetic modelling at Daresbury Laboratory.





Science and  
Technology  
Facilities Council

# Thank you

Acknowledgements:

- Dušan Topalović, Jure Počkar, Tadej Milharcic and Mirko Kokole (Kyma)
- Alfie Shahveh (Diamond Light Source)



**Facebook:** Science and  
Technology Facilities Council

**Twitter:** @STFC\_matters

**YouTube:** Science and  
Technology Facilities Council