



# MCBXF magnet assembly and powering tests results at CERN

J. C. Pérez

CERN TE-MS-C-SMT

On behalf of MCBXF team.

Acknowledgments to people who contributed to this presentation.

14<sup>th</sup> HL-LHC Collaboration Meeting - Genoa  
7-10 October 2024



<https://indico.cern.ch/event/1421594/overview>

# Outline


- MCBXF: Spanish in-kind contribution for HL-LHC
- Series magnet production status in October 2023
- Remaining magnets production at CERN
- Summary

# Spanish in-kind contribution for HL-LHC

CIEMAT and CDTI signed a contract in March 2021 with ELYTT Energy (Spain) to produce the series magnets:


- 6 MCBXFA
- 11 MCBXFB

During the prototyping phase, 2 MCBXFB and 1 MCBXFA prototypes, as well as the first MCBXFB for the series, were built within a collaboration between CIEMAT and CERN.



# MCBXF combined dipole orbit correctors for HL-LHC


## Insertion Region Layout



Magnification of the area around correctors:



First CP cold mass waiting in SMS18 for cold powering tests



First Q2a cold mass installed in the IT-String



# MCBXF series magnet production

- From March 2021 until **September 2023** ELYTT Energy delivered to CERN **3 MCBXFB** magnets
- The series production contract was stopped in September 2023 by mutual agreement between CIEMAT, CDTI and ELYTT.

The situation was:


- 4 MCBXFB (1 made by CIEMAT & CERN) magnets over the 18 foreseen to be built by ELYTT were delivered
- 33 Coils still to be produced:
  - 16 MCBXFB
  - 17 MCBXFA
- No MCBXFA assembled at ELYTT
- **14 Magnets still** to be assembled at CERN:
  - 8 MCBXFB
  - 6 MCBXFA

A strategy to complete the remaining magnet production, on schedule, was presented in October 2023.

The idea was to split the manufacturing into two separate sites:

- **CIEMAT** to produce the missing **coils** in its new laboratory **in Madrid** and will oversee the production of the remaining components
- **CERN** to be responsible for **assembling the magnets** in its facilities in **Geneva**

# Magnet production planning presented in January 2024



The initial planning accounts for a delivery rate of 1 magnet every 2.5 months, exception for the first magnet (B05), with an assembly time of 3 months (used for knowledge transfer and production line set-up) to cope with WP3 master plan.




# The team

All prototypes were developed and assembled at CERN in close collaboration with CIEMAT until fall 2021.

CERN's team has the required know-how to perform this task, but a series production approach was required.

A small, fully dedicated **core team to MCBXF** assembly activities has been formed.

- WP3 Project engineer
- 1 engineer for production follow-up
- Magnet assembly activities:
  - 1 trained engineer for assembly
  - 1 CERN trained technician to teach the newcomers (during first assembly)
  - 3 technicians for assembly
- 1 technician part time for electrical measurements
- Punctual support from MSC-LMF, MSC- SMT , EN-MME and ATS-DO is provided




# Magnet assembly life cycle

927 Laboratory




Large Magnet Facility





# Set up of the assembly line at CERN: Building 180

- All assembly operations but the Collaring are performed in building 180: 3 zones for MCBXF






# Set up of the assembly line at CERN: Building 927






# MCBXF Cold Powering


- Each dipole is tested in standalone mode up to its ultimate current
- Then the magnet is trained in combined powering up to its ultimate field



- Then the magnet is powered around its nominal perimeter by performing two rectangular powering cycles




Nominal torque per unit length at straight section is very high: **147 kNm/m**, about **84 MPa** at the inner dipole coil.





# MCBXFB05 powering test results

- Cold test (1<sup>st</sup> thermal cycle)
  - Single powering:
    - 1 quench while powering the inner dipole on standalone configuration
    - No quench for the outer dipole
  - Combined powering:
    - No quenches in the first quadrant, but 5 quenches in the second quadrant to reach ultimate.
    - We then went through all quadrants without further quenches (see the five markings in the current vs time plot).
- Cold test (2<sup>nd</sup> thermal cycle)
  - Single powering:
    - No quench
  - Combined powering:
    - No quench
- Documentation and EDMS status:
  - Documentation is up to date. NCRs are closed




MCBXFB05 is the first magnet tested after the restart of assembly activities by CERN at CERN.

Courtesy of G. Willering

JC. Perez – 7th October 2024

# MCBXFA1 powering test results

- Cold test (1<sup>st</sup> thermal cycle)
  - Single powering:
    - No quench for the inner dipole
    - No quench for the outer dipole
  - Combined powering:
    - 1 quench in the first quadrant at almost ultimate current.
    - We then went through all quadrants without further quenches.
- Cold test (2<sup>nd</sup> thermal cycle)
  - Single powering:
    - No quench
  - Combined powering:
    - No quench
- Documentation and EDMS status:
  - Documentation is up to date. NCRs are closed



# Documentation status

- MTF Assets (Coils/Magnets) modified to represent the new production scheme
- Results from the incoming inspections on the materials used from previous production are available
- NCRs from previous production are being closed
- Manufacturing and assembly procedures issued
- All updated drawings uploaded to PLM
- Documentation systematically upload by both teams to MTF
- NCRs from assembly at CERN well documented (root cause identification, corrective and preventive actions)

**Equipment Identifier:** HCMCBXF012-E9000001  
**Other Identifier:** MCBXF02  
**Description:** Dipole Orbit Corrector Q2 SERIES

**Equipment Identifier:** HCMCBXF012-E9000006  
**Other Identifier:** MCBXF06  
**Description:** Dipole Orbit Corrector Q2 SERIES

**Equipment Identifier:** HCMCBXF012-E9000001  
**Other Identifier:** MCBXF01  
**Description:** Dipole Orbit Corrector CP SERIES

Item in ABS	Created on	Last modified on	Responsible
Single Aperture (150mm) Orbit Cor	2024-07-01	2024-07-02	
	2022-05-30	2024-09-26	VIGUILLE HOUSIAUX

Kref [mm]	020	030	050	070	090	090	090
x [mm]	-0.0766	0.44007	-0.0403	-0.2341	-0.2798	-0.0747	1.05504
y [mm]	13.935	-4.2029	0.6882	-0.6841	-0.6999	-0.7532	2.63996
z [mm]	-1438.8	-0.5327	0.4682	0.5143	0.7770	0.5225	-1543.6
Y1	-12.87	0.02024	0.0082	0.0081	0.0081	0.007	9.8629
Y2	99.565	-4.990	-7.876	-0.5451	-3.237	-1.876	109.314
Y3	16.048	18.130	16.030	17.180	11.17	6.374	14.973
Y4	22.1	22.1	22.1	22.1	22.1	22.1	22.1
Y5	1.599	1.624	1.431	1.503	1.493	1.599	1.624
Y6	0.1558	1.469	0.329	1.143	1.216	0.946	0.211
Y7	0.2033	1.143	0.279	0.973	0.916	0.734	0.249
Y8	0.0113	0.183	0.183	0.0124	0.020	0.024	0.018
Y9	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y10	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y11	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y12	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y13	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y14	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y15	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y16	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y17	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y18	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y19	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y20	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y21	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y22	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y23	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y24	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y25	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y26	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y27	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y28	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y29	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y30	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y31	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y32	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y33	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y34	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y35	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y36	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y37	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y38	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y39	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y40	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y41	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y42	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y43	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y44	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y45	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y46	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y47	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y48	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y49	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y50	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y51	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y52	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y53	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y54	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y55	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y56	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y57	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y58	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y59	0.129	0.024	0.024	0.024	0.024	0.024	0.129
Y60	0.129	0.024	0.024	0.024	0.024	0.024	0.129

**PROCEDURE**

**FINAL ASSEMBLY PROCESS FOR MCBXFA SERIES MAGNETS**

**Abstract**

This document details all the processes needed to obtain a final magnet for the MCBXFA series magnets, including an inner collared dipole and an inner collared dipole with a. It covers the preparation of the longitudinal pushers, assembly of the endplates and non-poles; longitudinal press and quality inspection.


**TRACEABILITY**

Prepared by: J.A. Garcia Mateo, D. Duran Date: 2023-06-16  
Verified by: C. Martin Date: 2023-06-16  
Approved by: F. Toral Date: 2023-06-14  
Distribution: WF Members, RD

Rev. No.	Date	Description of Changes (major changes only, minor changes in EDCS)
1.0	2023-06-14	First complete version of the document.



# CERN assembly activities timeline





# Summary

Today we have:

- MCBXFB05 and MCBXFA01 have been assembled and successfully tested
- MCBXFB06 is waiting for cold powering tests
- MCBXFB07 assembly has started
- The provisional schedule presented at the beginning of the year is being perfectly followed and is in line with the requirements of the general WP3 schedule
- Less than a year ago, we were in a crisis situation following the closure of a contract for the manufacturing of the series for the combined orbit corrector magnets
- The necessary infrastructure to cover the assembly activities was set up in record time
- Today, we are in a stable situation with an assembly pace aligned with the forecasts made at the beginning of the year
- We are confident about the continuation of operations thanks to the establishment of a dedicated and stable team
- The results achieved so far, despite the unexpected challenges caused by the decision to close the contract signed with ELYTT, would not have been possible without the support of many individuals who may not always be visible at the forefront
- My sincerest thanks to all of them for their contribution



It is much easier to achieve ambitious goals with a cheerful and motivated team.

**Thank you guys !!!!**





Thank you for your attention



## Acknowledgements to:

Cristóbal Alcázar, Lyudmyla Andriychyk, Manuel Domínguez, Óscar Durán, Javier García, Jesus Angel García Matos, Luis Garcia-Tabarés, Luis González, Pablo Gómez, Jesús Jiménez, Ricardo López, Teresa Martínez, Carla Martins, José Antonio Pardo, José Manuel Pérez, Pablo Sobrino, Fernando Toral, Manuel Verastegui from CIEMAT  
Guillermo Morón and Juan Luis Morato from Arquimea  
Steve Beclé, Nicolas Bourcey, Federico Ben el Caid, Pierre-Antoine Contat, Nicolas Eyraud, José Ferradas, Lucio Fiscarelli, Bertrand Fornes, Hector Garcia, Ludovic Grand-Clement, Victor Guillen, Jean-Luc Guyon, Hector Garcia, Gonzalo Hernando, Olivier Housiaux, Michael Guinchard, Susana Izquierdo, Karim Kallat, Nicholas Lusa, Sebastien Luzieux, Franco Mangiarotti, Gregory Maury, Sabine Menu, Attilio Milanese, Sylvain Mugnier, Nicolas Peray, Francois-Olivier Pincot, Hervé Prin, Pietro Rizzo, Piotr Rogacki, Frederic Rougemeont, Ezio Todesco, Yanick Thuau, Patrick Viret, Gerard Willering from CERN...  
and many others that I certainly forgot to mention.

