



RFD Crab Cavity Contribution from the U.S.

Status, Issues and Delivery Dates

Leonardo Ristori – Fermilab


14th HL-LHC Collaboration Meeting – Genova, 7th October 2024




Outline

- Scope
- One Year in Summary
- Successful Qualification of First Pre-Series
- Bare Cavity Fabrication
- Issues with Processing and Rinsing
- HOM Dampers Fabrication
- Helium Tanks Integration a.k.a. Jacketing
- Plans for Acceptance
- Delivery Dates


Scope and Deliverables



Bare RFD Cavity



Dressed RFD Cavity
(front wall removed to show internal components)



Higher-Order-Mode Dampers (HOMs)


- **Project Scope includes 2 Prototypes + 2 Pre-Series + 10 Series**
- Deliverables: **10 qualified dressed cavities** (mix of pre-series + series)
- Bare Cavities: Fabrication + Processing **in Industry**; Intermediate Qualification **at FNAL** at 2K; re-processing (when necessary) **in Industry**; re-rinsing (when necessary) **at JLAB**
- Jacketing: Magnetic Shields + Helium Tank **in Industry**
- HOMs: H-HOM **by JLAB**; H-HOM FT, V-HOM, Pick-up **by CERN**
- Dressed Cavities: re-rinse + Install HOMs + Final Qualification **at JLAB** at 2K
- Transport to TRIUMF: Confirm performance at 2K, and acceptance by CERN

One Year in Summary

- First prototype helium tank welded successfully at Zanon without surprises.
- A total of 8 cold-tests were performed in the U.S. since October 2023.
- 2 Pre-Series Bare cavities (NRFD01 & NRFD02) were completed and processed at Zanon.
- 2 Series Bare Cavities (NRFD03 & NRFD04) being completed as we speak. Components formed successfully for all series.
- One Pre-Series cavity exceeded acceptance levels at bare stage, validating fabrication and processing at Zanon, and also HPR at JLAB.
- Successful investigations uncovered and solved issues with processing and with HPR at Zanon.

Cold Test Records

Best Result for Each Cavity



Pre-Series #2 (NRFD02) Test Results


- Performed 3 tests in total, always exceeding acceptance requirements, but with radiation onset (indicative of contamination). Onset level continued to improve after successive high-pressure rinses by JLAB.
- Final test shows no radiation up to acceptance level.
- Low field Q_0 is high: Chemistry by Zanon is successful.
- Radiation onset is at high field: HPR and clean assembly by Jlab is successful.



JLAB Cleanroom




8/26/24: FNAL VTS Control Room




Last 2 tests for Pre-Series Bare Cavity #2

BCP Issues at Zanon


- Prototype #1** which exceeded acceptance (although marginally) was selected to validate chemistry at Zanon and subjected to a total of 3 bulk chemistries. Full consumption of Niobium material was observed in 2 locations. It is not useable in its current status.
- The outcome of a detailed investigation was that although the removal in most cavity surfaces is very well controlled, the setup at Zanon did not have sufficient water cooling on the outside of cavity and the acid near the cavity flanges was reaching higher than optimal temperatures, causing excessive removal.
- Tests were performed with the improved cooling and yielded positive results with variation of removal near flanges reduced by ~50%.



Prototype #1 after 3+ BCP cycles




BCP Setup at ANL



BCP Setup at Zanon

HPR Issues at Zanon

- Both pre-series cavities processed and rinsed at Zanon are showing **localized discoloration** (see pictures). Suspecting excessive and localized HPR pressure.
- Thanks to recent validation at JLAB, we facilitated knowledge transfer to Zanon and modified the process to align as much as possible with JLAB.
- **Zanon introduced manual HPR** of ports followed by the automatic process. Also parameters were modified to produce a **faster feed speed and increased total rinse time**.
- Particle counts in cleanroom dropped by more than a factor of 10 and no discoloration is visible now.



Pre-Series #1 with internal discoloration




Manual HPR introduced at Zanon

No discoloration visible now


Cavity Fabrication Status at Zanon

- First two series NRFD03 & NRFD04 are undergoing trim-tune operations (see plot and pictures). Cavity length, cavity geometry, and frequency all need to be achieved at the end.
- NRFD04 was presenting non-standard behavior after the first cut (frequency reduction after cut versus expected frequency increase). After reshaping, the following cut was as expected.
- Final welds will be completed later this month.
- All components for series cavities were produced in parallel. Deliveries are expected to ramp up dramatically in the next 6 months.




Some Components of Series #3 and #4 ready for trim-tuning

It Was a Year of Visual Inspections...





Fabrication Challenges at Zanon


- Arguably this SRF cavity is one of the most complex to build and has some of the tightest tolerances compared to others.
- Rework activities are often necessary to achieve requirements.
 - Geometrical tolerances on stamped/coined subcomponents (pole & waveguides in particular)
 - Complex EBW between Half Main Body sub-components and Waveguides Boxes-End Caps
 - Alignment between End Groups-Main Body during final EBW
 - Non straightforward behavior of cavity, and components during reshaping.



HOMs Fabrication at JLab



- PRR held in May 2022
- Prototype: 3 sets (FY21/FY22)
Complete (only 1 usable set)
- Pre-Series: 3 sets (FY24)
Complete but not deliverable
- Reduced scope to only H-HOMs
- Series: 10 sets (FY24/FY25)




- Quality of Hook/Tee EBW are improved (top right).
- Pre-Series deviations are smaller than prototypes, which passed simulations and RF check.
- All ceramic feedthroughs are now provided by CERN.




Production Status

Hooks/Tees
7 out of 10 complete



Hook and Tee Weldment



**DN100
Brazements**
5 out of 10
complete



**DN40
Brazements**
8 out of 10
complete

**Inner Can
Assembly**



Final Assembly








Production Schedule

| | | 2024 | | | 2025 | | | | | |
|------------------|--------------------------|------|-----|-----|------|-----|-----|-----|-----|-----|
| | | Oct | Nov | Dec | Jan | Feb | Mar | Apr | May | Jun |
| HHOM 01 - 04 | Assembly | █ | █ | █ | █ | █ | | | | |
| | Testing | | | | | | █ | | | |
| | Acceptance | | | | | | | ★4 | | |
| HHOM 05 - 07 | Assembly | | █ | █ | █ | █ | █ | | | |
| | Testing | | | | | | | █ | | |
| | Acceptance | | | | | | | | ★3 | |
| HHOM 08 - 010 | Raw Material Procurement | █ | █ | █ | | | | | | |
| | Part Fabrication | | █ | █ | █ | █ | | | | |
| | Assembly | | | █ | █ | █ | █ | █ | | |
| | Testing | | | | | | | | █ | |
| | Acceptance | | | | | | | | | ★3 |



Prototype Jacketing at Zanon

- Welding of Proto #2 Helium Tank was completed without surprises and with ~zero frequency shift.
- Cavity is at JLAB waiting for cleanroom equipment to be ready for HPR and preparations for cold test.
- Magnetic measurements were completed, showing an attenuation factor of ~ 40x well above specification.
- No changes foreseen for pre-series / series.




Jacketing of Pre-Series + Series

- First two magnetic shield assemblies and all Titanium materials are in hand at Zanon.
- Manufacturing drawings all approved.
- Welding book still not approved, contingent on tests at CERN on bimetallic transitions.



Acceptance of RFD cavities

- Acceptance Plan
 - Describes the process for acceptance between AUP and CERN, including OK to ship from CERN, and final checks at TRIUMF after receiving
- Acceptance Criteria – Part A (at JLab)
 - All requirements from FRS will be verified with a test or a set of measurements during cavity production or during final tests at JLab.
- Acceptance Criteria – Part B (at TRIUMF)
 - Series of tests/measurements to be carried out at TRIUMF under AUP supervision to confirm performance of cavities after shipment.
- Revising to implement:
 - 2K operation at TRIUMF
 - 4.5 MV administrative limit.



Recommendations from DOE Review

July 2024

- 1. *“Re-evaluate if the cavity re-processing procedure needs to include the 48h 120C bake by the end of CY24.”*

Status: **OPEN**. Topic for discussion at this annual meeting.

- 2. *“Evaluate if cavity High Pressure Rinse (HPR) procedures need to be adjusted to allow multiple re-rinse cycles without surface oxidation by the end of CY24.”*

Status: **ADDRESSED (CLOSURE by end of CY24)**. HPR Process at Zanon was adjusted to better align with the process at JLAB which has proven to be successful. First HPR cycle was performed, particle counts in cleanroom dropped by a factor of ~10. Cold tests later this month.

- 3. *“Re-evaluate the required cavity re-rinsing rate, including potential impact on cost and schedule. Adjust the re-rinsing estimate, if necessary, by the end of CY24.”*

Status: **ADDRESSED (CLOSURE by end of CY24)**. Re-rinsing rate assumptions will be increased based on recent experience with 2 pre-series cavities. The scope increase will need to go through the monthly chance control board.

RFD Tests and Delivery Dates

Proto 2
PS 1
PS 2

| ZRI Serial | Bare Cavities delivered to FNAL | Bare Cavities qualified and back at Zanon | ZRI Serial | Jacketed Cavities delivered to JLAB | Dressed Cavities Delivered to TRIUMF | CERN Serial |
|------------|---------------------------------|---|------------|-------------------------------------|--------------------------------------|---------------------|
| NRFD001 | 6/1/2024 | 8/1/2024 | RFD001 | 9/15/2024 | 1/15/2025 | HCACFCA005-UP000001 |
| NRFD002 | 8/17/23 | 9/15/2023 | RFD002 | 4/16/2024 | 1/31/2025 | HCACFCA005-UP000002 |
| NRFD01 | 10/7/2024 | 12/1/2024 | RFD01 | 1/30/2025 | 3/31/2025 | HCACFCA002-UP000001 |
| NRFD02 | 4/16/2024 | 9/20/2024 | RFD02 | 11/19/2024 | 2/15/2025 | HCACFCA002-UP000002 |
| NRFD03 | 11/15/2024 | 1/14/2025 | RFD03 | 2/28/2025 | 4/29/2025 | HCACFCA002-UP000003 |
| NRFD04 | 12/6/2024 | 2/4/2025 | RFD04 | 3/21/2025 | 5/20/2025 | HCACFCA002-UP000004 |
| NRFD05 | 12/27/2024 | 2/10/2025 | RFD05 | 3/27/2025 | 5/26/2025 | HCACFCA002-UP000005 |
| NRFD06 | 1/17/2025 | 3/3/2025 | RFD06 | 4/17/2025 | 6/16/2025 | HCACFCA002-UP000006 |
| NRFD07 | 2/4/2025 | 3/21/2025 | RFD07 | 5/5/2025 | 7/4/2025 | HCACFCA002-U |
| NRFD08 | 2/22/2025 | 4/8/2025 | RFD08 | 5/23/2025 | 7/22/2025 | HCACFCA002-U |
| NRFD09 | 3/12/2025 | 4/26/2025 | RFD09 | 6/10/2025 | 8/9/2025 | HCACFCA002-U |
| NRFD10 | 3/26/2025 | 5/10/2025 | RFD10 | 6/24/2025 | 8/23/2025 | HCACFCA002-U |
| NRFD11 | 4/9/2025 | 5/24/2025 | RFD11 | 7/8/2025 | 9/6/2025 | HCACFCA002-U |
| NRFD12 | 4/23/2025 | 6/7/2025 | RFD12 | 7/22/2025 | 9/20/2025 | HCACFCA002-U |

| Agreed Late Delivery Dates |
|----------------------------|
| Apr-25 |
| Jun-25 |
| Jul-25 |
| Sep-25 |
| Oct-25 |

- Deliveries range from **February – September 2025**.
- Delays since last update can be attributed to challenges with geometrical tolerances, managing NCRs according to QA plan, unexpected JLAB VTA shut-down.
- Dates in red indicate conflict with JLAB shut-down.
- Prototype** estimated to arrive at TRIUMF in January 2025.
- Pre-Series** cavities estimated to arrive at TRIUMF shortly after.

Summary

- Successful cold test of Pre-Series cavity, validating the materials, the fabrication, and the chemical processing for the deliverables.
- Issues with processing and high-pressure rinsing appear to be addressed. Confirmations will come with tests in the upcoming months.
- Completed the first helium tank welding without surprises. Cold tests to confirm in Dec-Jan. Zanon is ready for the next tanks.
- Series cavities still at peak production, prioritizing quality, navigating through NCRs, slower than anticipated, but no showstoppers.
- Horizontal HOM dampers are at peak production at JLAB with first deliveries in Spring 2025, in time for dressed cavity tests.
- Acceptance Plan being slightly revised, to be validated with Prototype and executed with Pre-Series soon after.
- We will entertain discussions in WP4 on HPR process, as recommended by the recent DOE review.
- Deliveries of 10 cavities to TRIUMF range Jan-Sep 2025. We have consumed the float to "late" deliveries.

THANK YOU FOR YOUR ATTENTION!

U.S. RFD Teams

Fermilab

RF/Mech Design, Procurements, Cold Tests

Leonardo Ristori, Paolo Berrutti,
Manuele Narduzzi, **Sasha Netepenko,**
Taha Posos, Colin Narug, **Marilyn**
Wodzinsky

Jefferson Lab

HOM Dampers Fabrication and Cold Tests

Naeem Huque, Alex Castilla, **Peter**
Owen

Old Dominion University

General Oversight and RF measurements

Jean Delayen, Subashini De Silva

SLAC National Accelerator Laboratory

RF Simulations

Alessandro Ratti, Zenghai Li



The poster for the HL-LHC Collaboration Meeting in Genova, Italy, features a collage of images: a lighthouse at sunset, a yellow particle detector component, and a group of people. The text is arranged in a grid-like fashion with large, bold letters.

HIGH LUMINOSITY LHC

HL-LHC COLLABORATION MEETING

GENOVA, ITALY, 7-10 October 2024

Jointly organised by **INFN** and **CERN**, the **14th HL-LHC Collaboration Meeting** will take place in person in **Genoa, Italy** from **7th to 10th October 2024**. This edition will provide the occasion to showcase the successful production and validation of the first series D2 magnets, produced by ASG in Genoa as an in-kind contribution by INFN (Italy), as well as the completion of production of the MgB₂ wires for the superconducting link by ASG.

Based on the traditional programme with plenary and work package parallel sessions, this meeting will serve as a technical update forum for the 8th Cost and Schedule Review, scheduled for 11th to 14th November 2024. The main objectives will be to update all HiLumi collaborators on the advancement of the series production of components for the project, to showcase the status of the IT String test stand installation at CERN, and to update all collaborators on the latest schedule changes.

| CERN – Organizing Committee | INFN – Local Organizing Committee |
|--|---|
| Oliver Brüning Project Leader | Andrea Bersani - Communication Officer |
| Markus Zerlauth Deputy Project Leader | Barbara Caiffi - MBRD Deputy Technical Coordinator |
| Cecile Noels Project Office & Communications | Mirko Corosu - IT Manager |
| Florence Thompson Project Office & Communications | Stefania Farion - MBRD Technical Coordinator |
| | Filippo Lovi - Deputy Conference Coordinator |
| | Alessandra Pampaloni - Conference Coordinator |
| | Marco Statera - HO Corrector Technical Coordinator |

For more details and registration : HL-LHC.Secretariat@cern.ch / hilumilhc.web.cern.ch

