



MQXFA Fabrication Status & Schedule

*Giorgio Ambrosio - FNAL
with contributions from the
whole MQXFA team*



HIGH LUMINOSITY LHC

th

HL-LHC COLLABORATION MEETING

GENOA, ITALY, 7-10 October 2024

Jointly organised by **INFN** and **CERN**, the **14th HL-LHC Collaboration Meeting** will take place in person in **Genoa, Italy** from **7th to 10th October 2024**. This edition will provide the occasion to showcase the successful production and validation of the first series D2 magnets, produced by ASG in Genoa as an in-kind contribution

by INFN (Italy), as well as the completion of production of the MgB₂ wires for the superconducting link by ASG.

Based on the traditional programme with plenary and work package parallel sessions, this meeting will serve as a technical update forum for the 8th Cost and Schedule Review, scheduled for

11th to 14th November 2024. The main objectives will be to update all HiLumi collaborators on the advancement of the series production of components for the project, to showcase the status of the IT String test stand installation at CERN, and to update all collaborators on the latest schedule changes.



CERN – Organizing Committee

Oliver Brüning - Project Leader
Markus Zerlauth - Deputy Project Leader
Cécile Noels - Project Office & Communications
Florence Thompson - Project Office & Communications

INFN – Local Organizing Committee

Andres Bersani - Communication Officer
Barbara Caffi - MBRD Deputy Technical Coordinator
Mirko Corcos - IT Manager
Stefania Farison - MBRD Technical Coordinator
Filippo Levi - Deputy Conference Coordinator
Alessandra Pampaloni - Conference Coordinator
Marco Statera - HQ Connector Technical Coordinator

Acknowledgement



- **US HL-LHC Accelerator Upgrade Project (AUP)**
 - **BNL:** K. Amm, M. Anerella, A. Ben Yahia, M. Bornstein, H. Hocker, P. Joshi, F. Kurian, J. Muratore, J. Schmalzle, P. Wanderer
 - **FNAL:** G. Ambrosio, G. Apollinari, M. Baldini, J. Blowers, R. Bossert, R. Carcagno, G. Chlachidze, J. DiMarco, S. Feher, S. Krave, V. Lombardo, C. Narug, A. Nobrega, V. Marinozzi, C. Orozco, T. Page, J. Seyl, S. Stoynev, T. Strauss, M. Turenne, D. Turrioni, A. Vouris, M. Yu
 - **LBNL:** D. Cheng, J. Doyle, P. Ferracin, L. Garcia Fajardo, E. Lee, M. Marchevsky, M. Naus, I. Pong, S. Prestemon, K. Ray, G. Sabbi, G. Vallone, X. Wang
 - **NHMFL:** L. Cooley, J. Levitan, J. Lu, R. Walsh
- **CERN: HL-LHC Project**
 - G. Arnau Izquierdo, A. Ballarino, M. Bajko, C. Barth, N. Bourcey, B. Bulat, M. Cruovizier, A. Devred, H. Felice, S. Ferradas Troitino, L. Fiscarelli, J. Fleiter, M. Guinchard, O. Housiaux, S. Izquierdo Bermudez, N. Lusa, F. Mangiarotti, A. Milanese, A. Moros, P. Moyret, C. Petrone, J.C. Perez, H. Prin, R. Principe, E. Ravaioli, T. Sahner, S. Sgobba, P. Tavares Coutinho Borges De Sousa, E. Todesco, J. Ferradas Troitino, R. Van Weelderren, G. Willering

Outline

- **MQXFA17 Analysis**
- **Status by Component**
- **Schedule and Plans**

MQXFA17 Analysis I

- MQXFA17 showed detrainning and degradation in a single coil during vertical test
 - Quench location (Lead End) similar to MQXFA13
 - Inverse temperature and ramp-rate dependence
- Analysis, in progress, has found:
 - Main factor: **low prestress in the lead end**
 - Possible contributing factor: variations in coil properties




MQXFA17 Analysis II

Increased to
135 MPa

- Main factor: low prestress in lead end
 - Actual load keys (39 mil) < Target load keys (43 mil)
 - One coil gauge reached max allowable stress (**120 MPa**) during bladder operation.
 - Shell and Coil averages were also close to the max of their spec ranges
 - MQXFA magnet Specs (doc-4009): *“If, with such load key shim targets, the coil stress measured in 2+ strain gauges during the loading or during bladder inflation indicate that the coil stress may reach values above the coil stress spec. during subsequent loading steps or at the end of the loading, **priority should be given to keeping the coil stress within the specs.**”*
 - Tapered load shims had not yet been demonstrated

More details in “MQXFA magnet assembly & preload” in this session





Load keys



Inserted in MQXFA18/12b/16 and will be used in all future magnets

Lessons Learned from MQXFA13/17 test & analysis

- If midplanes in coil ends are “too small” & there is low prestress → risk of excessive strain



Relative differences are more relevant than absolute numbers because of mesh size and de-bonding assumptions





Courtesy of A. Bartkowska 6

Preventive Actions

- Main actions:
 - Added Tapered Load Shims in magnet Lead End
 - During last step of azimuthal preload
 - Added coil dimension measurements in the critical area and FE analysis based on measured coil size
 - Increased target prestress from 80 to 90 MPa
 - Set target for minimum loading key size based on coil dimensions → higher pre-stress controlled by dimensions
 - Comparison with best magnets
 - Increased the maximum allowable stress during preload from 110 to 135 MPa
 - Based on feedback from CERN MQXFS program

Load keys & shims



Tapered load shims in Lead End

More details in “MQXFA magnet assembly & preload” in **this session**

Limiting Coils



Magnet	Q1	CLIQ + Q2	Q3	CLIQ + Q4
MQXFA03	204	110	202	111
MQXFA04	203	113	206	112
MQXFA05	207	116	209	115
MQXFA06	122	119	211	123
MQXFA07	212	124	214	114
MQXFA07b	212	124	218	114
MQXFA08	215	126	213	128
MQXFA08b	215	126	219	128
MQXFA10	132	221	131	129
MQXFA11	223	222	134	135
MQXFA13	227	139	229	141
MQXFA14b	217	230	143	231
MQXFA15	233	226	220	117
MQXFA17	151	237	152	239
MQXFA13b	150	139	229	141

Coil issue caused by small/zero pole-key gaps in this magnet quadrant

Coil issue caused by small (average) arc-length in lead end.

All coils were affected

➔ Why coil 239 failed in MQXFA17?




Coil Property Measurement & Simulations

Coils in MQXFA magnets

Magnet	Q1	CLIQ +	
		Q2	Q3
MQXFA03	204	110	202
MQXFA04	203	113	206
MQXFA05	207	116	209
MQXFA06	122	119	211
MQXFA07	212	124	214
MQXFA07b	212	124	218
MQXFA08	215	126	213
MQXFA08b	215	126	219
MQXFA10	132	221	131
MQXFA11	223	222	134
MQXFA13	227	139	229
MQXFA14b	217	230	143
MQXFA15	233	226	220
MQXFA17	151	237	152
MQXFA13b	150	139	229

- Question: “Are there coil-coil differences that may cause a weakness in some coils?”
- Measurements:
 - Wedge to end-part gap dimension
 - Bonding strength epoxy-wedge
- Simulations:
 - Impact of gaps dimension & “filled” epoxy properties on strain at wedge-part transition



Coil 239 after epoxy impregnation

Outline

- MQXFA17 Analysis
- **Status by Component**
- **Schedule and Plans**

MQXFA Status Summary

Control Account	Component status wrt Baseline*	Comments
Strand procurement & QC (FNAL, FSU)	96% complete	Procuring spare cond.
Cable fabrication & insulation (LBNL)	100% complete	
Coil part procurement (FNAL)	~100% complete	Completing QC
Coil fabrication (FNAL)	98% complete	Last coil fabrication
Coil fabrication (BNL)	100% complete	
Magnet part procurement (LBNL)	100% complete	
Magnet assembly (LBNL)	58% complete	

*Will change if additional cables/coils are added to Baseline

- ➔ Main task is magnet assembly.
Supported by 4 reviews / meetings per magnet



Coil Status

Coils available (completed, not yet power tested)	38	
Coils in production (at Fermilab)	1	
Coil rejected during fabric., magnet integr. & test		13
Coil on hold after fabric., magnet integr. & test		16
Coils to be recovered from on-hold – future issues	1	
Coils needed for magnets not yet tested (10)	- 40	
Expected coils balance	0	

- Two risks for additional coils in Risk Register
 - Risk of coil issues during magnet test
 - All other coil issues (mostly magnet assembly)

Conductor Status

- Strand Inventory:
 - Available strands for **one MQXFB** (~800 m) cable
 - Incoming strand:
 - for **3 MQXFA cables** (~500 m) by end of October
 - for **2 MQXFA cables** by January 2026 (maybe earlier)
- Cable inventory is empty:
 - Planning to make one MQXFA cable in Nov./Dec.
 - We may make 2 more cables in first quarter of 2025

Coil Parts


Coil Parts	Qt. in inventory
Pole	3
End Parts	3
Wedges	16
QH Trace	4
NbTi Cable	13
Insulation Components	3

Under procurement	Qt.	Status
CERN End Parts Coating	14+ sets	In coating process at the vendor
MQXFA QH Trace	2	Under fabrication at CERN

MQXFA Structures and Assembly

- Structure procurement is complete (except a few spare parts).
- Magnet assembly is at peak production with two assembly lines fully operational
- 20 MQXFA magnets assembled (MQXFA03-18, 7b, 8b, 13b, 12b):
 - MQXFA12b: used to test insertion of tapered load shims
 - Tapered load shims were inserted in the Lead End at $\frac{1}{2}$ preload and removed to test the procedure.
 - Data from additional gauges were analyzed → very good agreement with FE
- FMEA through all magnet assembly travelers to address integration issues (first round done, second in progress)

More details in “MQXFA magnet assembly & preload” in **this session**



Plans and Schedule

- Plans for next magnets:
 - MQXFA18 (1st with TLS) is under test at BNL
 - MQXFA12b retrofitted with TLS (50 um) is at BNL
 - MQXFA16 retrofitted with TLS (50 um) almost complete
 - Re-assembly of MQXFA17b has started
- Working Schedule
 - August update:


Magnet Assembly	P6 Schedule	
P6 Label	Start	Finish
MQXFA-12b	2-Feb-24	9-Sep-24
MQXFA-16TLS	9-Sep-24	10-Oct-24
MQXFA-R4/17b	23-Aug-24	21-Nov-24
MQXFA-19	27-Jun-24	12-Dec-24
MQXFA-20	15-Oct-24	28-Jan-25
MQXFA-21	26-Nov-24	11-Mar-25
MQXFA-22	15-Jan-25	22-Apr-25
MQXFA-23	27-Feb-25	28-May-25
MQXFA-24	10-Apr-25	24-Jun-25
MQXFA-R5	27-May-25	1-Aug-25

Magnet Tests

More details in “Production testing summary of the MQXFA magnets” in **WP3** session Tue PM

Vertical test is done at BNL by 302.4.01, post-test analysis is done by 302.2.01

- 11 magnets met requirements during vertical test
 - 3 magnets (MQXFA07/08/13) needed a coil change to meet requirements
 - 1 magnet (MQXFA17) is waiting for a coil change
 - MQXFA05 passed the Endurance Test
 - 7 thermal cycles (5 vertical + 2 in CA02), 53 quenches, 87+ power cycles
 - MQXFA11 demonstrated resilience (after highway crash)



All magnets that showed limited test performance during vertical test were identified during the first thermal cycle (TC).
 → All magnets will be tested vertically, with only one TC to be within budget.



MQXFA magnet being moved to vertical test station at BNL

MQXFA Summary



- 11 magnets met requirements, 10 more to go
 - 3 magnets that did not meet requirements were repaired by changing one coil and met requirements.
 - All magnets will be vertically tested
- Major procurements are complete
- Last coil is in fabrication at Fermilab
- Strands in inventory for up 5 coils (6 max)
- Coil parts in inventory for up ~3 coils
- Magnet assembly is at peak production rate
- Lessons learned have been implemented in revised design features and assembly specs
- We plan completing the assembly of all magnets by next HL-LHC Collaboration Meeting

Back up Slides




MQXFA/B Design

PARAMETER	Unit	MQXFA/B
Coil aperture	mm	150
Magnetic length	m	4.2/7.15
N. of layers		2
N. of turns Inner-Outer layer		22-28
Operation temperature	K	1.9
Nominal gradient	T/m	132.2
Nominal current	kA	16.23
Peak field at nom. current	T	11.3
Stored energy at nom. curr.	MJ/m	1.15
Diff. inductance	mH/m	8.26
Strand diameter	mm	0.85
Strand number		40
Cable width	mm	18.15
Cable mid thickness	mm	1.525
Keystone angle		0.4



Nb₃Sn Conductor
RRP 108/127



P. Ferracin et al., "Development of MQXF, the Nb₃Sn Low-β Quadrupole for the HiLumi LHC" IEEE Trans App. Supercond. Vol. 26, no. 4, 4000207


G. Ambrosio et al., "First Test Results of the 150 mm Aperture IR Quadrupole Models for the High Luminosity LHC" NAPAC16, FERMILAB-CONF-16-440-TD

Low- β quadrupole magnets from LHC to HL-LHC


- Cold mass OD from 490/420 to **630 mm**
- More than double the aperture: from 70 to **150 mm**
- **~4 times** the e.m. forces in straight section
- **~6 times** the e.m. forces in the ends

State of the art quadrupoles at the time of LHC construction


MQXA



MQXB




MQXF




Same scale for all 3 plots

“Endurance” & “Resilience” Demonstrations



MQXFA05 “Endurance Demonstration”

All magnets that met requirements demonstrated **very good memory** and **temperature margin**:
 I_{nom} @ 4.5 K



MQXFA11 “Resilience Demonstration”