

Status and Strategy of Beam Loss Monitor Ionisation Chamber (BLM IC) Production

Gerhard Schneider for BLM IC team



14th HL-LHC Collaboration Meeting, Genoa, 09.10.2024

Contents

- BLM System Function
- BLM IC History at CERN
- BLM IC Production Objectives
- BLM IC Parts
- BLM IC Production Sequence
- Status of the Project
- Strategy for the Coming Years
- Summary





Beam Loss Duration and Protection Systems



- Impossible to have active protection from ultra-fast losses
- No real redundancy for fast losses; later additions of beam and magnet current change monitoring



Courtesy: C. Zamantzas

LHC BLM System Overview



- A highly critical system for the protection of the LHC.
- Deployed throughout the 27 km tunnel.
- Speed, reliability, fail-safety are required.
- A large amount of measurement data is published continuously.





Work Principle of the BLM IC



- Voltage 1500 V
- 1.1 bar Nitrogen Gas
- 61 Electrodes
- Particle Ionising Gas

5

Measure Current



BLM IC History at CERN

- More than 4,000 BLM ICs are operating at CERN.
- About 93% are installed in the LHC.
- They were previously produced in collaboration with external institutes.
- The end of long-term collaboration with these institutes made re-engineering of the BLM IC necessary.



Production Objectives

Produce 1000 BLM ICs:

- 200 for HL-LHC
- 800 for the renovation in the LHC injector complex
- Timeline:
 - 400 units to be delivered by end 2025
 - >200 units to be delivered by end 2026
 - Remaining units in 2027



BLM IC Parts Overview

- Ceramics Al₂O₃ with very low conductance (2x)
- Electrodes: AI EN6082 (61x)
- Ceramic Feedthroughs (2x)
- Welded cover with all vacuum welds done by TIG
- Vacuum container
- Many other components, totaling 330 parts





BLM IC Critical Part Endplate

- Endplate Production Competencies (LHCBLM_0002):
 - Precision machining
 - UHV cleaning
 - UHV-compatible assembly and welding of copper "pinch-off" tube (SS/Cu) and electric feedthroughs (SS/SS)
 - Dimensional and basic electrical checks
 - Leak check



Ceramic feedthroughs (2x) Copper tube dia 8/10 mm Stainless Steel plate 304L Copper to Stainless Steel weld

BLM IC Critical Part Ceramic Insulator

- Ceramic Insulator Production Competencies (LHCBLM_0005):
 - Precision ceramic Al₂O₃
 - Ultra-high resistance:
 - < 1 pA when 1.5 kV applied
 - Resistivity checks in a controlled environment to guarantee consistent measurements
 - UHV-clean delivery







BLM IC Parts Assembly Sequence (1/3)"Stacking"

- Mount the electrodes, spacers and ceramic insulators.
 - The spacers and electrodes are stacked by arranging the electrodes in an alternating pattern.
- Low dust & hydrocarbon "free" area required → office type cleanliness sufficient.







BLM IC Parts Assembly sequence (2/3)"End Plate"

 The End Plate (LHCBLM_0002), with electrical connections and "Pinch-off", is installed.





BLM IC Parts Assembly Sequence (3/3)"Finishing"

- Insert the stack, including the end-plate, into the vacuum housing.
- Two Leak-tight welds are made on either end of the tube.





BLM IC Conditioning and Finishing on Test Stand

- Leak Check
- Bakeout to 220 °C
- Residual Gas Analysis
- Refill with Nitrogen to 1,100mbar absolute (100 mbar overpressure)
- "Pinch-off"
- Electrical Checks

→Complex expert procedure







Add the electronic components and yellow sleeve

 Add all electrical components to the BLM IC.

 Install the yellow sleeve onto the BLM IC.





Status of the Project – Set the scene 23/24

- Following the end of the collaboration, a significant amount of re-engineering was required to ensure the function and quality of the BLM IC production.
- The result of this process has resulted in several drawings and engineering specifications.



Status of the Project – Produce New BLM ICs with the New Procedures 23 and 24 in HiRadMat



Done with a beam of 288b (4x42b)

Similar Trend as previous measurements

Total 6 BLM tested: Performance as expected



Status of the Project – Procurement

- The raw material orders on-going
 - \rightarrow Not expected to be critical.
 - →All relevant raw materials have been ordered by CERN according to CERN specifications.
- Price enquiries for critical items are currently with the bidders:
 - Ceramic insulator as per DO-34404/SY/HL-LHC (DR-10411247).
 - End plate as per DO-34448/SY/HL-LHC (DR-10441935) to be sent out in the days to come.





20

Nalkway

BLM Test stand and

Status of the Project – Go For Series Production: Location @ CERN

- Objective is to have 400 produced by end 2025:
 - CERN's in-house production will fully confirm the processes.
 - → "Stacking" will occur in 37-R-15+17, and the lab space is currently being cleared.
 - → The BLM IC test stand in building 283 requires significant refurbishment and the installation of safety equipment, including fire detectors.



Status of the Project – Go For Series Production: Missing Apparatuses

- Extension of the Test Stand aims to transition from 1 single item to a batch process of 20 units in one bake-out cycle.
 - Objective is to achieve one (ideally two) bake- out cycles per week.
 - \rightarrow A study for the extension is ongoing.
 - Rotation of personal on this particular job is causing some delays.





Strategy of the Years to Come

2024

- → Order all materials.
- \rightarrow Design the extension of the test stand.
- 2025
 - \rightarrow Make assembly space available for CERN in-house series production (Q1/Q2).
 - → Follow-up production of BLM IC components.
 - → Procure and assemble the test bench extension.
 - → Advance the strategy for assembling the remaining 600 units, either in collaboration with a partner institute (possibly at a lower cost) or within European industry.
- 2026
 - \rightarrow Start series production outside CERN.



Summary

- 1,000 BLM ICs to be produced, including 200 for HL-LHC.
- BLM ICs were re-engineered, design updates were made, and prototypes produced at CERN. A total of 6 BLM ICs were tested in HiRadMat in 2023 and 2024.
- All relevant series raw materials are procured by CERN to guarantee the quality, especially for vacuum-critical material.
- Price inquiries for critical components, such as the ceramic insulator and the end plate, have been sent out or are imminent.
- The test stand extension to accommodate 20 units ongoing.
- Lab space is being prepared to start CERN's in-house production of 400 units as from Q2 2025.
- Efforts to establish contacts with both institutes and industry are ongoing to make the assembly of the remaining 600 units.





"THANK YOU"

to all the many, many colleagues in

SY-BI, EN-MME, TE-VSC, ATS-DO, IPT-PI, HSC-OHS,...

