

# Canada RFD CM series challenges – procurements and schedule

Bob Laxdal

TRIUMF Hi-Lumi Technical Coordinator

Oct. 9, 2024



# Project Strategy


- The project strategy calls for procurement of parts for a single cryomodule, TCM0, followed by procurement of parts for the production series TCM1-4
- Project slippages due to Covid and other forces vs. boundary conditions on project funds are having an impact on this strategy
  - Shifting timelines for
    - TCM0 cavities from AUP
    - Released drawings, deliverables and parts lists from CERN
  - Fixed timeline for spending the funds
- The present strategy has been to procure series components as soon as drawings are released and strategically assign some scope to CERN in order to spend \$\$ within fixed timeline



# Funding constraints

- Due to the nature of the funding agreement ALL funds for the project must be spent and all parts received (to trigger payment) before April 2025
- ✓ Over 5M\$ has been committed over the last year - TRIUMF has presently spent or committed 97% of the funds – (now 98%)
- Present risks
  - Over 50% of funds are encumbered including 19% from CERN that need delivery to TRIUMF before April 2025
  - Some drawing packages and procured parts lists are still not released

Spent	Encumbered	CERN scope	Remaining
\$4,328,342	\$3,531,564	\$1,873,701	\$266,393
43.3%	35.3%	18.7%	2.7%



# Schedule Discussion

# Cryomodule Assembly Boundary Conditions

- CM string assembly requires cavities from AUP, FPCs and beamline assemblies from CERN – first articles are required to assemble TCM0 and TCM1
- The critical path runs through delivery of the prototype cavity (**rigid**) and CM design (**coupled to parts fabrication schedule**)
- TRIUMF also requires delivery of CM parts from CERN for both *in scope* articles and *added scope* articles (at least for first units):
  - Rf test adaptors – **Jan 2024** - Dec 2024
  - String assembly components – **Mar 2024** - Mar 2025 – partial PIMs received
  - CM assembly – **April 2024** - May 2025
  - CM test – **May 2024** - Oct. 2025




AUP Delivery Projection		
Cavity Pair	Module	Delivery
Prototype	TCM0	<b>Feb 2025</b>
Cavities 1 and 2	TCM1	May 2025
Cavities 3 and 4	TCM2	Jun 2025
Cavities 5 and 6	TCM3	Jul 2024
Cavities 7 and 8	TCM4	Aug 2025
Cavities 9 and 10	TCM5	Sep 2025

\* indicates requested dates as of Oct. 2023

# The 'TRIUMF' Schedule Issue

- The 'TRIUMF' schedule shown at the plenary is a reflection of a long list of dependencies, delays and lessons learned
  - AUP/ZANON challenges with jacketing - **delays TC0**
  - JLAB cavity testing shutdown - **delays TC0**
  - CERN delays in final design, FPC/rf adaptors production and lessons learned from CM testing – **impacts 'bravery factor' for TCM0 and CM production times**
  - UK lessons learned in the RFD prototype build timing – **experience argues against being too aggressive with schedule**
- TRIUMF is the last in the queue but the slippages in the schedule to date are a WP4 issue and need understanding in that context
- What follows is an attempt to rationalize and understand TRIUMF's estimate of what is possible and critical path




# Schedule Methodology

In preparing the estimate of the schedule update considering the TRIUMF 2026 SD we first estimated the present timeline without it

- Finding: Project end date (without SD) anticipated as May 2028


# TCM0 strategy and string assembly qualification logic

- The prototype cavity TC0 will be requalified after arrival from Jlab
  - The test coupler will be removed and the FPC installed
- The dummy cavity will be prepared for string installation
- The string will be assembled and leak checked and then vented and disassembled
- TC0 will be retested via cooldown to 2K
- The successful test of TC0 after string assembly is a critical milestone for the project and is required before string assembly of TCM1
- The arrival of TC0 at TRIUMF is on the critical path for all deliverables to CERN – the arrival has been steadily being pushed out over the last year







# Timeline without SD2026 (First cavity)



# Timeline without SD2026 (Cryomodule design)



# Timeline without SD2026 (Cold tests)




# Schedule Methodology

In preparing the estimate of the schedule update considering the TRIUMF 2026 SD I first estimated the present timeline without it

- Finding: Project end date (without SD) anticipated as May 2028
- Fact: Estimated end date at Oct. 2023 meeting was Oct. 2026 (19 months earlier)

# Timeline - Oct. 2023



# Rationalization of dates


- In Oct. 2023 collaboration meeting the end date was indicated as Oct. 2026
  - so why now is it May 2028 (+19 months)?
- Consider
  - First cavity delayed by 11 months
  - Cryomodule design delayed by 12 months
  - TCM0 logic was not appropriately considered – recommend to add a characterization milestone – add +4 months
  - First build (TCM1) too aggressive based on UK experience – add +4 months

	<b>Oct. 2023</b>	<b>Oct. 2024</b>	<b>Oct. 2024 **</b>	<b>Oct. 2024 ****</b>
TC0 arrival	March 2024	Feb. 2025 (+11)		
CM design frozen	Dec. 2023	Dec. 2024 (+12)		
Project complete	Oct. 2026	Sept. 2027 (+11)	Jan 2028 (+4)	May 2028 (+4)

\*\* consider to add a TCM0 qualification milestone

\*\*\*\* consider to increase time of TCM1 (first full build – based on UK experience)

# Timeline - Oct. 2023




19 months

## And ..... Impact of TRIUMF SD2026


- TRIUMF management has decided (just) to implement a long shutdown in 2026 to focus effort on the completion of the ARIEL project
- Technicians on HiLumi will be assigned tasks with ARIEL during 2026 that will slow effort on CM assembly
- Qualification of arriving AUP cavities will not be impacted – cavity testing facilities will be supported
- The actual impact on HiLumi will only be known once the ARIEL tasks are fully assigned – the goal will be to add sufficient effort to determine that all parts are in hand for the series starting in 2027
- We estimate that this will push out project completion by **~6 months**



# Timeline without SD2026



# Timeline with SD2026





# What can be done?

- Understand the dependencies
- Stop the bleeding
  - Deliver TC0 in Feb 2025 in order to make real progress before 2026
    - Goal is to qualify string assembly and parts inventory before end of long shutdown
  - Try to freeze the design as of Dec. 2024 – procurement impacts schedule
  - Deliver all parts on time
- Add risk – for discussion but not recommended
  - Decouple TCM0 build from TCM1 (saves ~2 months)
  - Assume a (more) success-based schedule (saves ~4 months)
    - There is experienced gained that would indicate that the schedule is already somewhat success based – with little contingency – ie no expectation in schedule that CM fails test or cavity fails requalification
  - Send last (spare) module without cold test (saves 3 months)

# Other discussion points

# Preparation for cavity testing

- TRIUMF will requalify the AUP cavities upon delivery from JLab
- TRIUMF worked with AUP to draft cavity requalification test criteria
- **Important that this gets signed off soon**



# Procurement cooperation

## CERN/TRIUMF agreement on parts exchange

- excellent cooperation to help deal with NA material issues and

## Bi-phase lines

- Production well advanced at CERN with first article for TCM1 delivered – excellent cooperation

## SS316 material

- CERN sends TRIUMF material to overcome lack of certified material in NA


## Hardware/Instrumentation

- TRIUMF needs updated list of procured parts ASAP including fastener summary BOM

## Invoicing



- WP4 may need to coax the first invoices from CERN-> TRIUMF to get money flowing

Description	Date
4x-HOM adapters and 2x field antenna	TBD
5x Bi-phase and lower cryo-lines for RFD	(1x) Mid-Summer 2024 Remainder Q1 2025
Full set of vacuum equipment for beam Lines and ancillaries	(1x) Q3 2024 Remainder Q1 2025
FSI interferometer unit (sweeping lasers + electronics)	TBD
Full set of Tuner bellows and cavity support (blades) bellows	TBD
Additional AdHoc Equipment for TCM0 and series Cryomodules	TBD



## First PIMs received from CERN

- Components for first string assembly
- Tested in clean room for particulate
- Results seem acceptable – good to compare with UK experience



# RESULTS

## **SMALL BELLOW**

- Flanges had a particle count of 57 for 0.3 micron.
- The assembly had a particle count of 1257 for 0.3 micron in the beginning.
- The particle count decreased to <250 with continuous cleaning by filtered Nitrogen.

## **LARGE BELLOW**

- Flanges had a particle count of 39 for 0.3 micron.
- The assembly had a particle count of 2282 for 0.3 micron in the beginning.
- The particle count decreased to <100 with continuous cleaning by filtered Nitrogen.



# Summary

- First cavity delivery and cryomodule design are both on the critical path for RFD completion
  - Interdependencies of delivery times and RFD project end need to be added to schedule
  - TRIUMF SD2026 estimated to have an impact of ~ 6 months
- 2024 strategy addresses finite time window for spending available funds
  - Requires timely delivery from vendors (and CERN) of agreed deliverables in order to make payments
  - ~1.6MCHF in CERN scope
  - ✓ First out of scope fabricated parts received from CERN

