

Magnetic Center Alignment Results

09Oct2024

Presented by J. DiMarco

Alignment of MQXFA magnets during Cryo Assembly (CA) production

- Relies on Single Stretched Wire (SSW) system with magnets powered at 10A AC (7.8125 Hz freq)
- Repeated at various steps of production to check, and if necessary, adjust, magnet alignment of the CA

SSW provides measurements of

- X/Y centers
- Z-center location
- Yaw, Pitch, Roll angles
- Integrated magnet strength



MQXFA04

MQXFA03


SSW system in use during fabrication

For each CA, measurements are made at various fabrication steps. Below is a typical example for CA03 – multiple measurements may be made depending on need for adjustments or to confirm results

LQXFA03													
		Magnet positions relative to average center line											
		SSW-A											
		MQXFA11					MQXFA10						
		LE		Interface End		Roll	LE		Interface End		Roll	Z-distance A11-A10	deltaAngle(mrad)
meas date	meas descrip.	X(mm)	Y(mm)	X(mm)	Y(mm)	(mrad)	X(mm)	Y(mm)	X(mm)	Y(mm)	(mrad)		
19-Apr-23	initial meas, no shell	-0.021	0.024	0.021	-0.024	-0.73	0.052	-0.228	-0.520	0.228	-0.26	4.7942	0.46
25-Aug-23	tacked, before weld	0.021	-0.062	-0.021	0.062	-6.30	0.421	-0.085	-0.421	0.085	-4.70	4.7934	1.59
27-Oct-23	after weld	-0.178	0.408	0.178	-0.408	-1.64	0.689	-0.695	-0.689	0.695	0.34	4.7932	1.97
31-Oct-23	after weld	-0.224	0.411	0.224	-0.411		0.685	-0.738	-0.685	0.738			
8-Jan-24	after end cap weld	-0.201	0.217	0.201	-0.217	8.24	0.683	-0.760	-0.683	0.760	10.02		1.78
4-Apr-24	on saddles	-0.104	0.320	0.104	-0.320		0.674	-0.572	-0.674	0.572			
5-Apr-24	on saddles, tacked	-0.119	0.324	0.119	-0.324		0.668	-0.612	-0.668	0.612			

LQXFA01

LQXFA01 end coordinates



Wire on 2-magnet average axis (common axis).
Reproducibility of end measurements generally on the ~0.1 mm level

A03

A04

LQXFA02

LQXFA02 end coords., wire on common axis




● Interface End X(mm)
 ● Interface End Y(mm)
 ● Interface End X(mm)
 ● Interface End Y(mm)

A06

A05

Alignment Relative to MQXFA11/MQXFA10 Average Center Line 27Oct2023 - after welding

Horizontal Offsets plan view




MQXFA11 Lead End: X= -0.224, Y= 0.411 mm
MQXFA11 Interface End: X= 0.224, Y= -0.411 mm
MQXFA10 Interface End: X= 0.685, Y= -0.738 mm
MQXFA10 Lead End: X= -0.685, Y= 0.738 mm

A11 roll angle = -1.64 mrad
A10 roll angle = 0.34 mrad
Delta angle = 1.97 mrad
Ave Angle = -0.65 mrad

A11 Z-dist A-stage to magnetic center = 3.7388 m
A10 Z-dist A-stage to magnetic center = 8.5320 m
Z-dist A11 to A10 = 4.7932 m (Lw=12.4866 m)

Vertical Offsets profile view



Normal separation of magnet Z-centers ~4.792 m

Alignment Relative to MQXFA15/MQXFA07b Average Center Line
10Jul2024 - Initial Meas.


CM05

In the initial alignment of CM05, the Z-center separation looked too close (on the edge of allowed range)


MQXFA15 Lead End: X= 0.064, Y= 0.145 mm
 MQXFA15 Interface End: X= -0.064, Y= -0.145 mm
 MQXFA07b Interface End: X= 0.244, Y= -0.223 mm
 MQXFA07b Lead End: X= -0.244, Y= 0.223 mm

A15 roll angle = -0.27 mrad
 A07b roll angle = 0.55mrad
 Delta angle = 0.82 mrad
 Ave angle = 0.14 mrad

A15 Z-dist A-stage to magnetic center = 3.5665 m
 A07b Z-dist B-stage to magnetic center = 3.5644 m
 Z-dist A15 to A07b = 4.7843 m (Lw=11.9147 m)




Vertical Offsets
profile view




Low by about 9 mm

Z-offset determination





Initial wire position





One magnet powered AC 10A, SSW aligned on magnet axis

$$L_m = \sim 4.2m$$



$$L_w = \sim 10m$$

Stages moved counter-directionally



$$x = +D$$

Including any stage offsets from magnet axis, x_a , x_b , the position of the wire in the magnet for stage position x , y is :

$$x_m = x - \frac{x_b - x_a}{z_b - z_a} (z - z_a) - x_a$$

$$y_m = y - \frac{y_b - y_a}{z_b - z_a} (z - z_a) - y_a$$

Flux induced for wire motion is

$$\varphi_{CN\pm} = \int_{z=z_a}^{z_b} \int_{x=0}^{x=\pm D} \left(1 - \frac{2z}{L_w}\right) g * (b_2 x_m - a_2 y_m) dx$$

Where g is the magnet gradient and b_2/a_2 are the normalized normal and skew quadrupole coefficients in the SSW frame (i.e. they allow for tilt of the SSW system wrt magnet)

Z-offset determination (continued)

$$\varphi_{CN_{\pm}} = gL_m * \left(b_2 \frac{D_2}{2} * \left(1 - \frac{2(z_b + z_a)}{L_w} + \frac{4}{3} * \frac{z_a^2 + z_b^2 + z_a z_b}{L_w^2} \right) \mp \text{additional terms} \right)$$

If average +/- flux from counter-directional motions

$$\varphi_{CN_Ave} = \frac{\varphi_{CN+} + \varphi_{CN-}}{2} = gL_m * \left(b_2 \frac{D_2}{2} * \left(1 - \frac{2(z_b + z_a)}{L_w} + \frac{4}{3} * \frac{z_a^2 + z_b^2 + z_a z_b}{L_w^2} \right) \right)$$

Also know that $z_a + L_m = z_b$

Where L_m is known from warm rotating coil measurements

Geometry dependent terms

Combine these to solve for $z_a + L_m/2$ which gives distance from the A-stage to the magnet center

$$z_c \equiv \left(z_a + \frac{L_m}{2} \right) = \frac{L_w}{2} \mp \frac{1}{2 * \sqrt{3}} \sqrt{\frac{6\varphi_{CN_Ave}}{gL_m D^2} L_w^2 - L_m^2}$$

Estimating resolution and error

$$z_C \equiv \left(z_a + \frac{L_m}{2} \right) = \frac{L_w}{2} \mp \frac{1}{2 * \sqrt{3}} \sqrt{\frac{6\varphi_{CN_Ave}}{gL_m D^2} L_w^2 - L_m^2}$$

$$L_w = 10m$$

$$g = 0.089 \frac{T}{m} @ 10A, roomTemp$$

$$D = 0.06m$$

$$L_m = 4.2 m$$


$$\varphi_{CN_Ave} = 1.95 \times 10^{-4} Vs$$

$$\varphi_{CO_Ave} = \frac{\varphi_{CO+} + \varphi_{CO-}}{2} = \frac{gL_m D^2}{2}$$

- φ_{CN_Ave} is measured by SSW during warm measurements to better than 5e-8Vs. An error in CN-flux of 2e-7Vs causes an error in z_C of 1.5mm. This implies that the **fundamental resolution** will be better than **0.5mm**.


- L_w is measured with laser tracker to better than 100um so is not a significant contribution to measuring Z_c (**0.1mm**).
- $L_m g D^2 = \sim 1.35 * 10^{-3} Vs$ is measured by φ_{CO_ave} during SSW measurements (=average of +/- flux for co-directional stage motions) to a few units ($\sim 5e-4 \rightarrow 5e-7 Vs$), which causes error in z_C around **0.5mm**.
- L_m is calculated from the warm measurements with rotating coil at LBL/BNL to within $\sim 2mm$. This should be the largest error source. If L_m is off by 10mm, the error in Z_c will be 1.5mm, so expect the L_m error to contribute **< 0.5mm**

Nominally, assuming magnetic lengths are similarly centered in mechanical lengths



For CM05, A15 is 1.5 mm closer to center, and A07b is 6.4 mm closer to center than the nominal 2.337 m

Mechanics were set as normal, but coils were not centered as usual within yokes – especially for A07b



LBNL found a shift toward the return end in MQXFA07b consistent with SSW measurement. Coil center was set to be in the structure center, but there were differences btw lead and return end in each coil causing an offset. Will be monitored more closely in future.

Alignment Relative to MQXFA15/MQXFA07b Average Center Line


Aug2024 - Initial Meas. - after Zcen repositioning

After adjustment of magnet supports in tooling, able to change separation by ~5 mm to be closer to normal and well within allowed range


MQXFA15 Lead End: X= 0.031, Y= 0.245 mm
 MQXFA15 Interface End: X= -0.031, Y= -0.245 mm
 MQXFA07b Interface End: X= 0.132, Y= -0.727 mm
 MQXFA07b Lead End: X= -0.132, Y= 0.727 mm

A15 roll angle = -0.41 mrad
 A07b roll angle = -0.07 mrad
 Delta angle = 0.33 mrad
 Ave angle = -0.24 mrad

A15 Z-dist A-stage to magnetic center = 3.5664 m
 A07b Z-dist B-stage to magnetic center = 3.5588 m
 Z-dist A15 to A07b = 4.7895 m (Lw=11.9147 m)




Vertical Offsets profile view




With final roll adjustment

But pitch of A07b seemed to change so that now slightly larger than 0.5 mm




Mechanical survey of fiducials indicates no significant change in position of magnet ends before and after axial adjustment



Alignment Relative to MQXFA07b/MQXFA15 Average Center Line
 13Aug2024 - Meas. check after repositioning and survey - stages swapped

**Horizontal Offsets
 plan view**




MQXFA07b Lead End: X= 0.241, Y= 0.752 mm
 MQXFA07b Interface End: X= -0.241, Y= -0.752 mm
 MQXFA15 Interface End: X= 0.040, Y= -0.101 mm
 MQXFA15 Lead End: X= -0.040, Y= 0.101 mm

A15 roll angle = -0.41 mrad
 A07b roll angle = -0.07 mrad
 Delta angle = 0.33 mrad
 Ave angle = -0.24 mrad

A15 Z-dist B-stage to magnetic center = 3.5525 m
 A07b Z-dist A-stage to magnetic center = 3.5728 m
 Z-dist A15 to A07b = 4.7894 m (Lw=11.9147 m)

Survey of mechanical position indicates that magnet positions did not change, But SSW persists in indicating the pitch change, even with the stages swapped. Will continue to monitor this...


**Vertical Offsets
 profile view**



Stages Swapped (A-stage at A07b leads) – still see A07b with pitch change

Feedcan adapter box (warm bore tube diameter ~44 mm)

Magnet assembly (warm bore tube diameter ~102 mm)






~18 m wire length



At 1.9K, SSW determination of magnet separation not presently accurate enough for cold measurements, at least partially because of more constrained wire motions at one end of the WBT

Ultimately, Z-center separation
measured at 1.9 K with rotating coil
outfitted with laser tracker targets



LQXFA01 Rotating Coil Summary at 16233A

Cryo-Assembly Magnet:	A04	A03
Integral <u>Gdl</u> (T):	559.95	559.70
Magnetic length (m):	4.213	4.216
Body field TF (T/m/kA):	8.187	8.178
Magnet center separation (m):	4.7721	

(Magnet separation measured by SSW during fabrication was 4.7892 m, expected shrinkage ~ 15mm, (observe ~17))

Summary

- SSW measurements are used extensively in fabrication and cold test to determine alignment parameters and integral strength
- Change in alignment when CM was placed on inspection table was observed and corrected starting with CM02
- Separation variance in CM05 was found and adjusted to be within normal range
- Final axial magnet separation at 1.9K determined with rotating coil. Warm to cold axial shift observed was ~17 mm.

Additional Slides

LQXFA01 Integrated harmonics

Nominal Current, 16233 A

