



FUTURE
CIRCULAR
COLLIDER



FCC-ee large scale project installation planning: challenges & proposals



S. Fleury | M. Benedikt | M. Bernardini | J.-P. Burnet | F. Valchokova-Georgieva

Outline

- FCC study presentation
- Layout and integration evolution
- Civil engineering input
- Equipment to install
- Sector sequence
- Overall planning output
- Overlook

The Future Circular Collider

Multi-stage collider inspired by LEP-LHC program



Courtesy of M. Benedikt

~ 2045 - 2060
90 – 365 GeV



~ 2070 - 2090
100 TeV

FCC-ee

FCC-hh




90.7 km with 8 surface points using existing CERN sites and infrastructures



The Future Circular Collider

- More precision and more energy to sharpen our knowledge and to push the frontier of unknown

Modern and future accelerators





Ref: V. Shiltsev and F. Zimmermann, Rev. Mod. Phys. 93, 015006, 2021.

- In 2020, the European strategy of particle physics (ESPP) on the long-term plan for particle colliders
 - An electro-positron factory is highest priority
 - Europe should investigate technical and financial feasibility of a future hadron colliders with energy of at least 100 TeV with an electron-positron Higgs and electroweak factory as a possible first stage



Milestones from FCC Mid-term review Nov. 2023



1st stage collider, FCC-ee: electron-positron collisions 90-360 GeV
Construction: 2033-2045 → Physics operation: 2048-2063

2nd stage collider, FCC-hh: proton-proton collisions at ≥ 100 TeV
Construction: 2058-2070 → Physics operation: ~ 2070-2095

Courtesy of F. Gianotti, FCC Week 2023

Main milestones

- Phase I: Conceptual design: end in 2018
- Phase II: Feasibility study from 2021-2025
→ *Mid-Term review end of 2023*
- European Strategy for Particle Physics end of 2027
- Project approval by CERN Council in 2028

Preparatory phase: 2026-2032

Civil engineering milestones

- Study and tendering prior to 2033
- Site preparation of civil engineering areas in 2032
- Start of civil engineering work in 2033




Start of operation

- Foreseen 2045-2048
- **Output date after analysis: 2046**


FCC-ee in 2018

First planning version in Phase I

- Horizontal configuration of booster and collider
- 12 shaft access points
- 97.75 km tunnel



FCC-ee planning for the Conceptual Design Report



FCC-ee evolution: new integration



- Phase II since 2023, new elements to consider:

- Reduced number of shaft (12 → 8)
- 90.7km tunnel: 8 sectors of ~11km
- New cross section: vertical configuration
- New equipment specific information

Impact on civil engineering schedule

Impact on installation


→ Update of the FCC-ee schedule for construction, installation and commissioning



F. Valchkova-Georgieva, J.-P. Corso, and K. Hanke, Challenges and solutions in the integration studies of the future circular collider


Working Baseline: Civil engineering strategy release

- Underground machine passing through multiple kinds of geology with 8 access shafts at different depth



Courtesy of T. Watson


- Civil engineering (CE): from site preparation to tunnel boring
 - 8 [shaft+sector]: released in non-sequential order (wrt ground and depth)
 - No access for installation, before the releasing from CE
 - CE activities start in 2032 (site preparation) and end in 2039-2041 (from first sector A-B to the last sector F-G)




FCC-ee equipment to install in the arc

Number of surface sites	8
Surface requirements	~40 ha
LSS@IP (PA, PD, PG, PJ)	1400 m
LSS@TECH (PB, PF, PH, PL)	2032 m
Arc length	9.6 km
Sum of arc lengths	76.9 km
Total length	90.7 km

Initial configuration,
as delivered by civil engineering




Final configuration



+ Safety equipment

Equipment to install: shaft and alcoves

5 small alcoves
2 big alcoves
per section




Smoke / He extraction
Ventilation & fresh air

Cable trays

Lift

Experimental shaft point A




Number of surface sites	8
Surface requirements	~40 ha
LSS@IP (PA, PD, PG, PJ)	1400 m
LSS@TECH (PB, PF, PH, PL)	2032 m
Arc length	9.6 km
Sum of arc lengths	76.9 m
Total length	90.7 km

Small alcoves with transport layby and safety refuge


Working Baseline: FCC-ee installation sequence




Working Baseline: FCC-ee installation sequence



Working Baseline: FCC-ee installation sequence



Working Baseline: FCC-ee installation sequence





Working Baseline: ventilation

Ventilation configuration set-up during installation (half-sector ventilation principle)

- Shafts release order
- Fire doors needed for final ventilation system, and installed at the end of the sequence

→ Final ventilation system configuration available only at the end of the installation works underground


Ventilation → Different operational stages



Working Baseline: safety


The final safety systems (fire doors and detectors) cannot be installed and commissioned at the first stages of installation → sensible to dust

Temporary safety equipment



Working baseline: inputs for schedule analysis

- Civil Engineering strategy release
- Safety requirements
- Machine layout
- Equipment to install and locations
- Groups requirement and sequence



FCC-ee schedule: Layout





← Machine layout

Temporary general services for Civil Engineering	Civil engineering works (TBM direction)	TI HWC	Technical infrastructure hardware commissioning
Shaft and sector released by Civil Engineering	Shaft works	Acc. HWC	Accelerator hardware commissioning
	Underground Technical infrastructure installation		
	Machine installation and direction of installation		
Construction and installation activities		Commissioning activities	


FCC-ee schedule: assumptions

- Bottom-up exercise:
 - The installation sequence for one sector was defined
 - It was used as base for each sector (including the shaft)
- Resource limitation:
 - Four teams in parallel maximum can work in the machine for the same type of activity
- Safety:
 - Maximum 200 persons at the same time underground




FCC-ee schedule: civil engineering

Civil engineering activities



FCC-ee schedule: installation strategy

Installation from the middle of each sector to the adjacent shafts
 → Shorter distance for transport and workers




Temporary general services for Civil Engineering	Shaft works	TI HWC	Technical infrastructure hardware commissioning
Shaft and sector released by Civil Engineering	Underground Technical infrastructure installation	Acc. HWC	Accelerator hardware commissioning
Civil engineering works (TBM direction)		Machine installation and direction of installation	
Construction and installation activities		Commissioning activities	

FCC-ee schedule: commissioning

Technical infrastructure hardware commissioning
→ 6 months

Whole accelerator hardware commissioning
→ 6 months for the overall machine




One sector accelerator hardware commissioning
→ 6 months

Temporary general services for Civil Engineering	Civil engineering works (TBM direction)	Technical infrastructure hardware commissioning
Shaft and sector released by Civil Engineering	Shaft works	Accelerator hardware commissioning
	Underground Technical infrastructure installation	
	Machine installation and direction of installation	
Construction and installation activities		Commissioning activities

FCC-ee schedule: resource limitation

Resources limitations assumption
(4 teams in parallel max.)




Temporary general services for Civil Engineering	Civil engineering works (TBM direction)	TI HWC Technical infrastructure hardware commissioning
Shaft and sector released by Civil Engineering	Shaft works	Acc. HWC Accelerator hardware commissioning
Underground Technical infrastructure installation		
Machine installation and direction of installation		
Construction and installation activities		Commissioning activities

FCC-ee schedule: resource limitation

Example: for Technical infrastructure installation there are up to 4 teams in parallel

Same applied to all main blocks of activity (shaft work, technical infrastructure installation and machine installation)




<ul style="list-style-type: none"> Temporary general services for Civil Engineering Shaft and sector released by Civil Engineering 	<ul style="list-style-type: none"> Civil Engineering works Shaft works Underground Technical infrastructure installation Machine installation 	<ul style="list-style-type: none"> TI HWC Acc. HWC 	<ul style="list-style-type: none"> Technical infrastructure hardware commissioning Accelerator hardware commissioning 	<ul style="list-style-type: none"> One Shaft-Sector ventilation Shaft to shaft ventilation Final system ventilation
Construction and Installation activities		Commissioning activities		Ventilation mode

FCC-ee schedule: resource limitation

Example: Team 1 in Sector A-B for Technical infrastructure installation will then go to Sector G-H

All the team will thus work on 2 sectors sequentially




Temporary general services for Civil Engineering	Civil engineering works (TBM direction)	TI HWC Technical infrastructure hardware commissioning
Shaft and sector released by Civil Engineering	Shaft works	Acc. HWC Accelerator hardware commissioning
	Underground Technical infrastructure installation	
	Machine installation and direction of installation	
Construction and installation activities		Commissioning activities

FCC-ee overall planning: resource limitation

Shortest duration from shaft availability to completion of sector HWC
 → 5.5 years

Longest duration from shaft availability to the completion of sector HWC
 → 6.25 years





Temporary general services for Civil Engineering	Civil engineering works (TBM direction)	TI HWC	Technical infrastructure hardware commissioning
Shaft and sector released by Civil Engineering	Shaft works	Acc. HWC	Accelerator hardware commissioning
	Underground Technical infrastructure installation		
	Machine installation and direction of installation		
Construction and installation activities		Commissioning activities	

FCC-ee schedule: readiness for operation

Installation of infrastructure and machine
+
Hardware commissioning of each sector
and of the overall machine

**Machine ready for operation in
October 2046**



Next steps

Since the FCC Mid-Term report in November 2023, the FCC study is being deeply scrutinized. Additional and more precise inputs should now be considered in the following areas:



Installation Schedule: update and modify it according to the last equipment specifications



WBS: create a coherent and integrated structure



Project Schedule: create a Master Schedule, defining the work packages and work units



Integration: finalize the Machine Layout considering the new needs for equipment and infrastructure



Civil Engineering: consider the readiness for civil engineering tendering process



FCC-hh: develop strategy for the installation



Thank you for listening !