## Laser beamlines for run 2c/d

Eduardo Granados (SY-STI)

On behalf of the LP section





## Requirements for AWAKE Run 2 laser beamlines

•

Run 1

- Laser beam line to plasma cell 1
  - $-\lambda = 780 \text{ nm}$  (depending on oscillator)
  - t pulse = 100-120 fs
  - E > 200 mJ (unless new laser amplifier)
  - (Reflective telescope after compressor)
  - Beam delivery
- Laser beam line to electron gun 1
  - $-\lambda \sim 267 \text{ nm}$
  - t pulse = 0.2-10 ps
  - E ~ 0.5 uJ
  - (Beam delivery via image relay)
  - Synchronization based on IR laser
  - Spot size and fluence control
- Diagnostic beam line(s)
  - $\lambda = 780 \& 260 \text{ nm}$ : imaging, energy, timing.

- Laser beam line to plasma cell 2
  - $-\lambda = 780$  nm (depending on oscillator)
  - t pulse = 100-120 fs
  - E > 200 mJ (unless new laser amplifier)
  - (Reflective telescope after compressor)
  - Relay imaging beam delivery
  - Variable delay after split point.
- Laser beam line to electron gun 2
  - $-\lambda \sim 260-267 \text{ nm}$
  - t pulse = 0.2-10 ps
  - E ~ 20 uJ
  - (Delivery via image relay)
  - **Synchronization** depending on laser source
  - Spot size and fluence control
- Diagnostic beam line(s)
  - Synchronization and overlap counter-propagating IR beams with p+ beam



Run 2 c/d

#### Laser beamline concept for run 2 c/d





#### IR beamlines for plasma cells



#### IR beamlines for plasma cells



Relay imaging systems require only low-level primary vacuum, blue mirrors are "in air"

- Stretched pulse
- Compressed pulse
- --- Mirror leak

- Focusing on plasma cell attained by mismatching beam expanders
- Content of diagnostics sets still to be determined, location of safety devices, etc...

#### **IR** beamlines diagnostics

Diagnostics pre-PC1 and pre-PC2 "Beam conditioning section"

Parameter	Diagnostic	Control
Pulse energy	Energy meter (leak / real beam)	TBD
Beam position	Virtual camera (BI?)	Motorized mirrors (stepper or picomotor)
Timing (arm 1)	Spatiotemporal overlap diagnostics table	Delay stage
Beam size	Virtual and real imaging (BI?)	Beam expander
Pulse duration	Auto-correlator	Motorized compressor

Diagnostics spatiotemporal overlap (mostly TBD) "Beam matching section"

Parameter	Diagnostic	Control
Relative beam positions	CCD camera (BI?)	Motorized mirror (stepper motor)
Timing	X-correlator / fast PD	Delay stage
Beam sizes	CCD camera (BI?)	Beam expander





#### UV beamlines for RF guns



#### A dedicated UV laser in TSG4



### UV beamlines for RF guns – controls and diagnostics



Parameter	Diagnostic	Control
Pulse energy (IR+UV)	Samplers + energy meters	Motorized waveplates
Beam positioning	Leakage cameras	Motorized mirrors (picomotor)

Parameter	Diagnostic	Control						
Pulse energy	Sampler + energy meter	Motorized filterwheel						
Beam position	Virtual cathode camera	Motorized mirror (stepper motor)						
Timing	Sampler + photodiode	Delay stage						
Beam size	Virtual cathode camera	Motorized iris						
UV pulse duration	X-correlator / streak camera	Motorized compressor or UV stretcher						



#### New photoinjector already operative at CTF2





#### **Open questions**

#### IR beams

- Timing resolution required for synchronization -> Development of specific optical/electronic diagnostics
- 2<sup>nd</sup> Compressor vessel design -> size, location
- Pulse energy required in each cell? -> May not need reflective telescopes?
- 2<sup>nd</sup> cell may be compatible with non-diffractive beam shaping optical elements.
- Relays with compressed or stretched pulses? Location of the compressor(s)

#### UV beams

- Preferable option is to use a separate laser (as in CTF2) due to:
  - Synchronization with ionizing laser without additional delay lines (~ 80 m extra)
  - Location of compressors and harmonic stages (laser lab, near gun?) -> better pointing stability
  - Higher energy of UV pulse, copper cathode capability
  - Possibility to produce electron beams independently of the main laser status
- Pulse duration tunability capabilities, ranges? Variable compressor/stretcher? Different pulse durations for each e- gun? CTF2 tests will help answering these questions
- Photocathode material for fs gun -> emmitance and charge requirements -> UV energy needs.
- Pulse shaping in transverse/longitudinal capabilities?



#### Design work, integration, production, commissioning...

- Design office EN/MME
  - IR and UV beamline elements and systems with Nicolas Chritin
- Vacuum TE/VSC
  - IR and UV transfer systems (Chiara Pasquino) with Jose
- Access system EN/AA
  - Input from Vitor to the integration WP is available (?)
  - Laser PPS by Miriam Munoz Codoceo
- Equipment control BE/CEM
  - Coordinate with Odd Andreassen and Mario De Castro, foreseen to hire a QUEST and PJAS
- Overall Integration EN/ACE
  - To coordinate with Frederick Galeazzi
- Cooling for new UV laser and laser cabin ventilation EN/CV
- Timing/synchronization and RF gun SY/RF
  - To coordinate with Ben Wooley for RF locking systems
  - To coordinate with Steffen Doebert for photocathode needs
- Diagnostics integration / handshaking SY/BI
  - To be discussed with BI CP Stefano Mazzoni
- Cabling requests to be detailed (and new racks) EN/EL
- New UV laser room construction BE/EA (Vincent Clerc)



## Schedule of activities and spending profile

	2024	2025	2026	2027	2028	Task	20	024	202	25	2026	6	202	27	202	28	20	29	203	0 T	otal
	Q1 Q2 Q3 Q4	Q1 Q2 Q3 Q4	Q1 Q2 Q3 Q4	Q1 Q2 Q3 Q	4 Q1 Q2 Q3 Q4		Q1 Q2	2 Q3 Q4	Q1 Q2	Q3 Q4	Q1 Q2 Q	3 Q4	Q1 Q2 0	Q3 Q4	Q1 Q2	Q3 Q4	Q1 Q2	Q3 Q4 Q	1 Q2 (	23 Q4	
AWAKE run 2 steps	EYETS	inj LS3		YET	YET	Design work and jobs															
2.)		•		1		Optical design of IR and UV beams		20	75	5											95
za) operation (e-seeded self-modulation)	-					Opto-mechanical design main components		10	20	)											30
2b1) installation step density plasma cell	30	months of AV	VAKE not taki	ing <u>proton</u> :		IR/UV standard boxes			40	)	20									$\rightarrow$	60
2b2) operation (density step)						IR/UV standard piping vacuum	$\left  \right $			50	200	)	50	0	20	0				_	750
2c1) dismantle AWAKE configuration 2b													30								100
2c2) dismantle CNGS, install basic services						Procurement of main components															
2-2) install consists as black & aminor ant				L		Pulse compressor			25	0											250
2c3) Install services, cables & equipment						UV laser															
2c4) HW commissioning run 2c						Optical elements		20	20	)	20		20	)							80
2c5) commissioning wheam and operation	-		$\rightarrow$			Optomechanical components		20	10	)	10		10	)							50
,	18 months	for CNGS dim	antling proje	et 🗆		Diagnostics and instrumentation				20	50		50	)	4(	)			+	$\rightarrow$	160
						Motorization and controls				40	40		50	)	50	)					180
						Optical tables				_			60			$\downarrow$				++	60
LASER BEAM LINES																					
Suport for Run 2 a-b																					
Design of IR and UV beam transfer optics						UV laser room (electricity, water, ventilation)								200		+				++	200
Development of IR beams diagnostics	_					Safety systems								40							40
	-					Control Systems					100	,	1	00		80					280
Design of mechanical structures						RF locking systems							40	)					++		40
Dismantling beam lines																					
Procurement of pulse compressor																					2475
Manufacturing of beam elements (workshop)						Materials		40	34	0	120	)	19	0	90	2	5	0	50		
Procurement of optics and standard items						Jobs	:	30	18	5	270	)	35	0	20	0					
Control tools development (SW and HW)						Personnel					100	)	10	0	80	)					
HW Installation						Fellows STI-LP	<u> </u>	0	15	0   5	150		15	0	50	)	5	) ທ	50		2795
						oum por year (estimate)			0/		040		75	•	42			•	100		2733
Commissioning																					
Operation						МТР	3	86	56	5	580		54	5	20	5	14	8	94		2523





# Thank you for your attention!

