Status and plan of testbeam line at KEK

Yuji Enari, IPNS-KEK




Electron test beam from PF-AR



Electron in AR ring

βx = 20.6 [m], εx = 290 [nmrad]beam size $1σ_x = 2.4 [mm] 1σ_y = 0.1 [mm]$

60mA~4.7×10¹¹ electrons (whole) 5σ 3σ 5.4σ 2.5×10⁹ electrons/sec @5.4σ



- Photon emission by wire target (Graphene)
- Inject photon to a converter (16 mm Cupper plate) to make pair creation.
- Transfer electron with Di-pole and Quadra-pole magnets to the test stage.

How does it look like?



Counting room




Sensor Stage





Trigger counters


Use cases…












Test beam rate and profile




Rate:

Overall rate is 2~2.5 kHz Highest rate ~ 3 GeV.



Recently we optimize Q-magnet New: after optimization. $\Delta p/p \sim 10\%$.




Beam profile in beam axis direction



Beam width in sigma (gaussian fit) in beam axis direction Z=0 is at the edge of the last quadrupole magnet.

Momentum and AR operation Beam energy	Direction	Z = 0.65 m	Z= 1.50 m	Z=2.50 m
3 GeV @ AR 6,5 GeV	Horizontal	10.0 mm	12.9 mm	14.8 mm
3 GeV @ AR 5.0 GeV	Horizontal	10.2 mm	12.8 mm	
3 GeV @ AR 6,5 GeV	Vertical	8.9 mm	7.1 mm	5.2 mm
3 GeV @ AR 5.0 GeV	Vertical;	8.9 mm	7.0 mm	

ITDC TBL p=3 GeV (AR 6.5 GeV)



To have higher rate




- Position of Quadrupole magnets can be improved.
- Set them upper stream side.
 - Move one of QF just after Dipole magnet
 - Move forward rest of Quadrupoles by 1 m.
 - → The rate increased by 1.9 momentum spread: $2.8\% \rightarrow 3.4\%$.

Plan to proceed this modification

in Summer 2025

6 m



Concrete shield


Beam Time in 2025



- Beam time for electron test beam line:
 - 2025 Mar 03 ~ Mar 24
 - 2025 May 13 ~ July 07
 - 2025 Oct 14 ~ Dec 26
- Beam time for a group is typically 1 week
 - Wed 17:00 ~ Wed 9:00.
 - Often Wednesday is machine time.
 - PF-AR is operating with top-up mode
 - No down time for injection.
- If you would like to use the beam, let me know. (yuji.enari@cern.ch)
 - https://itdc.kek.jp/en/testBeamLine/index.html
 - https://www2.kek.jp/uskek/eng/apply/ar_tbl_eng.html

A plan for a hadron test beam in J-PARC






J-PARC Hadron experimental hall @ KEK Tokai campus

J-PARC Hadron experimental hall






- 30GeV protons are injected to gold target
- Using secondary particles
 - Max beam intensity: 115kW (4.2s cycle)
 - Record of beam intensity: 65kW
 - target: Gold 66mm thickness
- There is high momentum line

Name	Species	Mom./Energy	Intensity
K1.8	π [±] , K [±]	< 2.0 GeV/c	~10 ⁵ Hz for K ⁺
K1.8BR	π [±] , K [±]	< 1.0 GeV/c	$\sim 10^4$ Hz for K ⁺
KL	K_L	2.0 GeV/c (Ave.)	$\sim 10^7 Hz for K^0$
High-p	Proton	30 GeV	~10 ¹⁰ Hz
COMET	Proton	8 GeV	6.2x10 ¹² /shot*


*Phase 1

A plan for a Hadron Test beam line






現状の実験エリア




Modify this area as the plan on right side



Magnets are reserved!





Dipole magnet



Need to buy the power supply (400kW)



Two quadrupole magnets




2 x 50kW




Expected rate at the hadron TBL


Simulated by MARS


- Take into account for Target system and transfer hole
- Total rate is roughly consistent with simple measurement
 - With Ion chamber including low ET photon and electron.
- Expected charged pion rate
 - The bin of 0.9-1.0 GeV: 120 k / spill.
 - 1 spill ~ 4 sec
 - Need to confirm by measurement!





D電磁石on (-1.0 GeV/c)





Setup for the rate measurement



Need to reject photon, electron and proton!

reflective index: 1.045
60 mm x 160mm x 160mm
read out by four HPK H1161


Trigger counter
Scintillator + PMT
Three sets

Lead plate
Thickness of 1.5 cm $\sim 2 X_0$

Scintillator pad + MPPC pad size: 1 cm x 16 cm 16 ch for x and y.

Total 32 channel


Magnet to wipe out electrons reuse of KEKB Steering magnet Upto 0.03 T@ 5 A




Magnetic field (T)

Status of each component and plan










Sum of ADC of Four PMTs with Aerogel



- Install the setup next week.
- Waiting for the beam.
- Scheduled from 2025 Jan 17th

Summary




- The PF-AR electron test beam line
 - Stably running as scheduled.
 - Plan to make modification on magnet configuration next Summer
 - Rate will be increased by a factor of 1.9
 - Next year schedule: Mar, May-July, Oct-Dec
 - To request beam time, please contact YE (yuji.enari@cern.ch).
- Plan for a Hadron test beam line
 - KEK J-PARC hadron hall
 - Up to 2 GeV
 - Beam rate measurement will be performed early next year.

Plan of the hadron test beam line




改造後のテストビームエリア (π1.0)



生成標的から / (Q1入口まで14m)

- Dipole and quadrapole configuration
 - Length of beam line 22.4 m
 - Momentum selection
 - Full open slit: $Dp/0 \pm 5\%$, beam width: ± 15 cm
 - Slit with 1 cm 'Dp/p \pm 0.5%, beam width \pm 2cm




Last measurement on the particle rate



- Target monitor:
 - 1cm × 1cm × 2mm scintillator + PMT
 - 3 hold considnece
 - $5.34 \times 10^{-7} sr$
 - 90-100 k/spill (2024.6, 82 kW, 4.2 s cycle)
- Ion chamber installed in 2019.
 - 15 cm × 15 cm
 - 22M/spill (50.5kW, 5.2 s cycle)






Materials for PF-AR TBL

TBL control and monitoring




- Magnets currents can be changed with script.
 - User can change.
- Shutter is hard switch with interrock.
- Graphana is set up for monitoring



KEK accelerators and PF-AR ring





Tools at TBL



- Trigger, beam clock, veto signals
 - NIM level signals can be provided
 - Injection period may need to be vetoed.
 - NIM create, basic modules, oscilloscope are available.
- Tele-scope is not available
 - May be able to organize to set it up
- There is no common DAQ, no dedicated PCs.
 - User needs to prepare.
- Cooling / any specific infrastructure
 - Need to prepare by user.
- Room for preparation can be provided.
 - In another building (2 min on foot).





Cherenkov light emission on Aerogel



• β and momentum

