

An aerial photograph of a large circular facility, likely a particle accelerator, with a dashed white line tracing its perimeter. Overlaid on the image are several technical diagrams: a cyan wavy line representing a cryomodule layout, a white circle on the left, and a white dashed line forming a smaller circle. The background shows a dark, textured landscape with a body of water on the left.

FCCee cryomodules

V.Parma, SY-RF


On behalf of the FCC SRF team

SY-FCC workshop


CERN, 04 October 2024

RF configuration at PH (ttbar)

Klystron gallery




Beam tunnel



- 400 MHz: 66 cryomodules (264 cavities) --
- 800 MHz: 102 cryomodules (408 cavities) --
- + Booster (800 MHz): 124 CM at point L

-- 292 cryomodules $\rightarrow \approx 3$ x LEP RF system !! --

RF system layout - Baseline




- Physics schedule – number and type of cryomodules to be installed:
- 400MHz single-cell (Nb/Cu): 28 CM @4.5K, removed after the Z working point
- 400MHz two-cell (Nb/Cu): 66 CM @4.5K
- 800MHz five-cell (bulk Nb): 272 CM @2K, 122 CM for the collider and 150 CM for the booster.


Courtesy F. Peauger

Material	λ (nm)	ξ (nm)	κ	T_c (K)	H_{c1} (T)	H_c (T)	H_{sh} (T)
Nb	40	27	1.5	9	0.13	0.21	0.25
Nb ₃ Sn	111	4.2	26.4	18	0.042	0.5	0.42


4.5 K



400 MHz cavity



or



Baseline option: advanced fabrication technics, advanced coating (HiPIMS) & advanced surface preparation recipes

Alternative option to improve the accelerating gradient E_{acc} and the Q_0 factor


2 K (\rightarrow 4.5 K?)



800 MHz cavity



or




Baseline option: special surface processing (doping) to improve the Q_0 factor


Alternative option cavities to operate at 4.5 K instead of 2 K

400 MHz CM conceptual and integration studies

400 MHz in collider
(5.5 m tunnel)




- 400 MHz CM (based on LHC) for W to ttbar (also Z? >> FPC and HOM power extraction)
- Prototype to be built at CERN (under SRF-D project)



66 units

Cryogenic schemes




K. Canderan, SY-RF

beam height in RF points : 1200mm > 980mm beam height in the arcs
 → can be matched with ~ 0.15% tunnel slope in separation/recombination zones (150m long)


800 MHz CM conceptual and integration studies

800 MHz CM (based on PIP II at FNAL).

800 MHz booster
(5.5 m tunnel)



226 units
(over 10 yrs)




✓ Some integration issue still to be tackled (ceiling height, robot space reservation to be reviewed)



✓ MOU CERN/FNAL in preparation:

- 800 MHz CM prototype by FNAL by about 2031
- In view of a potential significant US contribution to FCC

Longitudinal integration study




- Collider SRF system **length** at the ttbar is **marginally exceeding** allocated length in PtH (2x1015m)
- Optimising for **more compact SRF configurations (6-cell 800 MHz cavity, RF and mechanical design)**




SRF R&D-D

A new project. What is it about ?


Build 400 MHz Demo, an FCC 2-cell cavity full size cryomodule




Items to be designed, built and qualified (non exhaustive list!)




Cavity Nb sputtered



He tank (LHC design shown)/cavity assy



FPC (new!), with WG windows



HOMs, RF extraction lines (LHC/Crab designs shown)

Parameter	Value	Remarks
No. cryomodules	66	
2-cell cavities per cryomodule	4	
CM length (GV flange to flange)	~ 11 m	
Cavity gradient Eacc (MV/m)	12 / 10.6	CM test / CM in accelerator
Q ₀	3.0E+09 / 2.7E+09	CM test / CM in accelerator
Dyn. HL (CW)/cavity at 4.5 K	129 W	(Z?) W, H, ttbar
Stat. HL/CM	197 W	Includes 50% margin (design maturity)
Environ. Magnetic field	≤ 5 mG	Shielding needs TBD
Max FPC power/cavity (kW, CW) (Z)/ W / H / ttbar	(894)/ 374 /378/78	FPC type/assembly TBD (WG with windows?)
FPC orientation/WG connection	Vertical/Top	accessible from CM top
Q _{ext} W / H / ttbar	9.2E+05/9.1E+05 /4.5E+06	Fixed antenna, adjustable on wave guide
HOM power per CM: (Z?)/ W / H / ttbar	(~45 kW)/~15 kW/ ~6 kW/ ~3 kW	HOM hook-type and coax.extract.

Lots of resemblances to LHC CM, but **final designs may be considerably different !**

Master schedule for 400 MHz CM demo

Work in progress

Task/milestone	2024	2025	2026	2027	2028	2029	2030	2031
SA18 facility operational						★		
HTC operational in SM18 (TBD)			★					
400 MHz CM Demo (2-cell) ready for testing (TBD)								★
Horizontal Test Cryostat (HTC) in M9	Design	Construction	inst.+test					
400 MHz CM Demo (2-cell)								
Cryomodule Design	Conceptual Design		Detailed Design					
Cryomodule manufacture				Construction				
Assembly (in SA18)						Assembly		
2-cell cavities (x4) tested								
RF design								
Mech. Design								
Manufacture								
Coating								
Bare vertical testing								
FPC (x4) & HOMs (x12) tested								
RF design								
Mech. Design								
Manufacture								
Conditioning & warm testing								
Helium tanks/tuning system (x4) ready								
Mech. Design								
Manufacture								
Dressed cavities/FPC/HOM assemblies (x4) ready								
Assembly								
Vertical testing of dressed cavity with HOMs								
HTC testing with FPC and tuning system								

duration ?

duration ?

duration ?

→

★

★

★


↓

↓



↑



Roadmap towards the Z




SA18 Layout



CM Assy Lines 1&2

Main Hall
ISO 8 Cleanroom

Access



EN-MME, TE-VSC/CRG, SY-RF, a major ATS endeavor !

Summary

- Conceptual design of CM 400 MHz and 800 MHz well advanced
- Tunnel integration studies in progress
- 5.5 m tunnel cross-section integration tight but feasible but with higher beam height than the arcs:
 - ✓ Proposed matching the arcs beam height with a slight tunnel slope
 - ✓ Some integration issues can be easily tackled
- Finalize integration study by end of 2024
- Design and build 400 MHz CM Demo (at CERN) and 800 MHz CM prototype (FNAL collaboration?)
- 400 MHz Demo, a big endeavor across ATS sector (project being set up, recruitment of new staff started)


Thank you ! Questions ?

Backup slides

TLSS length: 2032 m


Z machine

(0.24 GV, 100 MW)



W machine

(2.1 GV, 100 MW)




H machine

(4.2 GV, 100 MW)




ttbar machine

(22.6 GV, 100 MW)



TOTAL RF LENGTH: 1950,2 m



TLSS length: 2032 m


Z machine

(0.14 GV, 5 MW)



W machine

(1.05 GV, 5 MW)




H machine

(2.1 GV, 5 MW)



ttbar machine


(11.3 GV, 5 MW)



Midpoint

RF section

TOTAL RF LENGTH: 1335.3m



Inside the 400 MHz CM

