

### Overview

- Required SRF performance for FCC-ee
- Status, issues, and next steps on the roadmap for Nb/Cu
  - 1.3 GHz R&D program
  - 400 MHz
- Sustainable+ alternatives for 800 MHz: Nb/Cu at 2 K and Nb<sub>3</sub>Sn/Cu at 4.5 K

### FCC machine specs (surface resistance and peak fields)

Quantity	Booster (800 MHz)	Z (400 MHz, 4K)	W(400 MHz, 4K)	H( 400 MHz, 4K)	ttb (800 MHz, 2K)
$Q_{o}$	3 10 <sup>10</sup>	2.7 10 <sup>9</sup>	2.7 10 <sup>9</sup>	2.7 10 <sup>9</sup>	3 10 <sup>10</sup>
$E_a(MV/m)$	6.2→ 20.1	3.77	10.1	10.6	20.1
$R_s$ (av n $\Omega$ )	9.1	89	87	87	9.1
<b>B</b> <sub>peak</sub> (mT)	87.2	20.2	54	56.4	87.3
$E_{peak}(MV/m)$	41.2	8.3	20.2	21.2	41.3

NB: 4K and 2K are indicative

- Compared with state of the art for bulk Nb and Nb/Cu,
  - B<sub>peak</sub> < 100 mT (no HFQS) in all cases (120 mT demonstrated in Nb/Cu)</li>
  - E<sub>peak</sub> is quite relaxed
- We don't need ultra high fields, except maybe for the booster of the ttb
- Rs is challenging
- 800 MHz with Nb/Cu is not excluded and should be tried
- Challenge staged in time for the collider, booster is pulsed (Q may be relaxed?)

## Required performance gains in time for series production

Z (2033)

W, H (2038)

ttbar (2041)

#### 400 MHz:

2xLHC gradient @ 35% -50% lower surface resistance: @ Q=2.7x10<sup>9</sup>

2027?!

Collaborations with JLAB, INFN, KEK, ....

Collaborations with Cornell, FNAL, JLAB, IJCLAB, ...

800 MHz:

6.5 MV/m @ Q=3x10<sup>10</sup> (2 K)

Bulk Nb

21 MV/m @ Q=3x10<sup>10</sup> (2 K)


**Bulk Nb** 

Nb/Cu?


21 MV/m @ Q=3x10<sup>10</sup> (2 K)

Bulk Nb Nb/Cu? A15?

### State of the Nb/Cu 1.3 GHz program





At 4,2 K: Reproducible BCS parameters Optimised BCS resistance around 300  $n\Omega$  Scaled FCC ee target already met!




At 2 K: BCS resistance is suppressed but.. Erratic residual resistance (7-90 n $\Omega$ ) Scaled FCC ee target seems possible

## Our challenge: understand and control $R_s(H)$ : Nb thin films








### Progress on control of thermal currents



Comparing our measurement data, we noticed KEK is able to reach much better thermal gradients across Tc....



### Cavity manufacturing highlights

400 MHz Monoblock prototype

Successful 1.3 GHz hydroforming (KEK Collaboration)











### State of the art: 400 MHz (LHC geometry)





# Status and next steps for 400 MHz Nb/Cu single cell

- The cavity measured in 2023 implemented only one of the lessons learned in the 1.3 GHz program, i.e. HIPIMS. Seamless substrate and EP not yet done.
- Two 400 MHz cells machined from bulk have been produced, cut off welding is planned in October
- Toy cavity with beam ports was completed in May 2024, for EP and HIPIMS tests
- A dedicated cold test facility was commissioned in July and is operational (mitigate clash with HL-LHC). Include magnetic compensation and will integrate control of thermal currents
- In 2024 we have been delayed by EP in bldg. 118. The infrastructure is there but process not yet optimized, crab cavities have taken more slots
- Process optimization still on simplified cavity
- Next cavity test scheduled end of 2024, aiming at (seamless) EP+HIPIMS



### Status of the FCC 2-cell


RF design is basically done.

A simplified sketch with key dimensions has been provided to EN-MME and TE-VSC to allow first evaluations on mechanical design, surface treatments and coating systems.

#### Present issues:

- 1) Inter cell iris diameter significantly less then cutoff makes <a href="hydroforming not trivial">hydroforming not trivial</a>. MME looking at possible solutions
- 2) Unclear if EP is possible with the present infrastructure in bldg. 118, (will be OK in the new SRF building). VSC looking into possible solutions.

Prototype needed by 2027!



## Nb<sub>3</sub>Sn on copper


- Motivation
  - Operation at 4 K saving capital cost
  - Breakeven  $Q_0$  for plug power: 7.5  $10^9$  at 4K ( $\sim$  3  $10^{10}$  at 2 K)
  - Potential to drastically reduce plug power
- Good progress with flat samples, huge challenge: scale the process to a real cavity!
- Clear decision at 2024 CERN SRF workshop to focus on 800 MHz.
- Issues:
  - High temperature (700°C) coating system avoiding cavity collapse
  - Multiple cathodes
  - Mechanical design of the cavity
  - Conduction cooling for 4.5 K operation
- Ongoing definition of milestones
  - Flat sample performance target (4 K/2K breakeven point)
  - Cavity design
  - Coating system design
  - Cold test bench (must have for 800 MHz ayway)



70
60  $\mathbb{C}$  50  $\mathbb{C}$  40  $\mathbb{C}$  40  $\mathbb{C}$  50  $\mathbb{C}$  50  $\mathbb{C}$  60  $\mathbb{C}$  60  $\mathbb{C}$  7 =4.5 K Linear, fit:  $\mathbb{R}_s = 34.6 + 1.08_{pk}$  7 =2.5 K Linear, fit:  $\mathbb{R}_s = 25.1 + 0.38_{pk}$  10  $\mathbb{C}$  60  $\mathbb{C}$  30  $\mathbb{C}$  30

QPR sample

Best Nb3/Cu (HIPIMS)



Coating system concept with needed functionalities

### Summary

- Change of baseline would bring forward by  $\sim 10$  years the goal of 2-cell 400 MHz Nb/Cu working at 10 MV/m and  $Q_0 \sim 3~10^9$ .
- So far, we proved that this is possible with Nb/Cu
- 1.3 GHz program takeaways: seamless substrates, EP, HIPIMS coatings, control of thermoelectric currents, magnetic hygiene, cleanliness chain (infrastructure).
- Performance gains at 400 MHz probed on LHC geometry, with slow pace so far.
- Some bottlenecks (substrate, test facility) have been removed and we expect to speed up in 2024-2026.
- New SRF building coming online in 2029
- 2-cells: mechanical design only starting now. Prototype by end 2027 is <u>very very tight</u>. If done, it may not integrate all the improvements we have identified
- 800 MHz baseline with bulk Nb and some of the available "recipes" is relatively straightforward, this part is the subject of collaborations with other labs (FNAL, JLAB, IJLC)
- Alternatives (more sustainable) i.e. Nb/Cu and Nb<sub>3</sub>Sn/Cu are so far pursued in the context of the SRF R&D program. Detailed plan and costing under discussion with EN MME and TE VSC.

### SPARE SLIDES


22-Aug-24	Bare cavity in vertical test		Equipped cavity (with HOM couplers) in vertical test		Cryomodule (with FPC) in horizontal test		Operation in the machine	
	Eacc (MV/m)	Q0	Eacc (MV/m)	Q0	Eacc (MV/m)	Q0	Eacc (MV/m)	Q0
2-cell 400 MHz	13.0	3.3E+09	12.4	3.15E+09	11.8	3.0E+09	10.6	2.7E+09
6-cell 800 MHz	24.8	3.8E+10	23.6	3.65E+10	22.5	3.5E+10	20.25	3.0E+10
							Eliza .	

+5%

+5%

-10%

### SM18 Cryogenic capabilities – situation in 2023




How can we optimize the cryogenic consumption and benefit from available helium in transitory periods?

### Upgrades of RF cold testing facility



### Vertical inserts



⇒ This will allow to have a stock of prepared cavities "ready to be tested"



New V4bis insert and preparation area