

Network tests at CZ Tier-2

Jiří Chudoba, P. Vokáč, L. Míča, A. Mikula, M. Svatoš, P. Šesták, J.
Uhlířová,



Fyzikální ústav
Akademie věd
České republiky

Hepix Fall 2024 workshop, Nov 7 2024

FZU Computing Center

- Distributed resources with all central services and most of hardware at FZU
- Several clusters under one HTCondor LRMS: **10480** jobslots
 - 144 kHS06, avg: 13.8 HS06/core
 - 2500 jobslots at MFF UK, 29 kHS06
- Two clusters with Slurm for local users only, 52 servers, **2500** cores
- Clusters connected to national grid Metacentrum
 - 48 servers, **3072** cores, 6x GPU A40
 - 23 servers, 23×1.5 TB RAM, $48 \times 2 \times 23 = 2208$ cores
- Storage
 - 6.5 PiB under dCache
 - 3.69 PB xrootd (only ALICE), 4 servers at NPI Řež




Fully used local grid resources

- National e-infrastructure e-INFRA.cz
 - Common project of 3 united large research infrastructures
 - CERIT-SC, CESNET, IT4I
 - IT4I: National Supercomputing Center
 - CESNET EGI Grid site – auger, belle2
 - Data Storage department of CESNET




Network 2023




Excellent external connection thanks to CESNET

DC24



90 days before and during DC24, bin – 1 h
peaks at 3 Tb/s


DC24




2. week, den
5 min binning

CZ: 77,7 Gbps

DC24




bits




packets

LHCONE



PASNET


DC24



CZ
(in 4.5 days)

in: 2,5 PB
out: 2,1 PB


Network since 06.2024




Custom network test

- curl command for parallel uploads/downloads
- running on 15 disknodes at FZU
- all transfers to/from CERN EOS ATLAS
- 2 upload tests (to CERN)
 - 300 parallel transfers (15x disknode x 20 transfers), 10GB files – 102 Gbps hourly avg
 - 600 parallel transfers (15x disknode x 40 transfers), 10GB files – 159 Gbps hourly avg
- 2 download tests
 - 300 parallel transfers (15x disknode x 20 transfers), 10GB files – 136 Gbps hourly avg
 - 600 parallel transfers (15x disknode x 40 transfers), 10GB files – 167 Gbps hourly avg

Test 07.2024



Tests - July 2024



Summary and Outlook

- Excellent network connection even improved since the last year to 200 (LHCONE) + 100 (internet) Gbps
- New router with 400 Gbps ports just arrived
- More tests in when new connection is set up (Q1 2025)
 - more automatic?
 - via FTS?

We greatly appreciate network, computing and storage resources provided by e-INFRA.cz project

**This presentation is supported by MEYS project LM2023061
(FERMILAB-CZ)**