

A watercolor illustration of a Gothic cathedral with a tall spire. A bright yellow comet with a long tail streaks across the sky above the cathedral.

# XXXI Cracow EPIPHANY Conference

on the recent LHC results

13-17 January 2025

## Overview of the LHC performance in Run 3

- Major LHC events and performance in 2023 and 2024
- Prospects for 2025 & 2026
- Status of HL-LHC preparation



Reyes Alemany Fernandez, CERN

Beams department – Accelerator and Beam Physics group

# LHC in 2023

21.04.2023

1<sup>st</sup> stable beam of 2023



~4 days downtime

25.05.2023

RF finger module issue.

**Intensity limited to  $1.6 \times 10^{11}$  p+/b**




31.08.2023 (B)  
08.09.2023 (A)

2 x injection protection device (TDIS) vacuum leak.

**Stop p+ operation!**

End Sep – Early Oct ALICE background issue followed by studies and solution




Mar-Apr

May

Jun-Jul

Aug-Sep

Oct-Nov



12.05.2023


1<sup>st</sup> collisions  
2374 bunches




17.07.2023

Fallen tree in VD causing power glitch, magnet quench, and leaking bellow between cold mass and insulation vacuum

**~50 days of downtime**



26.09.2023:  
1<sup>st</sup> stable Pb ion beam




October

Beam loss induced SEU causing trips, quenches, etc. Studies, Lumi levelling




# LHC RF Finger Module Issue

25.05.2023



Visual inspection → annealed/plasticized spring on the 212 mm vacuum module due to localized temperature increase to more than 500°C





- ~ 4 days of downtime for repair
- Total number of modules present in LHC = 1819
- Inspections in 2023 of 212 mm type revealed 8 degraded modules
- Full replacement in 2023 not possible
- Replacement strategy staged in YETS23-24 (47/71) and YETS24-25

Mitigation for 2023 & 2024:  
Bunch intensity limited to  $1.6 \cdot 10^{11}$  p+  
Bunch length kept above 1.2 ns

# LHC Inner Triplet (IT) Bellow Leak

17.07.2023



- Magnet Quench due to electrical perturbation
  - 'Normal' high pressures in the He lines during the magnet quench created a small hole (1 mm<sup>2</sup>) in an edge welded bellow (non-conform) with major consequences (vacuum vessel pressure degraded and below repair)
- Quick repair in-situ with partial cryogenic warm-up
- **~50 days of downtime**
- **Similar events possible** on triplets and mainly in Q1-Q2 interconnection **until LS3**
- Inspection not possible without warm-up
- But warm-up poses a significant risk due to a thermal cycle of irradiated triplets


Consolidation of IP2 and IP8 IT proposed in LS3  
(IP1 and IP5 replaced by HL-LHC upgrade)



# LHC TDIS (Target Dump Injection Segment)

- Machine protection devices used during injection – regularly moving in and out
  - Located in front of IP2 (ALICE) for beam 1 and IP8 (LHCb) for beam 2
  - Each TDIS contains 3 modules with 12 edge welded bellows per TDIS
- Two leaks appeared on separate bellows of the same TDIS (IP8) within 1 week
  - Both varnished and blocked in out position
- Root cause: misspecification of the bellow, causing wear-out after 2-3 years
- Intensity per injection severely limited  
 ➔ **End of high-intensity p+ physics**  
 Ion run extended  
 p-p reference run moved to 2024

**31.08.2023 (B)**  
**08.09.2023 (A)**



### Mitigation:

- Both TDIS replaced by (non-conform) spares during YETS23-24 (expected life-cycle covers the year of operation)
- YETS24-25 replace by conform spares (based on refurbished TDIS with new bellows)


# Other limitations in Run 3 that require LHC parameters and configuration optimization




- Electron cloud and cryogenics load  
→ limits bunch pattern
- Radiation to inner triplets  
→ change of optics



# Electron cloud and cryogenics load



- **Heat load** → at the limit of cryogenic system
- Pressure rise
- Beam instabilities
- Emittance growth



~10% heat load reduction between Apr & Sep!


The additional 10% scrubbing leaves room to increase the number of bunches and bunch intensity:

➤ 2400 bunches with  $1.8e11$  p+/b with trains of 4-5x36b in reach

SEY: Secondary Electron Yield  
hc: LHC half-cell ~53 m

Under the effect of the cloud itself, conditioning of the copper surface of the LHC beam pipes is expected, decreasing thus the SEY of the surface. Such a process seems therefore to be hindered in some parts of the LHC ring.



# Ensuring the Longevity of the IT until LS3




**The problem:** collision debris (mainly pions) capture in the IT

**The consequence:** reduced lifetime of magnets → change needed before LS3

**The mitigation:** from nominal (FDF) to **Reverse Polarity** (DFD) optics



Main drawback: risk of radiation damage for the first module of D1 of both sides of IP1



- Exchange with spare should be considered for the YETS25-26
- **Moderate risk for 2025:** Replacement of a spare → 7 weeks of work in the tunnel
- Possibility to run with the first D1 module disconnected (~1 shift of work in the tunnel), increasing the strength of the remaining 5 modules (per IP side) and the MCBHX3

IT: Inner Triplet  
 IR: Insertion Region, IP: Interaction Point  
 RP: Reverted Polarity

D1: separation dipole  
 FDF: Focusing Defocusing Focusing  
 DFD: Defocusing Focusing Defocusing






# 2023 & 2024 LHC Performance


## ➤ 2023 summary:

- p+ period best availability 76%, stable beams for physics 52%
- Many long-term faults → target 75 fb<sup>-1</sup>/exp not reached

## ➤ 2024 summary:

- Highest production rate ever - up to **1.5 fb<sup>-1</sup>/24h**
- Peak luminosity at **~2.1x10<sup>34</sup> cm<sup>-1</sup>s<sup>-1</sup>**
  - Limited by cryogenic cooling capacity in the IT





## The 2023 & 2024 ion runs

# 2023 LHC Lead Ion Run Performance


## ➤ Ion run relied on several new concepts all successfully used in operation

- Slip-stacked 50 ns beams from injectors to provide higher intensity
- Crystal collimation to handle higher intensity without quenches
- TCLD collimators (HL-LHC equipment) & BFPP bump in IR2 to allow full luminosity for ALICE
- BFPP bump in IR8 to allow higher LHCb luminosity

## ➤ Several problems encountered

- Background in ALICE experiment – mitigated in 2023
- High beam losses in the ramp – mitigated in 2024
- Beam losses due to 10 Hz orbit oscillation – culprit found and fixed!
- Single-event upsets on quench protection system – mitigated in 2024

Delivered Luminosity 2023





# 2024 LHC Ion Run Performance

## ➤ 2024 Production


- ALICE, ATLAS, CMS: average **1.9 nb<sup>-1</sup>**
- LHCb: doubled 2023 production in half the time ➔ achieved!

Excellent injectors performance:

- Higher bunch intensities than LIU target
- Higher transmission efficiencies than before

Experiments' expectations for the full Run 3


- ATLAS/CMS/ALICE  
**5.35 nb<sup>-1</sup> for full Run3**
- LHCb  
1 nb<sup>-1</sup> but strong request for higher target (x2)



IP1,2,5: Remains 1.45 nb<sup>-1</sup> to be collected in 2025&2026

# 2025 & 2026 schedules

- 18.09.2024 Research Board approved the update of Run3/LS3/Run4 schedule:
  - Short YETS25-26 (08.12.2025 to 23.02.2026)
  - Run LHC until end of June 2026 with Heavy Ion run taking place in June
  - End of LHC Run 3 date on Monday 29th June 2026 (SPS North Area physics continues)



## 2025 scheduled (approved)

- 138 days of p+ physics
- 2 days of Vdm
- 25 days Pb run end of 2025
- NO pp ref run
- O-O and p-O collisions last week of June

## 2026 scheduled (info)

- 66 days of p+ physics
- 2 days of Vdm
- 25 days Pb run in June (PbPb or pPb)
- NO pp ref run




# Status of HL-LHC preparation



# HL-LHC parameters


- $2.3 \cdot 10^{11}$  p+/bunch
- $2.1 \mu\text{m}$   $\mathcal{E}^{n_{x,y}}$
- 25 ns bunch spacing
- $\beta^* = 0.15 \text{ m}$  ( $\beta^* = 0.5 \text{ m}$  @LHC)
- Virtual peak lumi with crab  $1.7 \cdot 10^{35} \text{ cm}^{-2}\text{s}^{-1}$
- LHC p+ Lumi Levelled @  $5 \cdot 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
- Pile up = 131

LHC Injectors Upgrade



$$\beta(L^*) = \beta^* + \frac{L^{*2}}{\beta^*}$$

$$\sigma_{x,y} = \sqrt{\epsilon_{x,y} \cdot \beta_{x,y}}$$



10 km

5 km

$\beta(L^*) > 10 \text{ km}$   
@IT

High gradient magnets:


- Stronger focusing
- Large aperture

Only possible with new technology

HL-LHC

# HL-LHC parameters

- But, larger beam size at the IP → larger crossing angle to avoid beam-beam interactions (need of large aperture)



$$\text{Lumi} = \text{Lumi}_{\text{ideal}} * \text{Spaghetti-Loss Factor}$$

$$\text{Lumi}_{\text{ideal}} = f(N_b \uparrow, I_b \uparrow, \epsilon \downarrow, \beta^* \downarrow)$$

$$F = \frac{1}{\sqrt{1 + 2 \frac{\sigma_s^2}{\sigma_{1x}^2 + \sigma_{2x}^2} \tan^2 \frac{\phi}{2}}}$$

*F = Spaghetti-Loss Factor*




- If **Spaghetti-Loss Factor** is not cured →
- LHC →  $\phi/2 = 285 \mu\text{rad} \rightarrow F \sim 85\%$
- HL-LHC →  $\phi/2 = 590 \mu\text{rad} \rightarrow F \sim 30\%$

**Crab-cavities are the solution**

# Magnets Nb<sub>3</sub>Sn


- Good progress across all key technologies
- US and CERN magnet production well underway
- Inner Triplet String testbed taking shape
  - Infrastructure in place and magnets starting to be installed



LHC NbTi → 12 kA  
 HL-LHC Nb<sub>3</sub>Sn → 16.5 kA (ultimate 17.5 kA)

The IT String will deliver the first complete experience of installing and operating the IT zone

The Inner Triplet String Testbed – focus for 2025



Magnet Line, Jacks & Alignment System



# Preparing for the Inner Triplet String Test

- Tracing on the floor:
  - Beamlines, pillars, jumpers, beam pts, jacks, anchors, ...
  - Robotic solutions for tracing to reduce time
- Magnet support jacks - installation and alignment
- First magnets aligned
  - Q2a and D1 in place and aligned in Nov 2024



13/01/2025



Epiphany 2025 R. Alemany Fernandez






# MgB<sub>2</sub> superconducting link

The flexible, double-wall, corrugated cryostat:

- **19 MgB<sub>2</sub> SC cables** in a single assembly, twisted together to form a compact bundle
- Can transfer altogether a DC current of about **120 kA at ~20 K**






The first Cold Powering System for the HL-LHC Triplets has been **successfully validated**: cryogenic, electrical and mechanical performance all met design parameters


Today in an **advanced phase of series production**

SC: Super Conducting  
 D1: separation dipole


# Crab Cavities



Increasing the number of collisions in the HL-LHC



5 DQW cryomodules (Europe)



5 RFD cryomodules (North America)

Delays in RFD cavities jeopardizes completion of RFD cryomodules in-time for LS3 installation



- Mitigation strategy being worked on



# Civil Engineering Complete



Point 1




Point 5






# Updated Schedule for HL-LHC



# Conclusions






CMS Experiment at the LHC, CERN

Data recorded: 2024-Nov-06 10:55:06.459264 GMT



Run / Event / LS: 387854 / 23097014 / 33



LHCb Experiment at CERN

Run / Event: 310067 / 3591585364

Data recorded: 2024-11-06 12:08:15 GMT





# CERN COURIER

January/February 2024. [cerncourier.com](http://cerncourier.com)

Reporting on international high-energy physics

## HIGH-LUMINOSITY LHC ON TRACK





# Spares

# Setting the scene



Injectors RUN 2 achieved parameters <sup>SPS ejection</sup>:

- **$1.2 \cdot 10^{11}$  p+/bunch**
- $2.6 \mu\text{m } \mathcal{E}_{x,y}^n$
- 25 ns bunch spacing

Integrated LHC luminosity  
 **$\sim 140 \text{ nb}^{-1}$  @ 6.5 TeV**  
 (per high lumi experiment)

**LIU & 1<sup>st</sup> phase of HL-LHC**

- New **Linac 4 @ 160 MeV H-**
- Booster injection @ 160 MeV and extraction @ 2 GeV
- PS injection @ 2 GeV, RF system upgrade, etc
- SPS RF system upgrade, etc

Injectors LIU targets <sup>SPS ejection</sup>


- **$2.3 \cdot 10^{11}$  p+/bunch**
- $2.1 \mu\text{m } \mathcal{E}_{x,y}^n$
- 25 ns bunch spacing

LHC p+ Lumi Levelled  
**@  $5 \cdot 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$**

**LIU & 1<sup>st</sup> phase of HL-LHC commissioning and exploitation**

**HL-LHC upgrades installation**  
 BCMS 25ns - H

**HL-LHC commissioning and exploitation**



$\mathcal{E}_{x,y}^n$  : normalized transverse emittance  
 LIU: LHC Injectors Upgrade


# LHC in 2024

**First injection: 8<sup>th</sup> March (3 days early)**




Beam position around the 27 km

**1200 bunches on 14<sup>th</sup> April (10 days early)**  
**1215 1215**



## Stable Lumi Production


Summer period



Beyond the 110 fb<sup>-1</sup> target



## Delivered Luminosity 2024



Mar-Apr


May

Jun-Jul

Aug-Sep

Oct-Nov

**Reverse Polarity optics commissioned (~ +1 week)**





**First Stable Beams @6.8 TeV 5<sup>th</sup> April (3 days early)**




**LHCb VELO closed for the 1<sup>st</sup> time**

## Very stable physics production


**Operating with 1.6 · 10<sup>11</sup> p+/bunch**  
**Bunch length control/target**  
**Limit RF module heating risk**



**pp reference run 28<sup>th</sup> Oct – 2<sup>nd</sup> Nov**  
**Integrated lumi over expectations**



installed RF burst disk type



new depressurizing valve

- Trigger event → power cut in point 4 following a wrong manipulation after issue with compensator
  - Afterwards: well-known chain of events:
    - the RF cavities are automatically isolated from the He input and output lines, consequently the cryomodule pressure increases due to the static heat loads the safety valves open and maintain the pressure around 1.9 bar
  - Unfortunately, two of the **new burst disks** installed during YETS22-23 did **not withstand the pressure** and **opened**
  - A test campaign on the spare disks confirmed that **likely these two disks were outliers**
- Mitigation to reduce the risk:**
- Installation of fast depressurizing valves to back up the warm recovery line
  - **Similar events may still happen** given small pressure margin between opening of safety valve and burst disk, which is necessary to be able to protect the RF cavities against major events, for which the burst disks were foreseen




# LHC in 2024

## Dealing with Limitations – RF Finger Modules

- Operating in 2024 with known weak modules
  - 47 of 71 replaced in YETS23-24
  - Remaining modules to be replaced YETS24-25
- Beam induced power depends on bunch intensity and bunch length
  - Bunch intensity limited to  $1.6 \cdot 10^{11}$  p+ in 2024
    - Run 3 max =  $1.8 \cdot 10^{11}$  p+/b
  - Bunch length control throughout the cycle

• Bunch intensity limited to  $1.6 \cdot 10^{11}$  p+ in 2024  
 • Run 3 max =  $1.8 \cdot 10^{11}$  p+/b





# Performance optimization

## ➤ Move to BCMS Beams

- Filling scheme based on 3x36b patterns imposed by heat load limitation from electron cloud
- Intensity limited to  $1.6 \cdot 10^{11}$  p+/bunch by RF fingers
- **Emittance: could be improved with BCMS**


## ➤ Optimised BCMS since May

- Higher bunch brightness
  - Smaller emittance beneficial for reducing losses at injection



BCMS Beam for the LHC in the PS

BCMS: **B**atch Compression and (**b**unch) **M**erging and (**b**unch) **S**plitting



# Outlook for the LHC in 2025

## ➤ 2025 Schedule


- 2025 luminosity target will be comparable to 2024 (target  $110 \text{ nb}^{-1}$ )
- Short **Oxygen run** mid-year and **Pb Ion Run** to end the year

## ➤ Ensuring longevity of the IT Magnets

- Full reversed polarity gives best outlook but would stop any forward physics
- Compromise is flipping the crossing plane with nominal powering in IR1 and reversed polarity in IR5
  - Good background conditions for FASER and SND
  - PPS rotated to allow data taking to continue
- Several magnets still reach estimated limits if 2025 and 2026 are good production years

## ➤ Moving to Flat Optics

- Recovers luminosity loss due to limitation of aperture in triplet with flipped crossing plane



IT: Inner Triplet

FASER: Forward Search Experiment (close to IP1)


SND: Scattering and Neutrino Detector (close to IP1)

PPS: Precision Proton Spectrometer (close to IP5)



# Beam screen heat load forecast @HL-LHC era

- The LHC **cryogenic capacity is limited** and cannot be easily increased  
Money, surface/underground available space, energy...
- From **Run 4, heat loads** applied to cryogenics will significantly **increase**  
LHC intensities  $\uparrow\uparrow \rightarrow$  Sync. Rad + Image Current + e-cloud  $\uparrow\uparrow$



The proposed mitigation strategy is :  
 “Treat” *in situ* a fraction of BS around the LHC to reduce the e-clouds  
 This treatment must be done in LS3

“Treat”: remove CuO + increase surface carbon concentration  
 + surface passivation on 100 selected half-cells


Under the effect of the cloud itself, conditioning of the copper surface of the LHC beam pipes is expected, decreasing thus the SEY of the surface. Such a process seems therefore to be hindered in some parts of the LHC ring.

# Key ingredients for the HL-LHC upgrade

A technologically “intense” upgrade project

- 1 New IT quadrupoles, Nb<sub>3</sub>Sn
  - 2 Civil engineering
  - 3 Crab Cavities
  - 4 Crystal collimation
  - 5 Low impedance collimators
  - 6 Superconducting links
- Injection and dump upgrades



...







# Preparing the Collider-Experiment Interface

- Protecting the machine from collision debris
  - Moving into the production phase for both the **TAXS** (secondary particle absorber) the **TAXN** (neutral particle absorber)
  - Mock-up area heavily used to train and test
    - Very soon house full setups of both ATLAS and CMS









# LHC layout & beam production



# Powering the HL-LHC magnets



# Powering Scheme




## Four power converters:

**18 kA** –  $I_{HL-LHC} = 16.23$  kA (Nb<sub>3</sub>Sn quadrupole)

**15 kA** –  $I_{HL-LHC} = 12.11$  kA (Separation dipole)

**2 kA** –  $I_{HL-LHC} = 2$  kA (Trim)

**2 kA** –  $I_{HL-LHC} = 1.74$  kA (Correctors)



Maximum current delivered by the power converters: **94 kA**



# Other limitations in Run 3 that require LHC parameters and configuration optimization



- Besides: RF fingers modules
  - ➔ limits bunch intensity and bunch length
- Electron cloud and cryogenics load
  - ➔ limits bunch pattern
- Radiation to inner triplets
  - ➔ change of optics

