


ePIC Silicon Vertex Tracker OB Mechanics and Cooling



Adam Huddart



Introduction


- L3
 - Inner - 23 staves with a (centre of mass) radius of 269 mm
 - Outer - 23 staves with a (centre of mass) radius of 275 mm
- L4
 - Inner - 35 staves with a (centre of mass) radius of 421 mm
 - Outer - 35 staves with a (centre of mass) radius of 427 mm
- Equal overlap between sensors, overlap set to fit stave within 45-degree cone.
- L3 and L4 support structure identical except for difference in length/number of and type of LAS

OB L3 (6RSU segments)




Introduction

- Stave structure is internally hollow to form channels for coolant airflow
- Majority of the stave structure is carbon fibre/foam
 - Assembled in a single co-curing operation
 - Preform FPC C channel and Central I-Beam
 - Vacuum bagged in autoclave with removable internal tooling
- Sensors are adhesively mounted as “modules” consisting of 2 EIC-LAS, ASICs, Bridge FPC and a Kapton carrier
- Focused on L4
 - More difficult in terms of structural and thermal targets.




L3/L4 Stave Structure Overview




Brief Overview of 1/4 Stave Prototype



Kapton Former




Carbon Fibre I-beam Mould



Internal Formers

- 1/4 of an L4 stave
 - One top one bottom module
- Preformed I beam and Kapton C Channel FPC Mock-ups
- SLA 3D printed end supports
- Multipart aluminium internal tooling
- 2 x 3mm rod runs through end supports, K9 foam cross braces & internal tooling to constrain and align stave components


Brief Overview of 1/4 Stave Prototype




- 1/4 of an L4 stave
 - One top one bottom module
- Preformed I beam and Kapton C Channel FPC Mock-ups
- SLA 3D printed end supports
- Multipart aluminium internal tooling
- 2 x 3mm rod runs through end supports, K9 foam cross braces & internal tooling to constrain and align stave components

EIC-LAS Module

- Module Consists of:
 - 2 EIC-LAS
 - 2 ASIC
 - Bridge FPC
 - Kapton Carrier
- Modules are assembled on tooling and transferred with sensors held into a curved shape with vacuum tooling
- Module transfer tooling will be tested on quarter length stave




What we Need to Prove



- Structure is sufficiently stiff
 - Does not vibrate excessively due to internal airflow
 - Stave structure must withstand internal pressure requirements
- Electronics temperatures stay within their target temperature window
 - FEA and CFD studies have informed prototype stave design
 - For prototype testing we will use dummy heat loads, measure temperature of LEC & ASIC mock-ups on stave prototypes
- Planned manufacturing methods are achievable and resulting assembly is within required dimensional tolerances.

Proving Mechanical Stiffness

- Modal Analysis through FEA
 - Must include the mass and stiffness or all components (and bonding methods) of the stave
 - Target first mode of 100 Hz
 - FEA analysis can be validated using piezo driven vibration table
- Prove pressure capacity of stave through pressure testing
 - Difficult to model/predict adhesive bond strength when surfaces are not rigid.



Quarter Length Stave FEA – First mode 97 Hz



Quantitative Structural Results

- Mass estimate


Component	Volume mm ³	Density kg/m ³	QTY	Mass	
Carbon Fibre Skin Upper	657.837628	1580	1	1.039383 g	
Carbon Fibre Skin Lower	690.516991	1580	1	1.091017 g	
Kapton C Channel	206.136635	1420	2	0.585428 g	
Stave End Mounts	1462.491448	1210	2	3.539229 g	
I Beam (Half)	322.104359	1580	2	1.01785 g	
K9 Foam Block	1295.980514	200	6	1.555177 g	
			Total Mass	8.828084 g	

Measured: 8.95 g


- 3pt bend test






1/4 Stave Finite Element Analysis




K: Static Structural
Total Deformation
Type: Total Deformation
Unit: m
Time: 1 s
26/09/2024 09:09



0.981N
Vertical load applied at
central K9 foam block




Thermal Modelling




- FEA/CFD models of the L4 stave and ASIC
 - Detailed modelling of thermal pathway for ASIC cooling to optimise it's layout
 - L4 model to estimate required flow velocity, coolant outlet temperatures and pressure drop.
- Keeping LEC and ASIC close to 25°C significantly decreases thermal output

Cooling Requirements



- Target delta T between all LEC or coolant or RSU of 10K
- Coolant (low pressure) enters the stave at the end support and flows down central air channel in the stave
- High power density components LEC and ASIC in close thermal contact with K9 foam for enhanced cooling
 - Porosity (and strategically positioned holes) allows air to pass cross braces

Numbers used




OB and disks


Power [mW]	5 RSU			6 RSU		
	LAS	AncASIC	FPC	LAS	AncASIC	FPC
Nominal	1092	382 (35% of LAS)	218 (20% of LAS)	1224	428 (35% of LAS)	245 (20% of LAS)
Max	1689 (+55%)	759 (45% of LAS)	507 (30% of LAS)	1897 (+55%)	853 (45% of LAS)	569 (30% of LAS)

OB		# of LAS/stave	# of staves	Total # of LAS	disks	Total # of LAS
L4	5-RSU LAS	16	70	1120	5-RSU LAS	1104
L3	6-RSU LAS	8	46	368	6-RSU LAS	1312

Stave Temperature & Flow




- L4 Stave Power
 - Nominal – 27.1 W
 - Max – 47.3 W
- L3 Stave Power
 - Nominal – 13.2 W
 - Max – 22.0 W
- Stave CSA = 260 mm²
- Required flow velocity
 - Nominal – 9,8 m/s (135 l/min)
 - Max – 17.0 m/s (235 l/min)




Air Supply

- OB airflow requirement – 12500 – 21500 L/min (0.2-0.35 m³/s)
 - Equivalent flow velocity through 30cm (12”) duct = 3-5 m/s
- Could we supply at pressure and locally reduce
 - 15 Bar through 16 x 10mm ID tubes
 - Flow Velocity - 11 to 19 m/s
 - System will need to be well tested and tolerant to blockages to avoid rupturing staves




Next Steps



- Build another $\frac{1}{4}$ Length stave for flow testing
 - Dummy heat loads to represent LEC, RSU and ASIC
 - Compare CFD studies with experimental results
- Feasibility of flat staves
 - Significantly easier for module assembly
 - Preliminary FEA studies show this has a limited effect on global stave stiffness
 - Further modelling of effect of internal pressure needed

Conclusions




- First $\frac{1}{4}$ Stave prototype was both successful and informative
 - Static load testing showed similar (slightly better) stiffness than FEA
 - Redesign end supports & try with silicone intensifier to reduce imperfections in the carbon fibre skins.
- Second $\frac{1}{4}$ Stave will allow us to test modal response of stave and validate thermal models
- More extensive analysis of a flat sensor stave needed




Additional Slides

Local Stiffness of EIC-LAS

- Air velocities in flow channel will be high
 - High pressure drop/high inlet pressure
- Modelled assuming rigid mounting around glue locations
- Curvature reduces deformation due to internal pressure
- Sensor/module curvature of $\text{Ø}180$ mm results in micron level deformation due to 1000 Pa internal pressure





Pictures



J: Copy of Copy of 4m Outer 8m Inner

Total Deformation
Type: Total Deformation
Frequency: 841.38 Hz
Unit: m
27/09/2024 13:03





Graph

Animation 20 Frames 2 Sec (Auto) AA


1.
888.23

Tabular Data

Mode	Frequency [Hz]
1	841.38
2	888.23





Graph Animation 20 Frames 2 Sec (Auto) 3 Cycles AA




Tabular Data

Mode	Frequency [Hz]
1.	96.982
2.	163.75
3.	219.46
4.	799.81





Graph Animation 20 Frames 2 Sec (Auto) 3 Cycles AA




Tabular Data

Mode	Frequency [Hz]
1	96.982
2	163.75
3	219.46
4	799.81

J: Copy of Copy of 4mm Outer 8mm Inner
Total Deformation 3
Type: Total Deformation
Frequency: 219.46 Hz
Unit: m
27/09/2024 16:37




Graph
Animation 20 Frames 2 Sec (Auto) 3 Cycles AA



Tabular Data

Mode	Frequency [Hz]
1	96.982
2	163.75
3	219.46
4	799.81

Future Design Work



- Current Staves have a dia 180 mm curvature
 - Curved surfaces may be difficult for wire bonding
 - FEA studies suggest curvature has minimum impact on structure stiffness
 - Future iterations may use a flat sensor/module