

Next phase

Update the two following




Table 32: Main CLIC accelerator objectives and activities in the next phase.

Activities	Purpose
Design and parameters	
Beam dynamics studies, parameter optimisation, cost, power, system verifications in linacs and low emittance rings	Luminosity performance and reduction of risk, cost and power
Main linac modules	
Construction of 10 prototype modules in qualified industries, two-beam and klystron versions, optimised design of the modules with their supporting infrastructure in the main linac tunnel	Final technical design, qualification of industrial partners, production models, performance verification
Accelerating structures	
Production of ~ 50 accelerating structures, including structures for the modules above	Industrialisation, manufacturing and cost optimisation, conditioning studies in test-stands
Operating X-band test-stands, high efficiency RF studies	
Operation of X-band RF test-stands at CERN and in collaborating institutes for structure and component optimisation, further development of cost-optimised high efficiency klystrons	Building experience and capacity for X-band components and structure testing, validation and optimisation of these components, cost reduction and increased industrial availability of high efficiency RF units
Other technical components	
Magnets, instrumentation, alignment, stability, vacuum	Luminosity performance, costs and power, industrialisation
Drive-beam studies	
Drive-beam front-end optimisation and system tests to ~ 20 MeV	Verification of the most critical parts of the drive-beam concept, further development of industrial capabilities for L-band RF systems
Civil Engineering, siting, infrastructure	
Detailed site specific technical designs, site preparation, environmental impact study and corresponding procedures in preparation for construction	Preparation for civil engineering works, obtaining all needed permits, preparation of technical documentation, tenders and commercial documents

New elements

This chapter will need to cover design and technology work for the next period (see table earlier), but also:

- The environmental studies and CE studies needed (learn from the FCC) – good confidence in ground conditions but shafts and caverns to be fixed – 2-3 years
- Preparation needed at CERN for infrastructures, test-facilities and expertise. Longer term
- Related: A budget estimate and personnel estimate is also needed for this phase. This is difficult but is partly covered in R&D table and operational personnel estimate.
- Consider also extras for Physics Beyond Collider beams (maybe not in this chapter but mentioned here for future work)