



FP420 Tracking Stations CERN Meeting Mar 2006

Overview



3D [xyz]



Breakdown of responsibilities for tracking detectors....




Detector Station built from a number of superlayers




Detector Blades (example)

3-D sensor bump bonded to FE ASIC. FE ASIC bonded to support (ceramic, carbon-carbon, etc) that provides heat path. Electrical connections wire bonded to eg Kapton/Polyimide flexible loom.

3D [xyz]



3D [xyz]



Kapton

Mech/Therm

3D Sensor


FE ASIC

Detector 'Superlayer', the basic building block

Two (logical) layers, both orientations. Superlayers share upstream control ASIC and other connections.

Usually about 6mm of material per superlayer (worst case may be ~10mm) Depth 12mm
Power - typically less than ~5W



3D [xyz]



...


...

3D (xyz)



Detector Station (example) ... stack of superlayers

3D [xyz]



	Depth	Material	Power
5 Superlayers 10 layers 20 blades	~60mm	30-50 mm	~25W
6 Superlayers 12 layers 24 blades	~72mm	36-60 mm	~30W
8 Superlayers 16 layers 32 blades	~96mm	48-80 mm	~40W

Resources...

✂ Funding:

As part of the UK bid to the PPRP we requested resources to develop the design of the tracking detector station, under 'Work Package 3'. The budget was 225K (15K Travel, 75K equipment, 2.5SY). This is/will be approved.



We are working up to placing orders for readout infrastructure and a wedge bonder. (Advice most welcome).



Modelling....

Geant for material/design studies:


We want to have some local ability to work through consequences of material/layout choices.



Thermal Modelling:

This is critical, thermal stresses determine mechanical accuracy, detector handling, etc.
We have experience at Manchester with FlexPDE (Atlas Silicon modelling)
We may want to use ANSYS with our default Mechanical CAD, AutoDesk Designer Pro
May consider buying I-DEAS for compatibility with MSSL
MSSL are well placed to work on the thermal modelling.

Plans....



Milestones....

LABS (Apr)

The Manchester HEP group has had it's office and lab space refurbished at a cost of 1.3 Million. Being handed over now, 'finished' date not certain, but 'soon'.

Fix the sensor design (Apr)

This has a major impact on the design of the detector station. Hope to fix this at a workshop at Stanford in April.

Obtain samples of bonded sensors (Apr)

Establish a readout testbench (May)

Commission bonding station (by June)

Develop/Test Electrical prototype (Sept)

Develop/Test Mechanical Prototype (Sept)

Testbeam (Sept)

No reason why we shouldn't test the electrical prototype if ready

Final design constraints specified (Sept)

Final Prototype (Dec)