






# Talk-for-Guides: Lifecycle of the LHC

## The CERN Accelerator complex and its running

Rende Steerenberg – BE/OP

6 December 2024

# The CERN Accelerator Complex




# Topics

- **Scheduling**
- **Satisfying our Users**
- **Controlling the Accelerator Complex**
- **Some things that will happen during LS3**


- **Scheduling**
- Satisfying our Users
- Controlling the Accelerator Complex
- Some things that will happen during LS3



# The long-term accelerator schedule




# The long-term accelerator schedule



- **The running of the accelerator complex is interleaved with:**
  - Technical stops – TS
  - Year End Technical Stops - YETS
  - Long shutdowns – LS
- **The periods between the LS's are typically 4 to 5 years**
- **Yearly schedules are made and approved by the Research Board based on this long-term schedule**
- **The present Long-term schedule runs until 2041 incl.**
  - This is at present the foreseen date to complete the (HL-)LHC programme

# The long-term accelerator schedule




- **End of the Run 3:**

- LHC – last beams scheduled to be dumped on 29 June 2026
- Injectors – End of beam production and physics scheduled for 31 August

- **Tentative dates to resume beam operation post-LS3 (still under discussion)**

- (HL-)LHC
  - Hardware re-commissioning January 2029
  - Beam re-commissioning May 2030
- SPS: May 2029
- PS Complex: May/June 2028

# Global overview of the LHC running until LS3





- **2025:** 35 weeks YETS to YETS → 165 physics days (protons, oxygen ions and lead ions)
- **2026:** 18 weeks YETS to YETS → 88 physics days (protons and lead ions)







# The Yearly Schedule: 2025

- Yearly Schedules are based on:
  - The long-term schedule
  - Physics needs as defined by the experimental committees and the Research board
  - The period necessary to restart the complex and to prepare the different beam types required
- There are two yearly schedules:
  - The LHC schedule
  - The Injectors schedule




- **Scheduling**
- **Satisfying our Users**
- **Controlling the Accelerator Complex**
- **Some things that will happen during LS3**

# Filling the LHC








# LHC

- 1232 main dipoles of 15 m each that deviate the beams around the 27 km circumference
- 858 main quadrupoles that keep the beam focused
- 6000 corrector magnets to preserve the beam quality
- Main magnets use superconducting cables (Cu-clad Nb-Ti)
- 12'000 A provides a nominal field of 8.33 Tesla
- Operating in superfluid helium at 1.9K

# The LHC Cycle

- = Field in main magnets
- = Beam 1 intensity (current)
- = Beam 2 intensity (current)






# Stored Beam Energy in the LHC





- The stored energy in one LHC beam at 6.8 TeV nowadays is about **400 Million Joules**
- This corresponds to the energy of a TGV train going at  $\sim 160$  km/h
- ..... but then concentrated in the size of a hair

# Filling the LHC & Satisfying Fixed Target users





# Satisfying the Fixed Target Users




# Satisfying Fixed Target users, when LHC is not filling

Example SPS:

<https://op-webtools.web.cern.ch/vistar/?usr=SPS1>

- **Cycle (e.g. SFTPRO1):**
  - Flat bottom – injection
  - Ramp – acceleration
  - Flattop – extraction
  - Ramp down – no beam

- **Super Cycle & Basic Periods:**
  - Sequence of multiple cycles of the same or different type that repeats itself
  - Length 30BP, 36.0s



# Satisfying Fixed Target users, when LHC is not filling

- **Cycle SFTPRO1:**
  - Two injections from the PS
    - Each PS cycle injecting takes 1.2S
  - Final destination North Area
  - Slow extraction over ~ 4.5 sec.
  - Total cycle duration 9BP, 10.8s
  - Used for physics

- **Cycle MD1:**
  - One injections from the PS
  - Destination internal beam dump
  - Total cycle duration 6BP, 7.2s
  - Used for Machine development studies (MD)

SPS-PAGE1 Current user: SFTPRO1 2.15E+13 06-05-24 13:21:49  
 SC 6 (30BP, 36.0s) Last update: 3 seconds ago


Target	I/E11	MUL	%SYM	Experiment
T2	74.3	13	93 a	H2/H4
T4	41.0	4	94 a	H6/H8
T6	71.5	1	97 a	AMBER
T10	20.7	0	97	NA62

Phone: 77500 or 70475  
 Comments (06-May-2024 12:44:04)

User	Injected	Flat Top	NOW:
LHCMD2	125 E8	27.4 E8	NA + MD11803 (+MD12203)
			NEXT: - o -



# PSB, PS and SPS super cycle composition example



- **SPS Fixed target (=SFTPRO1):**

- Requires 2 cycles in the PSB injecting into the PS injecting into the SPS
- While SPS is accelerating and extracting PS can PSB can serve ‘their’ users
  - PS: 2 x East Area requiring each 1 cycle in the PSB + 2 x nTOF requiring each 1 cycles in the PSB
  - PSB: in the shadow of the PS accelerating and extracting for East Area, PSB can produce ISOLDE
  - PSB can also use the cycles for ISOLDE that are not required by PS or PS and SPS

# Other examples




Infinitely other combinations possible....

- Scheduling
- Satisfying our Users
- **Controlling the Accelerator Complex**
- Some things that will happen during LS3


# Settings Management

- All machine equipment (e.g. power converters, RF cavities, beam instrumentation, ...) are items in a database with various properties
- Each cycle has a label (e.g. SFTPRO1, MD1, LHCINDIV, ISO,....) which are stored in a database
- The database contains settings (values, functions) for each cycles in each machine
- **Every time a cycle is executed:**
  - These values are sent to the equipment
  - The values and functions are activated by timing events that are also programmed in a database
- **This allows to program each cycle differently enabling the production of very different types of beams**




# Control Rooms

- **CERN Control Centre (CCC) – Prevezin**
  - 24/7 shifts
  - Linac4, PSB, PS, SPS, LHC
  - LINAC3, LEIR
  - Technical Infrastructure, Cryogenics
- **AD Control Room (ACR) - Meyrin**
  - Day time operation
  - Back-up operation from CCC during nights & weekends
  - Standby service by AD/ELENA operator
- **ISOLDE Control Room (ICR) - Meyrin**
  - Day time operation
  - Limited back-up operation by experimentalists during nights & weekends
  - Standby service by ISOLDE operator





# CERN Control Centre (CCC) lay-out




- **PS island**
  - 1 Shift leader + 1 or 2 Operators
- **SPS island**
  - 1 Shift leader + 1 Operator
- **LHC island**
  - 1 Engineer in charge (LHC-EiC)
- **TI/Cryo island**
  - 1 Technical infrastructure operator
  - 1 (or 2) Cryo operator(s)
- **During daytime 20 to 30 people extra for studies, setting-up new beams, issues, etc.**

- **Scheduling**
- **Satisfying our Users**
- **Controlling the Accelerator Complex**
- **Some things that will happen during LS3**

# What will happen during LS3?

- **HL-LHC project will be deployed**
  - The LHC Injector Upgrade (LIU) project was completed during LS2
  - During run the performance potential given to the injectors has been exploited and HL-LHC beam parameters have been achieved in the injectors.
  - Now LHC will be prepared to be able to cope with the high intensity and high brightness beams





# Upgrade to the High-Luminosity LHC is under way

- The HL-LHC will use new technologies to provide 10 times more collisions than the LHC.
- The stored beam energy will increase from ~300 MJ to ~600 MJ.
- It will give access to rare phenomena, greater precision and larger discovery potential.
- It will start operating in 2030, and run until 2041.



# Luminosity, the Figure of Merit

$$LUMINOSITY = \frac{N_{event/sec}}{S_r} = \frac{N_1 N_2 f_{rev} n_b F}{4\rho S_x S_y}$$

Intensity per bunch

Revolution frequency

Number of bunches

Geometrical Correction factors

Beam dimensions

## What to do to maximise luminosity?




- Increase the number of bunches and revolution frequency → constraint
- Increase the bunch intensity
- Reduce the transverse beam size (emittance)
- Reduce the beam size at the collision point
- Minimise the crossing angle
- Ensure good machine availability to increase integrated luminosity

→ LHC Injectors Upgrade

→ HL-LHC Upgrade

# Key Ingredient Injector Upgrade

- Charge exchange injection with  $H^-$




Phase Space Painting is possible (various particle distributions)

# The High Luminosity LHC Project

## Major civil engineering

- **New interaction region magnets**
- **Collimation** upgrade
- **Cryogenics** upgrade
- **Crab Cavities** to reduce crossing angle
- **Cold powering**
- **Machine protection**
- ...and much **more**...





# New Facilities and Equipment Being Added






# What will happen during LS3?

- **HL-LHC project will be deployed**
  - The LHC Injector Upgrade (LIU) project was completed during LS2
  - During run the performance potential given to the injectors has been exploited and HL-LHC beam parameters have been achieved in the injectors.
  - Now LHC will be prepared to be able to cope with the high intensity and high brightness beams
- **SPS North Area consolidation phase 1 & HI-ECN3 in view of the SHiP experiment**

# Scope of SPS North Area Consolidation


## Consolidation Phase 1 (2019 – 2028)

- Primary areas incl. TDC2, TCC2, BA2, BA80 & beam lines towards EHN1 & TDC8



**Consolidation Phase 2 (2029 – 2034): BA81, BA82, EHN1, EHN2 & associated beamlines**

# High Intensity ECN3 for the SHiP experiment



- TCC8/ECN3:**
- Beam Dump Facility
  - HI Target Complex
  - Related Infrastructure & Services



# What will happen during LS3?

- **HL-LHC project will be deployed**
  - The LHC Injector Upgrade (LIU) project was completed during LS2
  - During run the performance potential given to the injectors has been exploited and HL-LHC beam parameters have been achieved in the injectors.
  - Now LHC will be prepared to be able to cope with the high intensity and high brightness beams
- **SPS North Area consolidation phase 1 & HI-ECN3**
- **ISOLDE beam dumps replacement in view of possible energy and intensity upgrade**


# The ISOLDE layout

With the LIU upgrade the PSB:


- Can provide higher energy beam at 2 GeV instead of 1.4 GeV
- Has the potential to provide higher intensity beam to ISOLDE

To allow for this ISOLDE will need to be consolidated and possibly upgraded

- One major ingredient for this is the replacement of the beam dumps



# ISOLDE Beam Dump Replacement



Dumps already operate at their limit in terms of **temperature and mechanical stresses**


Suffering from: **Corrosion**



# What will happen during LS3?


- **HL-LHC project will be deployed**
  - The LHC Injector Upgrade (LIU) project was completed during LS2
  - During run the performance potential given to the injectors has been exploited and HL-LHC beam parameters have been achieved in the injectors.
  - Now LHC will be prepared to be able to cope with the high intensity and high brightness beams
- **SPS North Area consolidation phase 1 & HI-ECN3**
- **ISOLDE beam dumps replacement in view of possible energy and intensity upgrade**
- **Massive consolidation work (e.g. electrical infrastructure, ...)**
- **.... Many more... plus... the usual preventive and corrective maintenance**

**But until then the focus will be  
on beam production for physics  
Stay tuned...!**






# Breaking Performance Records



Peak Luminosity	$2.33 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Max. Luminosity in one day	$1.525 \text{ fb}^{-1}$
Max. Luminosity in 7 days	$8.342 \text{ fb}^{-1}$
Longest time in Stable Beams	5 days 3 hr 35 min
Max. Charge per bunch	$1.64 \times 10^{11}$

**The integrated luminosity for proton physics during Run 3 so far stands at an impressive  $196 \text{ fb}^{-1}$ , surpassing the combined total of Runs 1 and 2 - and Run 3 is far from over, with 2025 and 2026 still ahead of us.**



# Linac 4



- H<sup>-</sup> ion source at 45 keV
- Accelerates beam up to 160 MeV
- The chopping scheme allows removing some of the Linac bunches to make the beam fit into the PS Booster RF buckets
- Pulse rate 1.2 s






# PS Booster


- 1<sup>st</sup> Synchrotron with 4 superposed rings
- Circumference of 157 m
- Proton energy from 160 MeV to 2 GeV
- Can cycle every 1.2 s
- Each ring will inject over multi-turns, using charge exchange injection



Before stripping foil




Behind stripping foil






# PS

- **The oldest operating synchrotron at CERN**
- **Circumference of 628m**
  - 4 x PSB circumference
- **Increases proton energy from 2 GeV to max. 26 GeV**
- **Cycle length ranges from 1.2s to 3.6s**
- **Many RF systems allow for complex RF gymnastics**
- **Various types of extractions:**
  - Fast extraction
  - Multi-turn extraction (MTE)
  - Slow extraction





# SPS

- The first synchrotron in the chain at ~30m under ground
- Circumference of 6.9 km
  - 11 x PS circumference
- Increases proton beam energy up to 450 GeV with up to  $\sim 5 \times 10^{13}$  protons per cycle
- Provides slow extracted beam to the North Area
- Provides fast extracted beam to LHC, AWAKE and HiRadMat





# LHC




- Situated on average ~100 m under ground
- Four major experiments
- Circumference 26.7 km
- Two separate beam pipes going through the same cold mass 19.4 cm apart
- 150 tons of liquid helium to keep the magnets cold and superconducting



# The LIU Project was completed in LS2

- LINAC4 – PS Booster:
  - New LINAC 4 with H<sup>-</sup> injection
  - Higher injection energy
  - New Finemet® RF cavity system
  - Increase of extraction energy
- PS:
  - Injection energy increase from 1.4 GeV to 2 GeV
  - New Finemet® RF Longitudinal feedback system
  - New RF beam manipulation scheme to increase beam brightness
- SPS
  - Machine Impedance reduction (instabilities)
  - New 200 MHz RF system
  - Vacuum chamber coating against e-cloud



These are only the main modifications and this list is not exhaustive