


Low Density Wires: implementation during LS3 (and beyond)

<u>C. Pasquino</u>, R. Veness, W. Andreazza, H. Sullivan, G. Aliana, J. Emery, F. Roncarolo

HL-LHC Beam Halo Review

Beam Wire Scanners in the LHC



- Scanning speed 1 m/s;
- 10 micron of the beam size accuracy;
- Use case: LHC injection energy, few bunches only; used to calibrate the BSRT



Beam Wire Scanners in the LHC





- □ 8 BWS: 2 per plane per beam;
- 4 Legacy systems inherited from LEP;
- ☐ 4 Hybrid+, featuring new electronics and new feedthrough: intermediate implementation to bridge to the new generation of WS.




Beam Wire Scanners in the LHC - CONS


- □ Approved CONS program: <u>EDMS 2282009 Consolidation</u> of LHC Beam Wire Scanner Electro Mechanics;
- Improve performance
 - Reduce vibrations;
 - Reduce position uncertainty;
 - Improve positional resolution;
- Improve reliability
 - Reduce intervention frequency;
- Broaden the use case
 - Potential for use as halo monitor;
 - ☐ Higher intensity measurement can be designed to support CNT implementation;




Beam Wire Scanners LHC CONS - STATUS



In vacuum linear guide assembly In vacuum side coupling



instrument card






Pre-LS3 Development Phase

What is already designed (completed), installed, validated

- Magnetic coupling validated with the test rig;
- Adaptation of the control system to the new mechanism;
- Mechanical design well advanced detailed design with MME to start in January;
- □ Impedance design well advanced longitudinal impedance studies completed, transverse to be computed together with a power loss map;





Pre-LS3 Development Phase

What is planned and expected to be implemented before LS3

Roadmap up to LS3:

- Instrument design and development:
 - ☐ Impedance prototype to be installed in YETS 2025-2026 for beam validation;
 - □ Detailed mechanical design, with feedback from beam validation;
 - ☐ Test rig testing campaign for carriage lifetime and controls validation;
- ☐ CNT R&D:
 - ☐ HRMT tests foreseen in 2025 in the shadow of the 4 experimental weeks;
 - □ Dedicated HRMT week in 2026;
 - ☐ Installation of a CNT in the SPS linear wire scanner during YETS24-25;
 - Feasibility study for CNT gold ball bonding technique;
 - Assessment of the carbon (or CNT) wire position determination of the future canner using laser system in the lab

LS3 Implementation Phase

- Confirmed installation plans:
 - □ 4 BWS to be installed (2H+2V);
 - Vacuum layout discussed with VSC;
 - □ Cabling request filed, PLAN <u>12763</u>.
- Non confirmed plan and open items requiring resolution/decision: → see next slides
 - ☐ Technical challenges
 - □ Resource gaps
 - Approval/coordination needs, including support from integration, cabling, vacuum and other groups/teams/units



Technical challenges

Use Case 1 : Scanning the full beam

- Measurement that comes for "free" by replacing the standard C wire with a CNT.
- R&D activities:
 - CNT tension tests;
 - CNT assembly on the card by gold ball bonding;
 - Vibrations studies;
 - Braided wires possible solution?



Suitable for SPS full scans at flat top

Use Case 2 : Scanning the Halo only

- Scan from 8.5 to 3.5 σ only, assuming beam fully symmetric.
- R&D activities & open points:
 - How to know where the 3.5sigma is systematically? Coupling with another technique needed.
 - Only half halo distribution;
 - ☐ Improved moving mechanism? Or preloaded?
 - Speed?
 - Wire exposure to beam?
 - Possible test on Hybrid+ calibration tests bench
 - Challenges in the controls absolute position measurement needed.
 - ☐ Signal to background/noise ratio & related quenches?

Suitable for LHC partial scans at flat top

Resource gaps

- R&D on CNTs:
 - PhD position for CNT simulations;
 - □ PhD/GRAD for mechanical design implementation;
 - □ GRAD for CNT position measurement, motion control and electronics design;
- Material budget:
 - ■Prototype WS for CNT;
 - □ Equipment for nanomaterial handling;



Approval/coordination needs, including support from integration, cabling, vacuum and other groups/teams/units

- Depending on the strategy:
 - □SPS installation, full beam scans at extraction:
 - □All supports needed from SPS teams (integration, cabling, vacuum, survey) → feasible within LS3
 - LHC installation, halo beam scans at flat top:
 - □All supports needed from LHC teams (integration, cabling, vacuum, survey) → longer timescale



Post-LS3 Phase

- Features/capabilities that
 - ■will be available after LS3 → none in the LHC
 - ■will need to be developed after LS3 → a proto WS for LHC
- □ Expected timeline for transition from expert to operational mode → NaN ©
- □ Known risks related to schedule and (also picking from 'technical' presentation before) performance → it is an R&D program, fully based on the material quality and characteristics!



Budget (and Other General) Considerations

- Budget status:
 - □ Cost estimates for development and implementation phase vs available budget → see slides above
 - □ Funding gaps to be addressed ? → yep!
- ☐ Long-term budget considerations:
 - Maintenance and operational costs, including manpower → depends on the scenario, could be in the shadow or not
 - □ Possible need for upgrade, anything can be already anticipated → see slides before.



Key Milestones

Phase	Timeline	Deliverables	Dependencies	Budget Status					
Pre-LS3	By 2026	 □ HRMT test □ Material sim □ Material chemistry optimization □ Ball bonding 	No dependencies	Covered					
During LS3	By 2028?	☐ Proto for SPS	R&D dependecies	Not Covered					
Post-LS3	?	☐ Proto for LHC	R&D dependencies	Not Covered					



Conclusions

- Implementing a CNT wire within the new design of the linear wire scanner is feasible but entails R&D;
- ☐ In the SPS: the scanner could work in the full scan modes, LIU intensity and flat top energy;
- In the LHC: the scanner could work potentially from 8.5 to 3.5 σ, but with much more R&D required (timeline beyond LS3).



		2025										2026											2027												
		Q1			Q2			Q3		Q4		Q1		Q2			Q3			Q4			Q1			Q2			Q3			Q4			
		Jan	Feb	March	April	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	April	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb M	arch	April	May .	lune	July	Aug	Sept O	t Nov D
	Design Office - Proto																																		
	Impedance Design																																		
	Proto Fab																																		
PROTO	Impedance Meas																																		
	VSC Acc. Tests																																		
	YETS INSTALLATION																																		
	Impedance feedback with beam?																																		
	Raw material Proto + series																																		
	Design Office - Final Instrument																																		
SERIES	LHC Series Fabrication																																		
	LHC Series Motor test and Calib																																		
	Installation																																		
_	Dummy vacuum chamber design																																		
Dummy	Dummy vacuum chamber production																																		
	Test rig tests - lifetime carriage																																		
Lab tests	Test rig tests - controls with mockup card																																		
	Test rig test with dummy vacuum tank																																		

		_		_	_	_						_													
			2027										2028												
			Q2			Q3			Q4			Q1			Q2			Q3		Q4					
		April	May	June	July	Aug	Sept	Oct	Nov	Dec	Jan	Feb	March	April	May	June	July	Aug	Sept	Oct	Nov	Dec			
	Design Office - Proto																								
	Impedance Design																								
	Proto Fab	Т																							
PROTO	Impedance Meas	Т																							
	VSC Acc. Tests	Т																							
	YETS INSTALLATION	Т																							
	Impedance feedback with beam?																								
	Raw material Proto + series																								
	Design Office - Final Instrument																								
SERIES	LHC Series Fabrication																								
	LHC Series Motor test and Calib																								
	Installation																								
D	Dummy vacuum chamber design																								
Dummy	Dummy vacuum chamber production																								
	Test rig tests - lifetime carriage																								
Lab tests	Test rig tests - controls with mockup card	1																							
	Test rig test with dummy vacuum tank																								

