Expected Contributions to the Taskforce for Detector Layout

F. Sorrentino

Configuration options

- Task force works have just started (kick-off on December 18), too early to distribute possible configurations
 - preliminary set of configurations in ~2 weeks from now
- However the study will address quite different aspects:
- Geometry-independent
 - optical layout, e.g.
 - Number of core/auxiliary optical elements to reduce the amount of cavern excavation
 - IMC folding (triangle -> bowtie) to reduce IMC tunnel length
 - Get rid of filter cavities
 - design of instrument elements
 - reduced footprint of LF TM cryostat
 - reduced height for LF TM towers
 - folded IP
 - active platform
 - reduced height of HF core optics towers (sticking to HF requirements)
- Geometry-dependent
 - Optical layout
 - position of filter cavities and mode cleaner cavities (in main tunnel, in same tunnel, etc.); to reduce the amount of tunnel excavation
 - Arm cavity folding to reduce tunnel length?
 - separate depth for HF and LF
 - design of instrument elements
 - vacuum tank access (lower vs lateral)
 - structure of caverns, e.g. stacked caverns to reduce amount of cavern excavation

Draft workflow -1



Draft workflow - 2



Draft workflow - 3



Interplay with local teams

- Requested connection with both TETI and EMR
 - Permanent liaison within task force
 - to join weekly meetings + in-person workshops
 - to allow a smooth and fast exchange of critical information between task force and local team
 - Periodic (biweekly?) meetings with engineers from the companies in charge of the civil engineering study
 - to validate/amend the set of criteria the task force will propose and use to identify the main cost drivers from the detector layout
 - to properly set up the flexibility envelope of the detector layout for optimal use in the civil infrastructure engineering design