




<mark>16/01/2</mark>025





16/01/2025

Vacuum, Surfaces and Coatings Group

Design, construction, operation, maintenance and upgrade of high & ultra-high vacuum systems for Accelerators and Detectors.


- •Expertise and support on thin-walled vacuum chambers, windows and bellows compensation systems
- •Expertise in vacuum sealing and leak-tightness technology
- •Expertise in dynamic vacuum phenomena
- •Management of the industrial support contract for vacuum work in accelerators
- •Expertise in vacuum control systems, vacuum interlocks and monitoring tools

Coatings, surfaces treatments, surface and chemical analysis for Accelerators and Detectors. Expertise and support in the fields of:

- •Coatings, electroplating and surface cleaning techniques
- •UHV characterization and of material and surfaces
- •Degassing analysis and treatments



Organisation https://espace.cern.ch/HiLumi/default.aspx









WP12 Contribution Vacuum preparations for collaborations

G.Bregliozzi & F.Silvagni Contribution from B.Henrist, P.C.Pinto. S.Fiotakis

Outline

Plug-in modules:

 Status of production, vacuum acceptance test, assembly, and shipping preparation.


Beam screen & Cold Bore:

Plasma cleaning, a-C coating, vacuum acceptance test, insertion procedure.

Extremity vacuum chambers & Ancillaries:

Status of production, vacuum acceptance test, assembly.





	ltem	Needed	Spare	Produced	Fully assembled	Comments
	PIMs	60	6	28	19	All bellows delivered, PIMs manufacturing on going
1 111	DRF inserts	60	6	30	19	Welding and assembly of remaining DRF will start in Q1- 2025
HL-LHC	PROJECT				MD12 Contribution 14	th Callaboration Masting 7 10 October 2024




PIMs assembly status

CRAB	DESTINATION	PIMs ASSEMBLED	TO BE ASSEMBLED
RFD	SPS (prototype)	6	-
RFD	CANADA 1st	3	3
DQW	UK 1st	6	-
DQW	CERN	4	2

- PIMs assembly for 2 cryomodules completed (first cryomodule UK and SPS prototype).
- PIMs assembly for 2 cryomodules on going (first cryomodule Canada and DQW CERN).
- PIMs for remaining 7 cryomodules to be assembled.



PIMs: DRF inserts vacuum acceptance test



Vacuum Acceptance Test on DRF inserts after standard CERN cleaning procedure for UHV application.






PLUG IN MODULES ASSEMBLY


1. Prepare the DRF insert and equipe it with thermalization clamps






2. Prepare the bellow and fix it to the assembly tooling






3. Connect the extension tooling to the DRF insert





4. Extend the DRF insert






5. Put the M4x20 screws inside with washer, but just in position





6. Compress the small bellow and for BS line extend the big one








7. Proceed with the insertion and ensure the insert is in the right position











8. Ensure the DRF is in the right position on both sides and all the holes are perfectly aligned







9. Fix the DRF to the bellow screwing the M4x20 screws inside




10. Uncompress/compress the bellows and remove the extending tooling. Finally fix the insert to the bellow on both sides






PIMs assembly an example





Insertion






Fix the bellow to the DRF with the screws inside


Contribution sides






Final Status & Transport

Assembled PIMs are shipped to UK and Canada in AI boxes with foam. PIM bellows are protected by



-LHC PROJECT



Cryomodule	EDMS number	Cavity
UK 1	3132909	DQW
Canada 1	3132914	RFD

PIMs Assembled ready for installation: 27%












Extremity vacuum chambers (EVC)

Extremity vacuum chambers are assembly with instrumentation and connect each the sector valve with the crab cryomodule

Item	Needed	Spare	Produced	Comments
Ext. Vac. Ch	40	4	44	8 shipped for cryomodule assembly (RFD prototype and DQW 1 UK)





EVC: production status: Completed

Extremity VC have been fully produced (RF inserts and st.steel chamber), assembly is on going.


Component	Asset	Total	% assembled
Extremity vacuum chamber for instrumentation	HCVMACAA_T001	44	50%







Extremity VC assembly





EVC: vacuum acceptance test

Three vacuum acceptance test have been performed:

- Acceptance test RF shield
- Acceptance test vacuum chambers
- Leak test vacuum chambers and ancillaries

Reports attached to asset code HCVMACAA_T001










EVC: vacuum acceptance test

ltem	Total Qty	Completely tested	
Extremity VC	38	18	
DRF shield	38	38	











Particle counting of copper inserts

Sara Domingo Gomez SY-RF-SRF



Introduction

- It was received two copper inserts (LHCVBMCC0018 and LHCVSR__3500001) with oxidation traces on the surface.
- It was performed a rinsing procedure and particle counting test to check cleanroom compatibility.
- The particle counting test was performed again after three days, during this time both pieces were kept in cleanroom under laminar flow, to check the evolution of the oxide of the components.




Preparation procedure

- Test place: Building 252
- Cleanroom: ISO 4
- Operators: G.Pechaud
- The rinsing of pieces in Bldg. 252 is carried out according to the established procedures. For detailed steps and guidelines, refer to the document: Low Pressure Water Rinsing (LPR) in Air (EDMS 2825568)
- 1. Clean all the pieces using clean room tissues soaked in isopropyl alcohol 70%
- 2. Transfer the pieces into the cleanroom ISO Class 4
- 3. Rinse the pieces with Ultra-Pure water (5 bars)
- 4. Rinse with Ethyl Alcohol 99%
- 5. Dry with nitrogen gun
- 6. Keep under laminar flow until dry (Approximately 3 hours)
- 7. Blow and particle count
- 8. Keep under laminar flow for 3 days
- 9. Blow and particle count



Pictures before rinsing





Pictures before rinsing

Mark in RF surface













Pictures after rinsing





1st Particle counting (10/12/2024)

Test place: Bldg. 252 Cleanroom: New daldrop ISO 4 Particle counter: SOLAIR 3200

Operators: G. Pechaud

Pie	ce	ISO		
LHCVSR_	_3500001	1		
LHCVBN	ICC0018	1		
Size of particles Number of particles [µm] (LHCVSR_35000				
0.3	0	0		
0.5 0		0		
1.0	0	0		
5.0	0	0		

All samples comply with the ISO standards for cleanrooms (ISO 14644-1)



2nd Particle counting (13/12/2024)

Test place: Bldg. 252 Cleanroom: New daldrop ISO 4 Particle counter: SOLAIR 3200

Operators: G. Pechaud

Pie	ce	ISO		
LHCVSR_	_3500001	1		
LHCVBN	ICC0018	1		
Size of particles [µm]	Number of particles (LHCVSR_3500			
0.3	0	0		
0.5 0		0		
1.0	0	0		
5.0	0	0		

All samples comply with the ISO standards for cleanrooms (ISO 14644-1)



EVC: Ancillaries

The assembly of the extremity vacuum chamber includes ancillaries and instrumentation








EVC: Ancillaries status


The assembly of the extremity vacuum chamber includes ancillaries and instrumentation. In-house contribution:

Component	Reference	Needed	Spare	In stock
Vacuum Gauge Manifold (1)	LHCVTFGC0001	11	2	19
Vacuum Gauge Manifold (2)	LHCVTFGA0001	11	2	19
VTD- Tee rot. Flange DN40-16CF	Pfeiffer Vac. 420RTR040- 16	10	1	15
VTD-Tee rot flange DN40CF	Pfeiffer Vac. 420RTS040	10	1	15











EVC: Ancillaries status

In-kind contribution:

Component	Reference	Needed	Spare	Purchased by CERN
Sector valve VVGSC DN80	VAT 47238-XE74-ANV1	40	4	40/40
VGPB- Cold cathode gauge	Pfeiffer Vac. IKR070 (PTR20 502)	60	6	36/60*
Non return valve (with rupture disk)	LHCVV0040	20	2	20/20
VGRB Pirani gauge DN16 CF-F	Pfeiffer TR018 (PT R15 011)	20	2	12/20*
VVFMD003- Angle valve T shape	VAT: 54132-GE02_AAY1	20	2	2/20*
lon pump	Sputter Ion – plus starcell 20	20	2	12/20*

* UK-STFC purchased those equipment on his own




Fasteners supplied by CERN

Concerning vacuum and RF equipment fasteners are supplied by CERN

The order related to the fasteners has been partially delivered, but some items have a delay due to the supplier: they will be delivered on week 48.

Ag coating is done at CERN. The global cost of the fasteners is around 3.5K CHF per cryomodule.





Final transport

EVC and Ancillaries are shipped to the UK and Canada in boxes with foam. EVCs are shipped in two per box, ancillaries are shipped with two foam, depending on the beamline, but in the same box. Like PIMs also the EVC come with a traveler.



Summary

Plug-in modules:

- Under production and assembly.
- First PIMs shipped to collaboration.

Beam screen production & a-C coating: Completed

Cold Bore Plasma Cleaning:

- Procedure prepared.
- Possibility to see the system next week in CERN

Extremity vacuum chambers & Ancillaries:

Production finalized, vacuum acceptance tests, leak test and assembly ongoing.



SPSV vs PIM RGA comparison

Stuart Wilde & Oliver Poynton ASTeC Vacuum Solutions Group 20 Aug '24



SPSV baseline


Conclusion


The scans show that any residual gasses are present in both measurements and are therefore not indicative of a leak on the PIMS.

The cart is thoroughly leak tested before each test and there was no leak present.

We originally thought there may be a virtual leak on this pumping system, for the same reasons described by Marco, but could not find any further evidence of this.

However, this type of background is consistent with our other unbaked systems that use similar RGA analysers and may be an artifact of the device.







Chemical treatment for Cu-OFE @ CERN

Surface Treatments:

DEGREASING (15 min)

- 10 20 g/l NGL Cleaning Technology 17.40 spec. ALU III
- 45 55 °C
- Ultrasonic agitation

ELECTROPOLISHING (60 µm)

- 55 % vol. phosphoric acid
- 45 % vol. ethanol
- 1 µm/min etching rate

PASSIVATION (~30 s)

- 70 80 g/l chromic acid
- 3 ml/l sulphuric acid
- Room temperature
- 1 µm/min etching rate

SUBU (chemical polishing) (10 µm)

- 5 g/l sulfamic acid
- 1 g/l ammonium citrate
- 5 % vol. hydrogen peroxide
- 5 % vol. n-butanol
- 70 50 °C
- 0.5 µm/min etching rate

