




# Commissioning of DSS at CRIS



Bram van den Borne, Simone Casci  
CRIS collaboration meeting 2025

# Decay Spectroscopy Station



# Introduction to DSS

## Decay assisted laser spectroscopy

## Laser assisted decay spectroscopy

Measure both decay and ion counts

- Select isomer with certain decay channel
- Purify spectra based on decay<sup>[1]</sup>



- Selectively ionise isomer of interest
- Purify spectra based on hyperfine structure<sup>[2]</sup>

# Introduction to DSS

Decay assisted laser spectroscopy

Laser assisted decay spectroscopy

Measure both decay and ion counts



[1] Koszorús Á., *et al.* Charge radii of exotic potassium isotopes challenge nuclear theory and the magic character of N = 32, *Nature Physics* **17**, 439-443 (2021).

[2] Lynch K.M., *et al.* Decay-assisted laser spectroscopy of neutron-deficient francium, *Phys. Rev. X* **4**, 011055 (2014).

# Introduction to DSS

## Decay assisted laser spectroscopy

## Laser assisted decay spectroscopy

Measure both decay and ion counts

- Select isomer with certain decay channel
- Purify spectra based on decay<sup>[1]</sup>



- Selectively ionise isomer of interest
- Purify spectra based on hyperfine structure<sup>[2]</sup>

## Why tape station?

Move long-lived contaminants away from detector  
No increasing background over time

# Zn beamtime in August 2023

- Test commission DSS tape station on  $^{75}\text{Zn}$





# Shortcomings DSS during beam time

1. Detection efficiency of beta's
  - Plastic scintillator with SiPM
2. Beam diagnostics in detection chamber
  - MicroTOF in detection chamber
3. No CRIS owned controller for timing tape movement yet
  - Arduino for timing control


# New Design DSS



# Design beta detection




# Design detection chamber







# Design gamma detection

- HPGe frame from IDS (long-term storage):
  - Support structure on rails,
  - 3 – 4 HPGe Clovers from IDS
- OSIRIS faces can be removed to fit on the chamber



# Design gamma detection support

- Mechanical support similar to that of DSS tape box
- Height-adjustable
- Safety file to be prepared
- To be manufactured by KUL workshop



# DSS Commissioning

# Commissioning plans 2025

## 22-28 January

- Vacuum test of the new baseplate
- Paint and mount the scintillator
- Offline test of the scintillator
- Assemble scintillator + test vacuum
- Setup Arduino timer for tape move

## 18-26 February

- Setup DSS signals to CRIS DAQ
- Offline test under vacuum with non-resonant laser on

# Commissioning plans 2025

## 22-28 January



- Vacuum test of the new baseplate ●
- Paint and mount the scintillator ●
- Offline test of the scintillator
- Assemble scintillator + test vacuum
- Setup Arduino timer for tape move ●

## 18-26 February

- Setup DSS signals to CRIS DAQ
- Offline test under vacuum with non-resonant laser on

# Plastic scintillator status



- BC-408 plastic scintillator
- Painted with reflective paint
- Glued to Al piece
- 2x copies






# Vacuum problems

- Support designed with vacuum-compatible, weldable feedthroughs
- Scarce quality manufacture by the KU Leuven workshop
  - Leaks from the welds
  - Plate warped in welding process
  - Sides milled with errors of few mm
- Test no epoxy → 0.6 mbar
- Test with epoxy →  $4e-6$  mbar
- Will be milled and fixed by the ISOLDE technical workshop



# Vacuum problems




# Commissioning plans updated

3-18 February (local team)	18-26 February
<ul style="list-style-type: none"><li data-bbox="384 472 1251 572">• Vacuum test of the baseplate from the ISOLDE technical workshop</li></ul>	<ul style="list-style-type: none"><li data-bbox="1378 472 2023 515">• Offline test of the scintillator</li><li data-bbox="1378 558 2135 601">• Setup DSS signals to CRIS DAQ</li><li data-bbox="1378 644 2186 801">• Offline test under vacuum with non-resonant laser on → Efficiency measurements</li></ul>

Thank you for your attention  
Questions?


# Arduino timer setup

- Figured out correct timing for the tape move



# Offline test scintillator

- Bias supply not compatible with SiPM



# NEED FOR Zn

- Plastic scintillator with SiPM
  - Get quote and scintillator from Luxium Solutions (Time: at least 1 month - waiting)
  - Paint with reflective paint from IDS (Time: 1 day)
  - Assemble onto beta detection mount (Time: 1 day)
  - Commission scintillator + SiPM (can be done offline) (Time: 1-2 days)
- MicroTOF in detection chamber
  - Make mount to hold MicroTOF (KU Leuven workshop or 3D printed if  $10^{-6}$  vacuum is fine) (Time: 1-2 weeks)
  - Power supply? (2000 V bias) (Time: ?)
  - Commissioning needed? (Time: during a beamtime when protons are off?)
- Simple Arduino setup for control tape movement
  - Arduino on my desk but feedthroughs + box need to be acquired (Time: 2 weeks)
  - Test and merge with CRIS DAQ (Time: 1-4 days)
- New baseplate
  - Feedthroughs + mechanical parts are on my desk
  - Make baseplate + weld feedthroughs/mechanical parts on it (KU Leuven workshop) (Time: 2-5 weeks)
  - Make collimator (KU Leuven workshop) (Time: 1 week)
  - Assembly (Time: 1-3 week)
    - Test non-resonant light influence on plastic with collimator in place
    - Test vacuum of new baseplate
- IDS gamma array not needed, but would be nice (Time: loads..)
  - Support structure on rails design + assembly
  - Support HPGe structure design + assembly

**Setup at CERN at  
least 2 weeks**

**Other PhD student to work  
on the HPGe array?**