

CMS FSC – ECR

plans for YETS & TS1

M. Albrow (FNAL), D. Cerci (Yildiz), S. Cerci (Yildiz), D. Lazic (Boston),
A. Mestvirishvili (Iowa), S. Ozkorucuklu (Istanbul), A. Penzo (Iowa), M. Pitt (CERN)



Outline

- Introduction and motivation for FSC (re)installation
- Overview of the proposed setup and its status
- Tasks for YETS 2024-2025
- Tasks for TS1 2025
- Discussion


Introduction

The CMS Forward Scintillator Counters (FSC):

- Detectors located in the vicinity of the beampipe and measure showers originating from very forward primary particles interacting with the beampipe
- FSC can tag low mass diffractive processes at the LHC [JINST 4 \(2009\) P10001](#)
- Proposed in Run 1 by the CMS collaboration: [CMS-NOTE-2010-015](#)



Run 1 setup



FSC in Run 1


2012 data taking with FSC:

- FSC was successfully operated in 2012 during high- β^* , pPb and PbPb collisions.

Example of a clean $pp \rightarrow p + (3\text{-jet}) + p$ event with rapidity gap tagged with (empty) FSC

FSC empty during the collision
=
Event with a large rapidity gap

Can be operated during very low
instantaneous luminosity



Sep 2011, courtesy of M. Albrow and S. Popescu



Revival of CMS-FSC

Goal: Operating FSC in the oxygen run

- Scheduled to week 27 in 2025
- CMS aims to utilize most of its forward detectors, including the CMS FSC sub-system

CMS feedback for oxygen run (last LPC on Feb 10th [link](#))

- **ZDC** will be included in the pO, OO and NeNe run
- CMS requests to include **PPS** in the pO run (physics case approved)
 - Running at 0 crossing angle is acceptable (no need for extra crossing plane studies)
 - Some beam-based alignment needed
 - **PPS** planned to be included “p” side (“O” side still under discussion)
 - Possibly also in the OO and NeNe runs (TBD)



Jul			
25	26	27	28
16	23	30	ZDCs out 7
		O ion setting up	VdM program
	TS1		
MD 1		O-O & p-O ions run	

FSC will enhance the physics reach to study diffractive pO interactions

Experimental setup

The CMS Forward Scintillator Counters (FSC):

- A minimal FSC setup is proposed to be revived for the upcoming pO run
- Will be located downstream of the proton beam, at 85 and 114 m from the IP5



CERN
Esplanade des Particules 1
P.O. Box
1211 Geneva 23 - Switzerland

EDMS NO. **3233176** REV. **0.1** VALIDITY **DRAFT**

REFERENCE
LHC-X5FC-EC-0002

Based on template: EDMS 1271880

CERN LHC

Date: 2025-02-20

ENGINEERING CHANGE REQUEST
Re-installation of the CMS Forward Shower Counters in Point 5

BRIEF DESCRIPTION OF THE PROPOSED CHANGE(S):
Proposal for re-install during the TS1 2025 the CMS Forward Shower Counters (CMS FSC) in point 5. These are scintillation counters read out by standard photomultipliers.
Original installation describes in ECR LHC-X5FC-EC-0001
<https://edms.cern.ch/document/1139168/1.0>

DOCUMENT PREPARED BY: Michael Pitt (EP/CMG)	DOCUMENT TO BE CHECKED BY: G. Arduini, M. Barberan, S. Bally, M. Bernardini, O. Beltramo, M. Brugger, O. Boetcher, J. Blanc, J. Bernhard, C. Bertone, G. Canale, J.-P. Corso, C. Coloca, J. Coupard, D. Delikaris, J. De Voght, J. Etheridge, J.-F. Fuchs, J.-M. Fernandez, C. Gaignant, G. Georgiev, G. Girardot, S. Grillot, A. Infantino, R. Jones, D.-L. Lazic, D. Letant-Delrieux, M. Loffredo, M. Marjanovic, S. Pelletier, E. Paulat, H. Mainaud Durand, M. Mulders, S. Roesler, R. Steerenberg, P. Sphicas, C. Tromel, H. Vince, J. Wenninger, M. Wolf, M. Youghil.	DOCUMENT TO BE APPROVED BY: Mike Lamont (On behalf of the LMC) F. Sanchez-Galan (On behalf of the TREX)
--	--	---

DOCUMENT SENT FOR INFORMATION TO:
RZE, ATS Group Leaders.

SUMMARY OF THE ACTIONS TO BE UNDERTAKEN:


- Install signal cables during EYETS 24-25 (EN-EL).
- Dry test of the setup during the EYETS 24-25 (CMS).
- Install the detectors on stations 2 and 3 during TS1 (CMS).
- Removal of the counters will take place after the OO run during the one day allocated for the CMS ZDC removal (July 2025).
- The signal cables to be removed during LS3 (EN-EL).

Note: When approved, an Engineering Change Request becomes an Engineering Change Order.
This document is uncontrolled when printed. Check the EDMS to verify that this is the correct version before use.


Sketch with CMS cavern, FSC locations, and "ZDC bunker" (ZDC DAQ)

Experimental setup

FSC status in the tunnel: 89 m station




LHC-UJ56/C-04R5 captured on 2021-01-12 by
EN-ACE-CL




The 3D integration of the stations
(performed by EN-ACE-INT)

Experimental setup

FSC status in the tunnel: 114 m station



LHC-UJ56/C-04R5 captured on 2021-01-12 by EN-ACE-CL



The 3D integration of the stations (performed by EN-ACE-INT)

Infrastructure

Detectors – using old ones

- Counters were released from RP and tested, the best 2+4 will be installed.

Stands (since run 1)

- Aluminium rails, bolted into the floor, designed so that the upper counters cannot fall and touch the beam pipe
- Can accommodate heater jacket (TBC)

HV cables (since run 1)




- Available since run 1, tested last week

Signal cables

Old were cut ☹️.

Luckily, the FSC is located just near the ZDC bunker.



New signal cables to connect FSC to the ZDC bunker are needed



Plans for YETS 2024-2025

Cabling (week 10, March 05 the latest)

- Task assessed during VIC on 14 Feb (impact [248338](#))
- New cable layout: 2x50m (St#2) 6x27m (St#3)
- Order for new cables + installation was made
- Can be only performed in YETS (unlikely during TS1)
- Exceptional authorisation: [EDMS-3235026](#)



Plans for YETS 2024-2025

Dry tests (week 10)

Impact (draft) [248925](#), duration 2 days (to be scheduled)

- Exercise the installation and removal of the counters


Participation is mandatory for the team responsible for the installation during TS1 2025.

- Safety tests of the assembly (followed by a technician)
- Noise tests (grounding, ...)
- Synchronization with ZDC readout

Signal arrival at FS2(85m), FS3(114m), ZDC(140m) – signal propagation to the bunker (50m, 27m, 60m respectively)

DIMR to be created with the following estimates:

- 50 μSv for individual dose
- 250 person. μSv for collective dose



Plans for TS1 2025

FSC installation (week 27)

Work Dose Planning prepared ([4325/1](#)):

- Safe zones assigned
- Limited time of work near the D1 magnet
- The Pb shield can be for FSC team disposal
- RP technician will follow up the installation



Jul			
25	26	27	28
16	23	30	ZDCs out 7
		O ion setting up	VdM program
	TS1		
MD 1		O-O & p-O ions run	

Installation:

- Performed by two teams, each team comprise of 2 members
- Following the installation noise tests to be performed from the bunker
- The installation work will be done in coordination with the CMS ZDC team



Discussion

- As the cabling work can be performed, the CMS-FSC can be prepared for the oxygen run (**urgent**).
- A few days of testing during the YETS 2024-2025 will be required to prepare the setup for the installation during TS1.
- CMS-FSC to be installed during TS1 for the pO/OO runs and will be removed afterward.

Backup

