



Lessons learned (Past, Present and Future) in CTF3

Frank Tecker – CERN

- Motivation
- CTF3 Preliminary Phase
- Present CTF3 (up to DL)
- Future CTF3 (CR and beyond)
- Conclusion





CLIC-related key issues



as pointed out by ILC-TRC 2003

Covered by CTF3

R1: Feasibility

- R1.2: Validation of **drive beam generation** scheme with **fully loaded linac** operation
- R1.1: Test of damped **accelerating structure** at design gradient and pulse length
- R1.3: Design and test of damped ON/OFF **power extraction structure**


R2: Design finalization

- R2.1: Developments of structures with hard-breaking materials (W, Mo...)
- R2.2: Validation of stability and losses of DB decelerator; Design of machine protection system
- R2.3: Test of relevant linac sub-unit with beam
- R2.4: Validation of drive beam 40 MW, 937 MHz Multi-Beam Klystron with long RF pulse *
- R2.5: Effects of coherent synchrotron radiation in bunch compressors
- R2.6: Design of an extraction line for 3 TeV c.m.


Covered by EUROTeV

* *Feasibility study done - need development by industry.*



N.B.: Drive beam acc. structure parameters can be adapted to other klystron power levels




CLIC Drive Beam generation




Drive beam time structure - initial



Drive beam time structure - final







CTF 3



- demonstrate **Drive Beam generation**
(fully loaded acceleration, bunch frequency multiplication 8x)
- Test CLIC **accelerating structures**
- Test **power production structures (PETS)**







CTF3 Evolution



- 2003 Injector + part of linac
- 2004 Linac + 30 GHz test stand
- 2005 Delay Loop
- 2006 TL1 + Combiner Ring
- 2007 - 2009 New photo-injector, TL2 + CLEX





CLIC drive beam scheme




- **Very high gradients** possible with NC accelerating structures at high RF frequencies (30 GHz \rightarrow 12 GHz)
- Extract required high RF power from an **intense e- “drive beam”**
- Generate **efficiently** long beam pulse and compress it (in power + frequency)

800 Klystrons
Low frequency
High efficiency



Long RF Pulses
 P_0, ν_0, τ_0

Power stored in
electron beam




Electron beam manipulation
Power compression
Frequency multiplication

Power extracted from beam
in resonant structures

144000
Accelerating Structures
High Frequency - High field



Short RF Pulses
 $P_A = P_0 \times N_1$
 $\tau_A = \tau_0 / N_2$
 $\nu_A = \nu_0 \times N_3$




Drive beam generation basics




Efficient acceleration


Full beam-loading
acceleration in TW sections



Frequency multiplication

Beam combination/separation
by transverse RF deflectors






Demonstration of frequency multiplication






CTF3 - PRELIMINARY PHASE 2001/2002

Successful low-charge demonstration of electron pulse combination and bunch frequency multiplication by up to factor 5



Streak camera image of beam time structure evolution







Combination by RF deflectors in a ring



● combination **factors** up to 5 reachable in a ring







Combination setup



- Developed a setup procedure to optimize combination
- 5 parameters
 - **Amplitude** and **phase** in each deflector
 - **RF frequency** (no wiggler for path length tuning)
- Monitor **trajectory** differences over various turns







Combination results




- demonstrated for factors 4 and 5 (also 2 and 3)

- beam current accumulates



- intensity profile (Streak Camera)





4 pulses injected




Combination factor 5



- bunch distance 333 ps \rightarrow 67 ps
- frequency 3 GHz \rightarrow 15 GHz






Isochronicity Tuning




- ring optics needs to be **isochronous** to keep short bunch length
=> high power extraction efficiency
- Streak Camera observations




non-isochronous – 2nd turn




isochronous – 60th turn



$\frac{\Delta p}{p}$
 δ
x
↑




→ Time




Bunch spacing variations



- Bunch spacing variations would reduce RF extraction efficiency
- variations were observed (for large orbit oscillations)
- theoretically understood, vanish when $D=D'=0$
- no deterioration of the power production







Bunch frequency monitor




- Analyses different harmonics of 3 GHz
- target frequency increases
- other decrease
- short pulse length difficult


9 GHz




12 GHz




15 GHz



18 GHz







Fully loaded operation



- **efficient** power transfer from RF to the beam needed


“Standard” situation:


- **small** beam loading
- power at structure exit lost in load



“Efficient” situation:

- high beam current
- **high** beam loading
- no power flows into load
- $V_{ACC} \approx 1/2 V_{unloaded}$





Fully loaded operation




- Disadvantage: any current variation changes energy gain


$$\frac{dV / V}{dI_{beam} / I_{beam}} = - \frac{I_{beam}}{I_{opt}}$$


at full loading, 1% current variation = 1% voltage variation

- Requires **high current stability**
- **Energy transient**




Time resolved beam energy spectrum measurement in CTF3







“Full” beam loading operation in CTF3




Dipole modes suppressed by slotted iris damping (first dipole's Q factor < 20) and HOM frequency detuning



RF signals / output coupler of structure



Beam current	4 A
Beam pulse length	1.5 μ s
Power input/structure	35 MW
Ohmic losses (beam on)	1.6 MW
RF power to load (beam on)	0.4 MW
<u>RF-to-beam efficiency</u>	<u>~ 94%</u>




Full beam loading operation in CTF3 - Demonstration for CLIC operation




CLIC: no RF pulse compression
length of the drive beam pulse: 140 μs

Demonstration at CTF3:



Setup: no RF pulse compression for this experiment (with exception of MKS03)
1.5 μs long pulses
Adjust RF power and phase and beam current, that fully loaded condition is fulfilled




analog
signal

measured RF-to-beam
efficiency:


95.3 %

Theory: 96%

(~4 % ohmic losses)




30 GHz test line




High-gradient test stand, CTF2

CTF3 linac

PETS branch









Power extraction structure PETS




- must extract efficiently >100 MW power from high current drive beam
- periodically corrugated structure with low impedance (big a/λ)
- ON/OFF mechanism




PETS ON/OFF mechanism



Reconstructed from GDFIDL data
PETS output pulse envelopes






30 GHz power production (PETS)



vacuum tanks containing Power Extraction Transfer Structure




17m waveguide with 5 bends but low-loss (85% transmission) (Russian collaboration)







First production of 30 GHz RF pulse for nominal CLIC gradient and pulse length in 2005




high power load / accel. structure



CTF3 schedule 2006




- almost continuous operation all year
- Split between RF production and commissioning
- 1st period: DL commissioning / 30 GHz nights and weekends
- 2nd period: only 30 GHz / TL1+CR installation
- 3rd period (very short!): TL1+CR commissioning / 30 GHz nights + weekends




30 GHz power testing



- testing needs large amount of accumulated running time
- RF **conditioning** largely **automated**
- **CCC** (CERN Control Center) **operators** supervise **CTF3** during night and week-ends
- **Six** prototype accelerating **structures tested** in 2006
- **Installation + testing time** per structure have been **reduced**
- **Switch over** from and to commissioning became routine and **very fast**




A.Rodriguez



Bunch length manipulations



- Compression for linac (especially PETS running)
- Tunable bunch length chicane
- Isochronous rings, TL1
- Tunable TL2






Bunch length manipulation in the INFN chicane




Accelerating structures
@Girder 15

4 Bends Frascati
Chicane


Delay Loop




RF pick-up



Changing the phase
of Klystron 15 to
insert a time to
energy correlation
within the bunch



Convert energy
correlation into path
length modification
and time correlation




Measure the Bunch
frequency spectrum

Klystron
 $V(t)$

t


- On-crest Acceleration - the bunch length is conserved through the chicane
- Positive Off-crest Acceleration - the bunch gets shorter
- Negative Off-crest Acceleration - the bunch gets longer

A. Dabrowski, January 16 2007




Bunch length measurement result

Maximum of FFT vs phase MKS15




measurement 6.6.2006, LO at 5350 MHz



- Data analysed using a self calibration procedure, by means of Chi square minimization.
- 16 measurements (corresponding to the 16 phases on MKS15)
- Fit done with lowest 3 mixing stages.
- 19 free parameters fit → 3 response amplitudes and 16 bunch lengths

$$\chi^2 = \sum_j^{16} \sum_i^3 (A_i e^{-(2\pi f_i)^2 (\sigma_j)^2} - y_{ij})^2$$

A. Dabrowski, January 16 2007



CTF3 Delay Loop



CLIC TEST FACILITY (CTF3)

WIGGLER

DELAY LOOP

QUADRUPOLE AND SEXTUPOLE

TRANSFER LINES

CHICANE


SEPTUM CHAMBER

RF DEFLECTOR

INFN
Istituto Nazionale di Fisica Nucleare
National Institute of Nuclear Physics

SIM 14-11-2005 A.ZOLLA


The main image is a 3D cutaway diagram of the CLIC Test Facility (CTF3) layout. It shows a large, yellow, U-shaped structure representing the delay loop. Various components are labeled and shown in cutaway views, including a wiggler, quadrupole and sextupole magnets, transfer lines, a chicane, a septum chamber, and an RF deflector. Several inset photographs show the physical components in a laboratory setting. The CERN logo is in the top right corner of the diagram area, and the INFN logo is in the bottom right corner.




Delay Loop Principle




- double repetition frequency and current
- parts of bunch train delayed in loop
- RF deflector combines the bunches






Delay Loop operation



- 1.5 GHz sub-harm. bunching system

- 1.5 GHz RF deflector






SHB system – Phase coding




- Key parameters for the SHB system:
- 1) time for phase switch < 10 ns (15 1.5 GHz periods)
 - 2) satellite bunch population < 7 %
(particles captured in 3 GHz RF buckets)

phase switch:




Phase switch is done within eight 1.5 GHz periods (<6 ns).


satellite bunch population:




Satellite bunch population was estimated to ~8 %.




Delay Loop – first recombination 2005







Delay Loop – full recombination




- 3.3 A after chicane \Rightarrow < 6 A after combination (satellites)




Combiner Ring






Combiner ring - latest status



We make up to a few 100 turns!


- Nominal isochronous optics
- RF injection
- short RF pulse in deflector that it's only seen by the beam at injection.



Switching on the SHBS (2 out of 3)




We got immediately the same Transmission in CR!



Combiner ring - latest status




Latest results from last week ... we **recombine** (factor 2)!



Second turn of second pulse and partly third turn of first pulse

Recombination – factor 2


- nominal isochronous optics
- energy ~ 115 MeV
- RF injection (2nd RF deflector off – so far)
- set up of the path length in CR with wiggler




CLEX – Two beam test stand




- High-power test of PETS – first tests of CLIC (lengthened) prototypes
- 12 GHz high-power test of accelerating structures
- Two beam acceleration of ‘main’ beam from CALIFES
- Measurement of breakdown kick, breakdown current meas. planned
- High-power test of PETS on/off mechanism
- Operation of CLIC module






CLEX – Test beam line



- High energy spread beam transport, low losses (Bench mark simulations)
- RF Power Production, Stability (End Energy <50%, 2.6 GW of RF power)
- Alignment (Test procedures for BBA) (100 microns alignment for PETS)
- Drive Beam Stability, Wake field (no direct measurement of the wake fields)
- ‘Realistic’ show case of a CLIC decelerator
- Industrialization of complicated RF components



CLIC Decelerator vs TBL



CLIC

$$E = 2.37 \text{ GeV}$$

$$I \sim 80 \text{ A}$$

$$P/\text{pets} \sim 170 \text{ MW}$$

$$W_{\text{ext}} = 90 \%$$

TBL

$$E = 0.15 \text{ GeV}$$


$$I = 30 \text{ A}$$

$$P/\text{pets} = 150 \text{ MW}$$

$$W_{\text{ext}} = 55 \% \text{ (16 cells)}$$

Very similar PETS for both machines,
32 A needed to produce nominal Power/PETS


$W_{\text{ext}} = 80 \%$ (23 cells) might be possible with some beam
improvements



TBL




2007/2008



Total: ~6 m






Tentative TBL-Schedule (S. Doebert)



Jul-Dec 06	Jan-Mar 07	Apr-Jun 07	Jul-Sep 07	Oct-Dec 07
Define module , Diagnostics, 12 GHz PETS	Fabrication of prototypes			
	Test of Prototypes			

Jan-Mar 08	Apr-Jun 08	Jul-Sep 08	Oct-Dec 08
Install 1 Module		Install a bit more ?	
Series production			

Jan-Mar 09	Apr-Sep 09	Oct-Dec 09	Jan-Mar 10	Apr-Jun 10
Install up to 8 PETS 1.2 GW	Run with 8 PETS 1.2 GW		Install remaining 8 PETS	Run with 16 PETS 2.4 GW



Conclusion



- fully loaded operation demonstrated and routinely used
- bunch train combination principle shown (Prel.Phase)
- phase coding of bunches and full current DL operation
- full current CR combination on a good way
- => fully loaded drive beam generation well covered

- extensive high power RF testing (now automated)

- different tests in CLEX from 2008