


# ***CLIC Collaboration Meeting***


***CERN, November 3-4, 2011***

## ***X-band activities at Sincrotrone Trieste***

***Presented by***

***Gerardo D'Auria***







**XL5 Klystron  
developed by  
SLAC**

**HV modulator:  
PFN + thyratron,  
developed in  
house**

**LLRF system:  
based on the  
present S-band  
system (developed  
in house)  
+  
X-band front-end,  
3-12 GHz up/down  
conversion  
chassis, supplied  
by industry.**





Measure	P1:top(C1)	P2:base(C4)	P3:pkpk(F2)	P4:pkpk(C3)	P5:--	P6:mean(C1)
value	272 V	-375.02 KV	174.9 V <sup>2</sup> s	960 V		
mean	273.17 V	-375.6687 KV	174.883 V <sup>2</sup> s	958.1 V		
min	272 V	-377.26 KV	174.6 V <sup>2</sup> s	896 V		
max	277 V	-372.34 KV	175.0 V <sup>2</sup> s	1.07 KV		
sdev	1.08 V	693.8 V	87 mV <sup>2</sup> s	49.2 V		
num	42	42	42	42		
status	✓	✓	✓	✓		

C1 DC1M 50.0 V/div  
-171.0 V offset

C4 DC1M 10.0 KV/div  
374.06 KV

Timebase -744 ns  
200 ns/div


Trigger C1|DC  
Stop 227.5 V

5.00 KS 2.5 GS/s

LeCroy

10/6/2011 12:07:32 PM

File Vertical Timebase Trigger Display Cursors Measure Math Analysis Utilities Help



Measure	P1:top(C1)	P2:base(C4)	P3:max(C1)	P4:max(C2)	P5:max(C4)	P6:mean(C1)
value	289.6 V	-391.7 KV	295 V	66.6 V	65 KV	
mean	289.676 V	-392.348 KV	292.59 V	66.440 V	65.60 KV	
min	289.2 V	-392.9 KV	292 V	66.0 V	65 KV	
max	289.9 V	-391.7 KV	295 V	66.6 V	68 KV	
sdev	214 mV	518 V	1.06 V	277 mV	952 V	
num	8	8	8	8	8	
status	✓	✓	✓	✓	✓	

Below the table are two sets of parameter settings:

- C1 DC1M**: 50.0 V/div, -153.0 V offset
- C4 DC1M**: 90 KV/div, 217.0 KV
- Timebase**: -14.6  $\mu$ s, 5.00  $\mu$ s/div, 5.00 kS, 100 MS/s
- Trigger**: C1|DC, Normal Edge, Positive


LeCroy

10/21/2011 6:52:47 AM


## Trieste XL5\_1B test report 06-10-2011

					Calorimetric measurements			
Charging voltage	Anodic Voltage	Anodic current	Micro Perveance	Cathode ion pump voltage ripple	Body power	Collector power*	Beam losses	Transm. efficiency
<b>V<sub>Fug</sub> (V)</b>	<b>V<sub>k</sub> (V)</b>	<b>I<sub>k</sub> (A)</b>	<b>μP</b>	<b>V<sub>CIP</sub> (KV)</b>	<b>B<sub>P</sub> (W)</b>	<b>C<sub>P</sub> (W)</b>	<b>B<sub>L</sub>(%)</b>	<b>η<sub>eb</sub>(%)</b>
3.22E+04	3.36E+05	2.32E+02	1.19E-06	1.4E+03	16	1,585	1.009	98.991
3.34E+04	3.46E+05	2.41E+02	1.18E-06		17	1,727	0.984	99.016
3.46E+04	3.54E+05	2.50E+02	1.19E-06	1.5E+03	20	1,835	1.090	98.910
3.58E+04	3.66E+05	2.63E+02	1.19E-06		20	1,970	1.015	98.985
3.64E+04	3.70E+05	2.68E+02	1.19E-06		21	2,025	1.037	98.963
3.76E+04	3.82E+05	2.78E+02	1.18E-06	1.6E+03	22	2,160	1.019	98.981


\* The collector power has been calculated in two different modes with almost the same results:  
 a) calorimetric measurements;  
 b) considering the V and I pulse integrals.





## X-band front-end (supplied by industry)





## S-band LLRF S-band system (developed in house)











***RF station:***

- XL5 klystron fully tested in diode mode up to 390 KV (@ 10 Hz) and 350 KV (@ 50Hz).
- RF activation of the tube just started.
- RF power measurements made with:
  - a. direct power measurements (bi-directional coupler/power meter);
  - b. calorimetric measurements.

***Accelerating structure and WG circuit:***

- The accelerating structure and the waveguide system are installed.
- Their RF conditioning is expected for the second half of November.

## Thanks to:

**J.P. Eichner, A. Haase, D. Sprehn, A. Vlieks, SLAC;**

**G. Riddone, M. Filippova, S. Lebet, CERN;**

**M. Dehler, PSI;**

**F. Peauger, CEA Saclay;**

**C. Serpico and all the members of the linac group at  
Sincrotrone Trieste.**