

Micromegas SDHAL TB status and plans

RD51/WG7 mini-week 21-23 Nov. 2011, CERN M. Chefdeville, LAPP, Annecy

- Status
 - Detectors
 - Characterisation
- Plans
 - Next prototypes
 - Test Beams



1 m² prototype tested in 2011

- Reminder on 2010 prototype
 - HARDROC2 ASIC: 20 ns shaping
 - 5 Bulk of 32x48 cm²
 - $_-\,$ pads of 1 cm^2
 - $_$ Thickness of 12 mm
- 2011 prototype
 - MICROROC: 50-200 ns shaping
 - 6 Bulk: 96×96 = 9216 pads
 - $_{-}$ Dead area < 2 %
 - Improved PCB
 - $_$ Better EMC to minimize X-talk
 - Possbility to by-pass single chips
 - _ Improved spark protections
 - _ Digital + Analogue readout
 - Improved mechanics: thickness of 10 mm
 - $_{\rm -}\,$ Thinner mask 3 to 2 mm
 - $_$ Gas tightness between ASU & cathode
 - \rightarrow Removable 1 mm thick chamber cover







August 2011 test beam

- After test at LAPP, good understanding of the detector
 - Noise level under control, successful RAMFULL runs
 - $\,$ $\,$ $^{55}\mbox{Fe}$ and cosmic signals seen
 - 3 thresholds under control
 - \rightarrow Ready for beam
- SPS/H4 3-22 August
 - 6 days standalone CALICE
 - 13 days multi-users RD51
 4 set-ups

- Measurements with muons (150 GeV/c)
 - Define working point of detector (voltage, shaping & threshold scans)
 - Measure efficiency, multiplicity, uniformity (2/3 of area)
 - Demonstrate RAMFULL operation in beam conditions
 - Measure multiplicity at various beam incidence angle
- Measurements with pions (150 GeV/c)
 - Landau distribution with analogue readout of low gain shaper
 - Shower signals with 3 thresholds
 - Validate spark protection by operation at (too) high gas gain





Setup (I)

- Trigger: 3 scintillators, overlap area of 6x16 cm²
- Tracking
 - Pad telescope of LAPP (Gassiplex)
 3 chambers of 6x16 pads of 1 cm²
 3 mm drift gap
 - Strip telescope of NCSR Demokritos, NTUA (Gassiplex) (RD51 Micromegas telescope)
 6 chambers with 10 cm XY strips of 250 µm pitch
 → active area of 2.4x2.4 cm²
 7 mm drift gap
 - DAQ: VME ADC + Sequencer and CENTAURE DAQ
- 1 m2 prototype with 144 Microroc
 - DAQ: (interDIF + DIF + CCC) and LAPP LabView DAQ
 - New gas: Ar/CF₄/iso 95/3/2, so-called "T2K gas"
- Hardware Synchronization telescopes/prototype with busy handshake between VME sequencer and CCC





Setup (II)



Some preliminary results

- During 18 days: about 6 Mevents
 - 85~% of muons
 - 15 % of pions



→ Working settings 200 ns shaping, 0.7 fC threshold, V_{mesh} = 390V, Gain = 3000, V_{drift} = 480V efficiency = 98 %, multiplicity = 1.1, noise rate = 0.1 Hz/channel

More details in WG1 session

October 2011 test beam

- Join CALICE test beam in H8
 - 3-12 October
 - GRPC/steel DHCAL
 - Occupy slot 47 (~ 5 interaction length)
- Goals
 - Validate prototype operating point in showers
 - Measure shower profiles using GRPC data
- Unfortunately CALICE DAQ very unstable
 - ightarrow Data taking in standalone
- Collected data: about 1 Mevents
 - 80 GeV/c pions ~ 50k evts
 - 60 GeV/c pions ~ 600k evts
 - . 100 GeV/c pions ~ 130k evts
 - . 120 GeV/c pions ~ 120k evts
 - . 150 GeV/c pions \sim 70k evts
 - 180 GeV/c pions ~ 60k evts





12 mm gaps!

October 2011 test beam

- Join CALICE test beam in H8
 - . 3-12 October
 - GRPC/steel DHCAL
 - Occupy slot 47 (~ 5 interaction length)
- Goals
 - Validate prototype operating point in showers
 - Measure shower profiles using GRPC data
- Unfortunately CALICE DAQ very unstable
 - ightarrow Data taking in standalone

Collected data: about 1 Mevents

- 80 GeV/c pions ~ 50k evts
- 60 GeV/c pions ~ 600k evts
- 100 GeV/c pions ~ 130k evts
- 120 GeV/c pions ~ 120k evts
- 150 GeV/c pions ~ 70k evts
- 180 GeV/c pions ~ 60k evts













8

Future plans

- Next m² prototypes:
 - 2nd MICROROC constructed in October 2011
 - _ Begin tested at LAPP (Readout, HT, gas, noise, cosmics)
 - New batch of chips available beginning of next year
 → construction of 1 to 3 prototypes
 at least 1 with resistive coatings (ANR SPLAM)
- 2012 TB goals
 - RD51: Comparison resistive/standard prototypes
 - _ Efficiency & multiplicity to MIPs, position scan \rightarrow 1 week
 - $_$ Effect of sparks (pions), beam rate & HV scans \rightarrow 1 week
 - \rightarrow 2 weeks at the end of the year
 - CALICE: test of all available planes inside structure (Fe or W)
 - $_$ Join physics run of a complete HCAL \rightarrow No beam privileges
 - _ DAQ not ready yet \rightarrow Uncertain at this moment
 - ightarrow Beam schedule will depend on state of CALICE DAQ