



LHC Injectors Upgrade



**THE
LHC INJECTORS UPGRADE
("LIU") PROJECT**

R. Garoby for the LIU Project Team

LIU-2011 November 25, 2011 CERN






- **Introduction**
- Project Management
- Anticipated Performance Goals
- Planning
- Summary



Goals & Means

Mandate

“The LHC Injectors Upgrade should plan for delivering reliably to the LHC the beams required for reaching the goals of the HL-LHC. This includes LINAC4, the PS booster, the PS, the SPS, as well as the heavy ion chain...”



Implementation

The LIU Project will:

- Analyze the status of the injectors and the HL-LHC requirements,
- Propose an upgrade path for the injectors, exploiting the work done by the Task Forces on the „PSB energy upgrade“ and „SPS upgrade“ and by the Working Group on the SPS upgrade,
- Organize the upgrades (WBS with resources and planning) and take care of their implementation,
- Take care of hardware and beam commissioning.



Basic Principles

To increase performance (soon extended for heavy ions)

Brightness ↗

- ⇒ **Increase injection energy in the PSB from 50 to 160 MeV, Linac4 (160 MeV H⁻) to replace Linac2 (50 MeV H⁺)**
- ⇒ **Increase injection energy in the PS from 1.4 to 2 GeV, increasing the field in the PSB magnets, replacing power supply and changing transfer equipment**
- ⇒ **Upgrade the PSB , PS and SPS to make them capable to accelerate and manipulate a higher brightness beam (feedbacks, cures against electron clouds, hardware modifications to reduce impedance...)**

**To increase reliability and lifetime (until ~2030!)
(tightly interleaved with consolidation)**

- ⇒ **Upgrade/replace ageing equipment (power supplies, magnets, RF...)**
- ⇒ **Procure spares**
- ⇒ **Improve radioprotection measures (shielding, ventilation...)**



Baseline Upgrade Actions

- Construction of LINAC4

- Upgrades of PSB, PS and SPS

+ Consolidation...

«Typical» list
of Work Units

PS/SPS	Management
	Beam dynamics
	Magnets
	RF systems
	Power converters
	Beam instrumentation
	Beam intercepting devices
	Installation
	Civil Eng.
	Radioprotection
	Machine interlocks
	Alarms
	Access system
	Survey
	Commissioning
Dismantling	

**All equipment
and service
groups are
involved!**



- Introduction
- **Project Management**
- Anticipated Performance Goals
- Planning
- Summary



LIU Project Mandate (continued)

...

The project co-ordinator will have the responsibility for the project management (WBS, technical co-ordination and integration, manpower and budget agreement with the departments as well as budget and timescale control). They will report on a regular basis to the Director of Accelerators and Technology. The executive role for manpower and budget for the projects/studies remains with the technical groups in the departments.

LIU Project Planning and Costing

PBS

① Project / Product Breakdown Structure

WBS

② Work Breakdown Structure

OBS

③ Organization Breakdown Structure

RBS

④ Resource Breakdown Structure

RRM

⑤ Resource Responsibility Matrix

WUD

⑥ Work Unit Dictionary

PGC

⑦ Project Gantt Chart :-)

Source: Project Management case study
– P. Bonnal, M. Meddahi



Project Organization Breakdown Structure

Director of Accelerators and technology - Steve Myers

LIU Project team

Roland Garoby (Project Leader) - Malika Meddahi (Deputy) - Brennan Goddard (LIU-SPS machine coordinator) - Simone Gilardoni (LIU-PS machine coordinator) - Klaus Hanke (LIU-PSB machine coordinator) - Maurizio Vretenar (Linac4 Project Leader)- Laurette Ponce (Project Safety Officer)-Django Manglunki (LIU-Ion chain coordinator)

LIU-PSB coordination team

K.Hanke – Activity leader
 B.Mikulec – Deputy
 V.Raginel – Scientific secretary
<https://espace.cern.ch/liu-project/liu-psb/>

LIU- PS coordination team

S.Gilardoni – Activity Leader
 H. Damerau– Deputy and Scientific secretary
<https://espace.cern.ch/liu-project/liu-ps/>

LIU-SPS coordination team

B.Goddard
 E.Shaposhnikova – Deputy
 G.Rumulo – Scientific secretary
<https://espace.cern.ch/liu-project/liu-sps/default.aspx>

LIU-Project Safety coordination

L. Ponce

Linac4 Project

M.Vretenar
<http://linac4-project.web.cern.ch/linac4-project/>

LIU Administrative Support: Cécile Noels, Nadine Audrey. Project Support: Pierre Bonnal, Sylvain Weisz, Tadeusz Kurtyka - EVM coordinators: De Jonghe, Benoît Daudin

<https://edms.cern.ch/> - by EDMS team and Project Support Office

Templates and document handling and lifetime

Indico

Description

The purpose of this document is to explain how, in the framework associated projects, information is produced, distributed and archived, and to define a common and coherent visual identity.



Work Breakdown Structure


20111003 - EMDS ID 1146814			
LIU Work Breakdown Structure			
1	LIU project		Roland Garoby
	LIU 1	62011	Management activities (EVM, APT, MTP, EDMS...)
	LIU 2		General planning
	LIU 3		Safety
	LIU 4		Quality assurance
	LIU 5		Design office-Fabrication-Subcontracting-Materials (EN-MME)
	LIU 6		Integration
	LIU 7		Project team meetings
	LIU 8	62011	Reviews - Conferences
2	LIU-PSB		Klaus Hanke
	LIU-PSB 1	Management	Klaus Hanke
	LIU-PSB 2	PSB Beam dynamics	Christian Carli
	LIU-PSB 3	Magnets	Antony Newborough
	LIU-PSB 4	RF systems	Alan Findlay
	LIU-PSB 5	Power Convertors	David Nisbet - Serge Pittet
	LIU-PSB 6	Beam instrumentation	Jocelyn Tan
	LIU-PSB 7	Beam Intercepting Devices	Oliver Aberle - Alternate Alessandro Masi
	LIU-PSB 8	Vacuum System	Jan Hansen
	LIU-PSB 9	LINAC4 to PSB transfer line and PSB injection systems	Christian Carli - Wim Weterings
	LIU-PSB 10	PSB Extraction system and PSB-PS transfer line	Wolfgang Bartmann - Jan Borburgh
	LIU-PSB 11	Controls	Steen Jensen
	LIU-PSB 12	Electrical Systems	Davide Bozzini, Slawomir Olek
	LIU-PSB 13	Cooling and Ventilation	Mauro Nonis
	LIU-PSB 14	Installation, Transport and handling	Ingo Rühl
	LIU-PSB 15	Civil Engineering	Luz Anastasia Lopez-Hernandez
	LIU-PSB 16	Radiation Protection	Joachim Vollaire
	LIU-PSB 17	Machine Interlocks	Bruno Puccio
	LIU-PSB 18	Alarms	
	LIU-PSB 19	Access Systems - Doors	
	LIU-PSB 20	Survey	Tobias Dobers
	LIU-PSB 21	Commissioning and Operation	Bettina Mikulec
	LIU-PSB 22	Dismantling	
3	LIU-PS		Simone Gilardoni
4	LIU-SPS		Brennan Goddard



Budget Control – (APT by J. De Jonghe, B. Daudin)

WUs dictionary defined for all LIU machines - resources, schedule and deliverables

LIU	PPA	Project	BC	Group	WBS
Management	Follows, visitors, associates, travel etc.	PBU-PRJ	LIU	62011	BE-HDO 1.1; 1.8
PSB	Management (M resources)	PBU-PRJ	LIU-PSB	67020	BE-OP LIU-PSB 1
	Beam Dynamics	PBU-PRJ	LIU-PSB	61020	BE-ABP LIU-PSB 2
	Magnets	PBU-PRJ	LIU-PSB	99281	TE-MSC LIU-PSB 3
	Magnetic Measurements	PBU-PRJ	LIU-PSB	69020	BE-RF LIU-PSB 4
	RF	PBU-PRJ	LIU-PSB	Existing* 55152	EN-STI LIU-PSB 7
	L4 on LBE/LBS and shielding	PBU-PRJ	LIU-PSB	63125	EN-STI LIU-PSB 7
	head and tail dump and the H0/H- dump	PBU-PRJ	LIU-PSB	99237	TE-EPC LIU-PSB 5.2
	Power Converters (PSB) - New MPS building	PBU-PRJ	LIU-PSB	99238	TE-EPC LIU-PSB 5.2
	Power Converters (PSB) -MPS and MPS	PBU-PRJ	LIU-PSB	99239	TE-EPC LIU-PSB 5.2
	Power Converters (PSB) - ALG1&2 upgrade	PBU-PRJ	LIU-PSB	99240	TE-EPC LIU-PSB 5.2
	Power Converters (PSB) - Transfer bendings	PBU-PRJ	LIU-PSB	Existing* 99271	TE-EPC LIU-PSB 5.1
	Power Converters (Injection)	PBU-PRJ	LIU-PSB	64020	BE-BI LIU-PSB 8
	Vacuum System	PBU-PRJ	LIU-PSB	67021	BE-OP LIU-PSB 21
	Beam Instrumentation	PBU-PRJ	LIU-PSB	Existing* 66020	EN-CO LIU-PSB 11
	Commissioning	PBU-PRJ	LIU-PSB	54247	EN-EL LIU-PSB 12
	Injection	PBU-PRJ	LIU-PSB	53661	EN-CV LIU-PSB 13
	Extraction, Transfer	PBU-PRJ	LIU-PSB	99236	TE-ABT LIU-PSB 10
	Controls	PBU-PRJ	LIU-PSB	54360	EN-HE LIU-PSB 14
	Electrical Systems	PBU-PRJ	LIU-PSB	61021	BE-ABP LIU-PSB 20
	Cooling & Ventilation	PBU-PRJ	LIU-PSB	99290	TE-MPE LIU-PSB 17
	RP and Safety	PBU-PRJ	LIU-PSB	89122	EN-MEF LIU-PSB 1.5
	Transport and Handling	PBU-PRJ	LIU-PSB		
	Survey	PBU-PRJ	LIU-PSB		
	Machine Interlocks (added to first budget)	PBU-PRJ	LIU-PSB		
	Integration studies (added to first budget)	PBU-PRJ	LIU-PSB		
	PSB Total				



LIU-PSB 6: Beam instrumentation

Short Workunits: 1- 3 of 3. Page size: 30

Workunits for year : 2011, for WBS LIU-PSB 6: Beam instrumentation

ID	Description	WBS	Holder	Start Date	Finish Date
91546	Fast BLMs at injection DUMP	LIU-PSB 6	C. Zamantzas (BE-BI)	01-May-2011	01-Jan-2014
91547	Screens at extraction BT.MPV10+30	LIU-PSB 6	D. Gerard (BE-BI)	01-Jun-2011	01-Sep-2013
91542	Watchdog DRS TMD (4 monitors)	LIU-PSB 6	P. Odier (BE-BI)	01-Nov-2011	01-Jan-2014

ID	Description	WBS	Holder	Start Date	Finish Date
91546	Fast BLMs at injection DUMP	LIU-PSB 6	C. Zamantzas (BE-BI)	01-May-2011	01-Jan-2014
MSP	Monitors and Acq system	64020		60,000 CHF	
MSP	Installation	64020		10,000 CHF	
DE	Ten Monitors and acq system			30	0 / 10 U
DE	Cables			30	0 / 100 %
DE	Installation			10	0 / 100 %

WORK IN PROGRESS



- Introduction
- Project Management
- **Anticipated Performance Goals**
- Planning
- Summary



Basic assumptions

- Beam parameters are given at injection in LHC: beam loss and blow-up inside the LHC are not accounted for.


- All necessary improvements are implemented in the injectors (Linac4, PSB to PS transfer at 2 GeV, coupled bunch instabilities suppressed, e-cloud suppressed, hardware upgraded...)

- Estimated beam degradation in the accelerator chain (based on observations in 2010):
 - ✓ PS: 5 % beam loss, 5 % transverse blow-up
 - ✓ SPS: 10 % beam loss, 5 % transverse blow-up.

- RF gymnastics being kept, imperfections are unchanged:
 - ✓ +-10 % fluctuation of all bunch parameters within a given PS bunch train.
 - ✓ Traces of ghost/satellite bunches.




Beam parameters at LHC injection [50 ns]





Beam parameters at LHC injection [25 ns]





- Introduction
- Project Management
- Anticipated Performance Goals
- **Planning**
- Summary



Comments

- ☞ **LIU performance goals in terms of beam characteristics at injection in the LHC have to meet the needs of HL-LHC and to be feasible... Subject of active interactions between HL-LHC and LIU teams (2nd joint «Brainstorming» session on January 24, 2012).**
- ☞ **MDs until the end of 2012 will help refine the knowledge and understanding of the injectors and check the potential of upgrades.**
- ☞ **End 2012/beginning 2013, the performance goals of the LIU project will be specified and the precise list of hardware modifications with their specifications will be issued.**



Planning

	Linac4	PS injector, PS and SPS	Beam characteristics at LHC injection
2011 - 2012	Continuation of construction...	<ul style="list-style-type: none"> • Beam studies § simulations • Investigation of RCS option • Hardware prototyping • Test of new beam gymnastics • Design § construction of equipment • TDR 	25 ns, $1.2 \cdot 10^{11}$ p/b, ~3 mm.mrad 50 ns, $1.7 \cdot 10^{11}$ p/b, ~2 mm.mrad
2013 – 2014 (Long Shutdown 1)	• Linac4 beam commissioning	<ul style="list-style-type: none"> • Modifications and installation of some prototypes in PSB, PS and SPS • Design § construction of equipment 	
2015 - 2017	• Progressive increase of Linac4 beam current	<ul style="list-style-type: none"> • Implementation of new PS beam gymnastics... • PSB modification and connection to Linac4 during extended winter shutdown • If/when Linac4 connected: progressive increase of PSB brightness with benefits for PS and SPS. • Equipment design § construction for PSB, PS and SPS • Beam studies 	<ul style="list-style-type: none"> • Possibly smaller emittance (25 ns) with new PS beam gymnastics... • Limited gain from Linac4 proper (pending PSB, PS and SPS hardware upgrades)
2018 (Long Shutdown 2)		<ul style="list-style-type: none"> • Extensive installations in PSB, PS and SPS • Hardware commissioning 	
2019 –2021		• Beam commissioning	After ~1 year of operation: beam characteristics for HL-LHC...



- Introduction
- Project Management
- Anticipated Performance Goals
- Planning
- **Summary**



Summary

- The goal of the LIU project is to make the LHC injector complex capable to reliably deliver the higher performance proton and ion beams required for High Luminosity in LHC until later than 2030.
- Performance for other users will at least be preserved and generally benefit (e.g. high intensity).
- More MDs will take place in 2012 to finalize the hardware modifications and their precise specifications.
- The implementation of hardware modifications will finish during LS2.

All equipment and service groups are concerned!



**THANK YOU
FOR YOUR ATTENTION!**





Reference



Why is today's beam better than nominal?



Simple! No more blow-up along the accelerators cascade...

- PSB:
 - Improved (achromatic) optics in the Linac2 to PSB transfer line since 2005 [http://khanke.home.cern.ch/khanke/papers/2006/ab_note_2006_001.pdf]
- PS:
 - Injection trajectories
 - Working point along the whole cycle
 - Transition
- PS to SPS:
 - Transverse matching with better optics in TT2-TT10

WARNING: NO MARGIN LEFT!