

7th "Trento" Workshop on Advanced Silicon Radiation Detectors (3D and P-type Technologies) Jožef Stefan Institute, Ljubljana, Slovenia February 29 – March 2, 2012

ATLAS Diamond Beam Monitor

Andrej Gorišek++ J. Stefan Institute, Ljubljana

Ljubljana, 29/2-2/3 2012

#University of Göttingen

- **#J.** Stefan Institute, Ljubljana
- **#**New Mexico
- **#**Ohio State University
- **#**University of Toronto









- **#**DBM existence closely connected to two projects:
- #ATLAS Insertable B-Layer (IBL)
 - additional layer of pixel detector installed on shrunk beam-pipe
- New Services Quarter Panel (nSQP)
 - # project to move the opto-links of current pixel detector outside of the inner detector volume for easier access

7th TW, 29/2-2/3, 2012

ATLAS Insertable B-Layer (IBL)

- **#**Current pixel detector
 - # 3 layers
 - **■** 10¹⁵ n/cm² benchmark
 - **±** 10³⁴ cm⁻²s⁻¹ instantaneous luminosity
 - **#** Inner B-layer planned replaceable


#Facts

- **\blacksquare** No hope replacing a layer in ~1y
- **#** LHC plans n x10³⁴ cm⁻²s⁻¹ in 2019+


ATLAS DBM

#Solution

Shrink beam pipe **#** Add insertable B-layer












- In Originally IBL planned for installation in 2016 shutdown
- **#** Chamonix 2011 \rightarrow LHC splice refurbishing in 2013/14
- **#** ATLAS reaction Fast Track IBL
 - **#** Installation in 2013
 - **#** Stave loading Feb 2012, all modules on staves end 2012
 - # Twice the needed # of modules (& sensors) required by mid 2012
 - **#** Schedule just in time, **no contingency** whatsoever !
- # Sensor review July 2011: ¾/¼ planar/3D
 - **#** 3D the $\frac{1}{4}$ at large η
 - # 100 % planar as backup, full quantity produced & bonded
 - **#** Diamond out of the game since Jan 2011 \rightarrow DBM

nSQP



The ATLAS Pixel nSQP (new Services Quarter Panels)

- **#** reproducing the Pixel services
- add long-term reliability to the operation of the Pixel Detector
- The current on-detector optoboards replaced by new optoboards located at ID End-Plate
- Frobably installed on the Pixel detector during the next LHC shutdown (2013/14).



A. Gorišek 6

nSQP Design Changes PPO to PP1




- IBL qualification modules are single FE-I4 chip pixel modules
 - # 50 µm x 250 µm pixels, 336 x 80 on an FE-I4 chip (16.8 x 20 mm²)
- **#** A very promising tracking device
- #All (most) services & back-end are being developed for the IBL (and adopted by DBM)
- **#**Take a ride on this wave
 - **#** Build the ATLAS Diamond Beam Monitor (DBM)



- # Bunch-by-bunch luminosity monitor (aim < 1 % per BC per LB)</p>
 - Finer segmentation and larger acceptance than Beam Condition Monitor (currently main ATLAS luminosity monitor)
 - **#** saturation not a problem
 - # internal stability monitoring
- **#** Bunch-by-bunch beam spot monitor
 - Need three-module telescopes for tracking
 - # Can distinguish hits from beam halo tracks
 - Unbiased sample, acceptance extends

far along beam axis






Luminosity

- **#** monitor luminosity delivered to ATLAS for individual BCIDs
- **#** aim for % level accuracy in lumiblock (1-2 minutes)

Beam Spot

- unbiased (trigger) beam spot monitoring
- # aim for ~1cm accuracy per event
- **#** Background monitoring

topology of BG different than IP interactions



Track Trigger test-bed # possible test-bed for ideas (pattern reco., tracking,...)

 \leftarrow all need more input from simulation (rate, occupancy,...)



Design considerations


- # Baseline: four telescopes of 3 IBL modules per side → 24 total
- Avoid IBL insertion volume and ID acceptance (η>2.5)
 In front of BCM (η~4.2); limited overlap
- # Place in pixel support structure close to detector and beam pipe
- Only possible if nSQP project brings pixels out in 2013
- Back-up plan is being considered if nSQP project will not be realized

DBM – geometry



A. Gorišek 11


Part of pixel volume, but needs IBL-type services
e.g. 1000 V for detector bias
Services inventory being included in nSQP
nSQP sets installation date for DBM – July 2013
Alternative location = beginning of 2014



7th TW, 29/2-2/3, 2012

DBM - installation






7th TW, **29/2-2/3**, **2012**



DBM - installation





7th TW, **29/2-2/3, 2012**





- Apart from sensors, mechanics and read-out modifications DBM just adds 24 IBL single chip modules to the existing 448
 - **#** Services: two half-staves in addition to 2x14 of IBL
 - **#** Requires an additional ~5 % of most IBL components
- Resources partly available under detector-specific part of IBL MoU
- **#**DBM is now included as one of IBL work packages




- Baseline: 24 modules to be installed
- # Production model: aim for 30 good modules
- **#**Loss of 25 % during module assembly
 - **#** Need parts to assemble 40+5=45 modules
 - # 45 sensors, FE-I4's, flip-chippings, flexes etc.
 - **#** 5 for irradiation studies
 - Diamonds are reusable!!! ©
 - After testing with 1st version of FE-I4A diamond sensors will be re-used for final modules with FE-I4B




A. Gorišek 16

- **#** Two suppliers: DDL(E6) and II-VI
- **#** Order 10 detectors from DDL (done)
- # Order wafer from II-VI for June delivery (10-20 parts)
- **#** Thin 23 existing thick parts
- Have 3+1 parts (correct thickness) at IZM



First DBM modules

Four DBM modules built at IZM
21x18 mm² pCVD from DDL
FE-I4 ATLAS IBL pixel chip
336x80 = 26880 channels, 50x250 µm²
Largest ASIC/diamond flip chip assembly





7th TW, **29/2-2/3, 2012**

bump bonding

ATLAS DBM

A. Gorišek 17

Noise map of a DBM module






Source test

- **#** Modules tested with ⁹⁰Sr using USBPix
- The bump-bonds at edges are alive despite the worry of relatively large (~310⁻⁶K⁻¹) CTE mismatch between diamond and Si

Two plots from edges:



ATLAS DBM



3000

2500


2000

1500


1000


DBM - test beam

- # 3 test-beam campaigns
 # Jul, Aug, Oct
- **#** FE-I4 tuning accomplished @ 500 e
 - **#** With 8ToT5ke
 - **#** Is probably ~1000 e because of offset












7th TW, **29/2-2/3, 2012**



- **#** ATLAS Pixel TB setup works for DBM
- **H** trigger rate @CERN ~400 Hz during spill \rightarrow 1M triggers in 3.5 4 hours
- # diamond TB schedule slightly more complex than Si, due to pumping
- # sample tuning more critical than for Si
 # much lower thresholds
 - much lower feedback current
- **#** we learned a lot:
 - # noise occupancy excessively high, most likely due to metallization
 - **#** no indication, that efficiency is unreasonably low
 - in-pixel TOT distribution unexpected, not yet understood (might be an artifact of the high noise occupancy)







7th TW, **29/2-2/3**, **2012**



#Defined interfaces with nSQP team

- **#**No showstoppers, agreed to work sharing
 - # Services routing done, **big thanks** to nSQP team
 - **#** DBM is treated as (half)stave 15 of IBL
- #Cooling loops (DBM needs to be thermally neutral)










DBM – telescope design















- Use identical hardware for Read out Driver (ROD) as IBL
- Reuse IBL-ROD firmware code as much as possible
 If possible add only additional blocks needed for DBM functionality – in form of "add-on"s






DBM - readout/triggers

- IN Normal IBL-like readout at ATLAS wide level-1 trigger signals
- In addition fill the bandwidth with pseudo-random triggers (monitor luminosity and beam-spot reconstruction)
- Prioritizing mechanism for ATLAS L1 triggers over pseudo-random triggers
- Possibility to use hit-bus information from FE-I4






A. Gorišek 25






A. Gorišek 26

Simulation studies underway



Decided to focus on z of vertex, momentum resolution bad anyway \rightarrow turn precise pixel side in r





#DBM picking up momentum

- **#**DBM integration into IBL and nSQP well under way
- #Components being procured
- Number of modules produced and exercised











DBM – sensor specifications








DBM – electrical services





7th TW, 29/2-2/3, 2012

ATLAS DBM

A. Gorišek 30



